

COINS AND THEIR CITIES

COINS AND THEIR CITIES

Architecture on the ancient coins of Greece, Rome,
and Palestine

by

MARTIN JESSOP PRICE

and

BLUMA L. TRELL

V. C. Vecchi and Sons,
23 Great Smith Street,
London SW1

Wayne State University Press,
Detroit,
Michigan 48202

1977

ACKNOWLEDGEMENTS

Most of the coins were photographed by M. Price. A few, from the British Museum, were the work of Ray Gardner; those from New York were by Toni Di Biase; those from Athens by J. Kroll; and those from Vienna are courtesy of G. Dembski. Acknowledgements for other photographs are noted in the text.

To the following we are indebted for practical help and encouragement:


Maria Cruz Perez Acorta - A. Adams - Howard L. Adelson - Ekrem Akurgal - Yucel Akyurek - American Council of
 Learned Societies - C.H. Ancombe - Marlon M. Archibald - Vahit Armanan - Ceuziye Artuk - Ibrahim Artuk
 Bernard Ashmole - M. Avi-Yonah - K. Ayling - Jean Babelon - Roger S. Bagnall - Donald M. Bailey - Anton Bammer -
 Richard D. Barnett - P. Bastien - Gabriella Battaglia - Alfred R. Bellinger - L. Belova - Rose Belsky - Seth Benardete
 Anna Benjamin - Adolf Berger - Peter Berghaus - Elle J. Bickerman - Margarete Bleber - Albert Billheimer - Ann
 Birchall - Sylvia Bird - George Blake - Harry Bobar - Phyllis Bray Bobar - Larissa Bonfante - Annelmarie Bonling -
 Lore Borner - E. Bosch - Bernard V. Bothmer - Aigle Bowlin - Jean Bram - Richard Bredan - Otto Brendel -
 Franklin Brill - Blanche R. Brown - Donald F. Brown - Mary Kathleen Brown - Milton Brown - Guido Bruck -
 Theodore V. Bultrey Jr. - H. Buttmann - Herbert A. Cahn - Francis D. Campbell, Jr. - Marie Canton - Vincenzo
 Cappelletti - Jennifer J. Carver - H. Carter - Robert C. Carver - Peter Clay - Judith L. Casson - Iomene Casson - S.A. Castle - Betty
 Chagari - K. M. Chale - M. Chapoutot-Remadi - Peter Clay - Robert J. Clements - William C. Conforti - George S. Coran -
 J. Comstock - Brian F. Cook - Walter W.S. Cook - H.S.A. Copinger - Peter E. Corbett - Persy Corotis - Eliana
 Covachik - J.E. Cribb - Paul E. Culley - Raoul Curjel - Stephen Daltz - Ellen Davis - Gunter Dembski - Sylvie de
 Roquefeuil - Michael DiBaise - Mervin R. Dilts - R.H.M. Dolley - Necati Dolunay - Françoise Dumas - Charles W.
 Dunmore - Jean Duplessy - Elisabeth Dusenbery - John Dusenbery - Leslie A. Elam - Ellen Epstein - Halek Ergulec -
 Kenan T. Erim - E. Exlieben - Joan M. Fagiller - Beatrice Farwell - Otto Feld - David H. Filipek - M.I. Finley - Nezhil
 Firilli - Joan Fisher - Louis Foucher - Peter F. Franke - Ray Gardner - Georg Gaster - Theodor H. Gaster - Theodore
 Gerassimov - Jean-Baptiste Giarl - J. Frank Gilliam - Einar Gjerstad - Theresa Goell - Tuncay Goynu - Bernard
 Goldman - Norma Goldman - Cyrus H. Gordon - Isabel S. Gordon - Ralph Gordon - Clairee Grandjouan - Michael
 Grant - Beatrice Green - Tamara Green - Philip Grierson - Konrad Gries - Henry Grunthal - Hans G. Guterbock -
 Tony Hackens - George M.A. Hanfmann - Jacob Hammer - Susan Handler - William Owen Hassell - Walter Havernick -
 Denys E.L. Haynes - Sybil Haynes - Richard M. Haywood - Rex Heaton-Scotts - Fritz M. Heichelheim - Adelheid
 Helmann - Charles A. Hersh - Ernest L. Hettlich - R.A. Higgins - Abraham Hiltz - Eduard Holzmaier - L. Hooley - K.A.
 Howes - Harald Ingholt - H.W. Janson - Joseph Jaquiott - G. Kenneth Jenkins - Nina Jidejian - Jotham Johnson - F.
 Elmore Jones - Hans Jucker Leo Kadman - Baruch Kanael - Balogs Kapossy - Vassos Karageorghis - Phyllis Katz -
 Ramon Katzoff - Jean Keltch - John P.C. Kent - J. Alexander Kerns - Arle Kinder - Fred S. Kleiner - Ernst W.
 Klimowsky - Bernard Koch - Guenter H. Kocke - Marie Kozakiewicz - Dya Kozaman - Colin M. Kraay - Aleksandra
 Krazyzanskaya - Casper J. Kraemer, Jr. - John H. Kroll - George L. Kustas - Samuel Kuthmann - H. Kwak -
 Lake - Paul Lampi - Robert L. Lamm - Karl Lehmann - Phyllis Leifer - Samuel Lieberman - Georges Le Rider -
 Katherine Liner - Kenneth Linser - Elaine Loeffler - Pamela Long - Stanislaw Lorentz - Iris Love - Nicholas M.
 Lowick - Denit Lowry - Heath W. Lowry - David W. Macdowall - James R. McCredie - Raymond E. Main - Monique
 Mainjonet - Lawrence J. Majewski - Rose Mangini - Joan S. Martin - Philip Mayerson - R. Medden - Gloria S. Merker -
 Erwin Merker - Y. Meshorer - David M. Metcalf - William E. Metcalf - Henri Metzger - Maria Angeles Mezquirliz -
 Melanie Mihalnik - George C. Miles - Helen Mitchell Brown - David Gordon Mitten - Otto Morkholm - Sawyer McI.
 Mosser - Wolfgang Mueller - Oscar White Muscarella - Ernest Nash - Paul M.F. Naster - Rudolf Naumann - L.
 Nemeskal - Edward T. Newell - New York University Graduate School of Arts & Science Research Fund - Helene
 Nicolet - Sidney P. Noe - Emanuela Nohejlova-Pratova - Geoffrey H. North - Edward L. Ochsenchiager - Manco
 Oeconomidou - Nekirman Olcay - Saadet Onat-Taner - David R. Owen - Francis Paas - Gaetano Panazza - Erwin
 Panofsky - Klaus Parlasca - Andre Parrot - Efrim Pegan - Francis E. Peters - Charles Picard - Anna Pinka - Hugh
 Plommer - A. Poljakov - J. Graham Pollard - Enrica Pozzi - S.H. Prescott - James B. Pritchard - U. Pschlow - Zelik
 Rahikic - Franklin Ray - Gisela M.A. Richter - Anne S. Robertson - Jerry M. Robinson - Elisabeth Rohde - Claire
 Rosen - Edward Rosen - Lucy F. Sanlder - Nada Saportli - Serge Saueron - Gert Schiff - A. Arthur Schiller - Ursula
 Schoenheim - Alan Schulman - Sabine Schultz - H.D. Schultz - Willy Schwabacher - Nora E. Scott - Henri Seyrig
 Shew - Shaw - Teresa Shatz - Barbara Shatz - Stephen Shatz - Sholem Shatz - William A. Shatz - Jarmila
 Stepkova - Donald F. Strong - Meriwede Stuart - Arthur Suhli - Matej T. Tichauer - Richard G. Summers - J. G.
 Sutherland - George F. Taylor - Abdegeilf Temimil - Raci Temimil - Margaret Thompson - Mary Lee Thompson -
 Ibrahim Tozen - Joseph B. Trapp - Franz Unterkirliche - Edibe Uzunoglu - Cornelius C. Vermeule III - Irene
 Vouroucha-Christodouloupolous - Hans von Aulock - Peter von Blanckenhagen - Paul von Khurm - Nancy M. Waggoner
 - Charles Walker - J.B. Ward-Parkins - Hans Weber - Giady D. Weinberg - Sank Weinberg - Bartlett Wells - C. Bradford
 Welles - Edna Williamson - Jorkanka Youroukova - Jacques Yvon - Fritz Zink - A.N. Zadokcs-Jitta

To the two M's

ISBN 0—8143—1586—0.

© 1977 Martin Price and Bluma Trell

Printed in England by the Friary Press Ltd., Dorchester and London



CONTENTS


Page	11	Preface
	15	On the importance of coins for the history of ancient architecture
	53	Early architectural types
	58	Rome : The Colosseum — The Capitolium — The Curia
	75	Athens
	79	Corinth
	87	Delphi
	91	Amaseia
	95	Neocaesarea: The Sanctuary of Ma
	99	Nicaea
	107	Troy : The Temple of Athena
	109	Cyzicus
	117	Parium : The Tomb/Altar/Shrine
	122	Pergamum : The Altar of Zeus
	127	Ephesus : The Temple of Artemis
	133	Samos : The Naiskos of the Temple of Hera
	137	Sardis
	143	Selge : The Prehellenic Sanctuary
	147	Paphos : The Sanctuary of Aphrodite
	151	Byblos : The Sanctuary of Aphrodite
	155	Sidon : The Temple of Europa/Astarte
	159	Baalbek — Heliopolis
	167	Emisa : The Temple of Elagabal
	173	Neapolis, Samaria
	177	Jerusalem : The Temple of the Jews
	181	Alexandria : The Pharos — The Sanctuary of Serapis — The Nilometer
	189	Various buildings arranged by type
	229	Bibliography
	239	Abbreviations
	241	The architectural coin types of the ancient world: A list
	289	Index


LIST OF COLOUR PLATES

Page 13	Fig. 277	Sidon: The Sanctuary of Astarte/Europa
	Fig. 285	Capitolias: Gateway to the Sanctuary of Zeus.
Page 14	Fig. 26	Nicopolis ad Istrum : City gate.
	Fig. 71	Neocaesarea: Portico.
	Fig. 86	Augusta Traiana: Gateway.
	Fig. 182	Nicaea: Gate.
Page 31	Fig. 23	Laodicea: Roman Forum.
Page 32	Fig. 5	Odessus: Temple of Frotuna.
	Fig. 283	Tripolis: Temple of Zeus Hagios.
	Fig. 326	Smyrna: Octastyle temple.
	Fig. 327	Pergamum: Temple of Asclepius.
Page 49	Fig. 70	Nicopolis ad Istrum: Nymphaeum.
	Fig. 169	Neocaesarea: Gate.
	Fig. 244	Sardis: Altar of Zeus Lydios.
	Fig. 328	Sardis: Two neocorate temples.
Page 50	Fig. 57	Caesarea Germanica: View of the Harbour.
	Fig. 81	Antioch: Bridge over the Maeander river.
	Fig. 82	Anazarbus: Aqueduct.
Page 67	Fig. 110	Rome: The Colosseum.
Page 68	Fig. 130	Athens: The Acropolis.
	Fig. 133	Athens: The Theatre of Dionysus.
Page 101	Fig. 24	Bizya: View of the city.
	Fig. 159	Amaseia: View of the city.
Page 102	Fig. 49	Prusa: Sacrifice before a round shrine.
	Fig. 201	Cyzicus: The Sanctuary of Demeter.
	Fig. 329	Tyre: Caryatid shrine.
	Fig. 330	Zela: Portico.
Page 119	Fig. 217	Pergamum: The Altar of Zeus.
Page 120	Fig. 32	Eumeneia: The Temple of Artemis Ephesia.
	Fig. 221	Ephesus: The Temple of Artemis.
Page 153	Fig. 271	Byblos: The Sanctuary of Aphrodite.
Page 154	Fig. 252	Selge: The Sanctuary of Zeus and Heracles.
	Fig. 266	Cyprus: The Sanctuary of Aphrodite Paphia.
Page 171	Fig. 282	Baalbek: The Sanctuary of Mercury.
	Fig. 284	Baalbek: Portico to the Sanctuary of Jupiter.
	Fig. 290	Baalbek: The Temple of Jupiter.
Page 172	Fig. 56	Pella: View of the city.
	Fig. 302	Neapolis: Mount Gerizim.

MAPS

Page 9	Cities of the Eastern Roman Empire
Pages 58-9	The City of Rome





PREFACE

Ancient coins illustrate more than a thousand different buildings most of which are now lost without trace. We tend to forget that a line of foundation stones is all that remains of the human effort of planning and labour which goes into the erection of an architectural monument; and it is therefore salutary to begin this study by comparing extracts from letters sent by a provincial governor to the emperor at Rome, dealing with the construction of just such buildings as appear on the coins. The letters come from the interesting correspondence of Pliny the Younger, while he was governor of the province of Bithynia and Pontus in Asia Minor, about A.D. 110, and they show the important part that such large building projects played in the day to day life of the Roman governors; and they show equally the age-old incompetence and self-seeking of local administrators.

Pliny to the Emperor Trajan (Book X, letter 37):

"Sire, the people of Nicomedeia have spent 3,318,000 sesterii on an aqueduct which they abandoned before it was completed, and it has now been demolished. They then voted another 200,000 sesterii towards another aqueduct; but this too has been abandoned; and so even after such large amounts have been squandered to no effect, there is still need for a great outlay if they are to have a water supply...."

Trajan to Pliny (Book X, 38):

"You must make sure that the citizens of Nicomedeia have a water supply; I am sure that you will apply yourself diligently to providing for what has to be done. But equally you should set up an enquiry to find who is responsible for such waste of public funds to date, in case certain individuals are profiting from starting and abandoning aqueducts. Let me know the findings of the enquiry."

Pliny to the Emperor Trajan (Book X, 39):

"Sire, the theatre at Nicaea, although still unfinished, is now well advanced; but I am told that the cost has been ten million sesterii (I have not been able to examine the accounts), and I am afraid that this has been wasted. The building is sinking, and cracks have appeared, either because the subsoil is too soft, or because the stone itself is too poor and friable....A number of additions have also been promised by private individuals, such as colonnades around the theatre and an arcade above the auditorium; and now all these are delayed until work can be completed on the main structure.

Also at Nicaea, the citizens have begun to rebuild the gymnasium which was destroyed by fire before my arrival; but they plan it on a much larger and more extensive scale than before, and have already spent a large sum. Yet there is a

danger that it may be to no avail, since it has been poorly and too openly planned.....

The citizens of Claudopolis are also excavating rather than building a huge bath complex in a natural hollow at the foot of a mountain...

I must therefore request you to send an architect to inspect both the theatre and the bath..."

Trajan to Pliny (Book X, 40):

"You are in the best position to make the decision about what must happen to the unfinished theatre at Nicaea. It will be sufficient for me to know your decision.... These Greeks are very lavish on their gymnasia, and perhaps the Nicaeans were too ambitious in their building scheme. They must be content with one which suits their needs. Again it is you who must decide on the future of the bath at Claudopolis, which you state in your letter to have been started on an unsuitable site. You can have no lack of architects. Every province has a number of skilled and experienced men; and you should not think that they can be sent out more quickly from Rome, when they usually come to us anyway from Greek lands."

Such were some of the building schemes with which Pliny had to deal during his governorship in Bithynia. The main gymnasium and a large theatre, possibly those of which Pliny was writing, are still to be seen at Nicaea. Yet the literary and archaeological evidence, although of paramount importance is in some ways more limited than that of the miniature buildings found on the coins, and it is to these that we must turn for a general view of many of the most important pieces of architecture in the Roman empire.

This book is mainly concerned with the coins of the provincial cities of the Roman empire which have never previously been collected in this way. The coins of Rome herself, on the other hand, are readily available for study in the general books on Rome listed in the bibliography; and we have therefore selected but a few examples to show their fine contribution to the study of the architecture of that city. We make no apology for this, since the number and variety of the provincial issues have never been recognized, whereas the coins of Rome, though much fewer in number, are better known.

Each building represented in the list at the back of this book could itself be the subject for a study with comparative archaeological and literary material. We have selected only a few cities to demonstrate how the coins may be studied, limiting ourselves to the problems of architectural details; but it will be clear that these in turn lead to questions of function and ritual which would require a separate study.

ancient coins are usually no longer extant, each variation becomes of the utmost importance. One artist will emphasize the general appearance of the facade of the building; another will put it in its natural setting, on top of a mountain or in a wooded grove; another will give details of the superstructure, or of the column capitals, or of the cult image. In each case the artist was concerned to identify for those who were to handle the coins, the particular building in the city depicted; and to achieve this, he was bound to use certain forms of shorthand. Only with the full recognition of commonly used 'conventions' can we compare the coins with such literary or archaeological information as may exist, and so build up a picture of any particular building.

In the second century A.D. Pausanias travelled throughout southern Greece and he has left us his famous descriptive itinerary, for which the coins make a poignant commentary. When he arrived in Arcadia, he visited the town of Cynaetha of which nothing now remains, and saw there among other things a stoa, sanctuary, and tree. The very stoa, sanctuary, and tree are depicted on the only known coin of the city. At neighbouring Bura, in Achaea, he also visited the oracle of Heracles, situated in the cave which may today contain the monastery of Mega Spilion; and this too is recorded on a coin, on the hillside below the town.



Fig. 6 AMASEIA, Pontus: Temple of Tyche with the facade removed to emphasize the cult image (Caracalla A.D. 209) BM.



Fig. 7 HERACLEA PONTICA, Bithynia: Temple of Roma with the facade opened to reveal the inner shrine (Philip I A.D. 244-249) BM.



Fig. 26



Fig. 71



Fig. 86



Fig. 182

Fig. 26 NICOPLIS AD ISTRUM: City gate with temple visible within, and above, a large public building. BM.

Fig. 71 NEOCAESAREA, Pontus : Portico with city goddess. BM.

Fig. 86 AUGUSTA TRAIANA : Military gateway. Berlin

Fig. 182 NICAIA: Gate. BM.

ON THE IMPORTANCE OF COINS FOR THE HISTORY OF ANCIENT ARCHITECTURE

"Hundreds of thousands of coins... have revealed to us not only the external appearance of many ancient cities but also the main feature of every aspect of their life — their walls, streets, gates, and public and private buildings...."

M. Rostovtzeff

This is the first attempt to collect in one place the buildings which appear on ancient coins. T.L. Donaldson's pioneering *Architectura Numismatica*, the only other such work in this field, published in 1859 and reprinted in 1966, was written before scientific archaeology became an important discipline for the study of the ancient world. It gives little idea of the amazing variety and detail presented by the coins. With the increasing specialization of modern times, coins have become the province of the numismatist, whose interests, often inward looking, have tended to stray away from other disciplines such as epigraphy, sculpture, and architecture. On the other hand the archaeologist for his part has tended to ignore or misuse such evidence as is offered by the coins, so that text books on architecture are produced without even a reference to the coins. This book is dedicated to healing this breach, and to showing the contribution which can be made to our knowledge of ancient architecture by studying the contemporary views of buildings as they are found on the coins. A glance at the illustrations will show the enormous variety of buildings for the very existence of which the coins are now the only evidence. Even when a building has been excavated the coins are often the only evidence for the superstructure, the part most vulnerable to act of God and man.

In the past bronze coins have often been neglected. Their utilitarian function may not have been thought worthy of a place in the history of art: They become more worn, and they corrode more easily than coins of precious metals. Yet architectural types are usually found on bronzes, and they exist today in thousands of examples. Indeed most of the 800 different buildings found on Greek coins occur on bronze issues of the cities of the Roman empire. Such coins are not only overlooked by many collectors, but are normally published only in academic works. They are to be found scattered throughout a labyrinth of books, articles, and catalogues which would daunt all but the most courageous reader. But when, as in this book, a single theme is pursued, and salient information is extracted, the importance and fascination of the coins become at once apparent. Each coin die was hand-cut by an engraver; each engraver was an artist (even if sometimes a bad artist!); and each artist had a different view of the three-dimensional building which he was transferring to the two-dimensional plane of a miniature relief sculpture. Since the buildings illustrated on



Fig. 1 CYNÆTIA, Peloponnese: View of the main buildings in the city (Caracalla A.D. 198-211) Berlin.



Fig. 5 ODESSUS, Moesia: Temple of Fortuna (Gordian III A.D. 238-244) BM. See colour plate p. 32.



Fig. 2 BURA, Peloponnese: View of the city with the oracle of Heracles below (Geta A.D. 198-211) Athens.



Fig. 3 PERGAMUM, Asia: Temple of Zeus Philios and Trajan (Trajan A.D. 98-117) Paris.



Fig. 4 GYTHEION, Peloponnese: Temple of Asclepius (Septimius Severus A.D. 193-211) BM.

ancient coins are usually no longer extant, each variation becomes of the utmost importance. One artist will emphasize the general appearance of the facade of the building; another will put it in its natural setting, on top of a mountain or in a wooded grove; another will give details of the superstructure, or of the column capitals, or of the cult image. In each case the artist was concerned to identify for those who were to handle the coins, the particular building in the city depicted; and to achieve this, he was bound to use certain forms of shorthand. Only with the full recognition of commonly used 'conventions' can we compare the coins with such literary or archaeological information as may exist, and so build up a picture of any particular building.

In the second century A.D. Pausanias travelled throughout southern Greece and he has left us his famous descriptive itinerary, for which the coins make a poignant commentary. When he arrived in Arcadia, he visited the town of Cynaetha of which nothing now remains, and saw there among other things a stoa, sanctuary, and tree. The very stoa, sanctuary, and tree are depicted on the only known coin of the city. At neighbouring Bura, in Achaea, he also visited the oracle of Heracles, situated in the cave which may today contain the monastery of Mega Spilion; and this too is recorded on a coin, on the hillside below the town.



Fig. 6 AMASEIA, Pontus: Temple of Tyche with the facade removed to emphasize the cult image (Caracalla A.D. 209) BM.



Fig. 7 HERACLEA PONTICA, Bithynia: Temple of Roma with the facade opened to reveal the inner shrine (Philip I A.D. 244-249) BM.



*Fig. 8-9 SEBASTOPOLIS-HERACLEOPOLIS, Pontus:
Sanctuary of Heracles. Two projecting wings flank a courtyard
to which access is restricted by a prominent barrier.
8 (Caracalla A.D. 198-211) Paris.*

9 Detail. (Julia Domna A.D. 193-211) Berlin.

Artists' conventions

There are those who condemn the coins as stylized representations of buildings with little use in the study of architecture; but the illustrations of this book provide a sufficient reply. Carefully delineated architectural details should particularly be noticed, such as the sculptured drums at the base of the columns of the temple of Artemis at Ephesus, the parotids flanking the steps in front of the temple of Trajan at Pergamum, and the great stairway in front of the temple of Jupiter at Baalbek. All these can be checked against the existing remains of the buildings to witness to the accuracy of the impressions, however sketchy, given by the coins; and in the many cases where nothing now remains, such details, even on worn or badly preserved coins, as half fluted or spiral fluted columns, windows in the pediment, stairways, and colonnades around the sanctuary, may be all important in allowing an accurate reconstruction of the architecture. It should however be stressed that variations in detail at different times need not imply a change in the architecture of the actual building.

At the same time, the die-maker could show in a manner that would baffle the modern photographer, parts both of the interior and of the exterior of a building. It was not necessary for purposes of identification to show the exact number of columns on the facade of a temple; it sufficed merely to indicate that there was a columned portico. The columns could be reduced so that the engraver could place in the facade the cult image, which actually stood in the interior of the temple. Equally commonly, the space between the central columns was widened to accommodate the image which usually identifies the shrine with no possible ambiguity; and the artist achieves this identification in a way that would suggest the age-old custom of epiphany, a god appearing in person before his worshippers. On the other hand the careful artist would never show more than the actual number of columns; and so with a long series of coins, we can usually deduce how many columns a building had. On some coins the architrave of the facade was completely omitted by the die engraver, the better to show on the facade the cult image. Furthermore many coins show the architrave of the temple arched to present an architectural form known as an arcuated lintel. Although this is commonly found on coins of Syria and Anatolia, in the remains of actual buildings it is extremely rare. The one example on coins which can be paralleled with existing remains is the famous gate to the sanctuary of Jupiter at Baalbek. It seems therefore impossible that all the coins with arcuated lintel illustrate buildings with that actual architectural form — indeed sometimes the same building is shown with and without the arch. It may be supposed that the engraver was normally using this as a device to reflect the domed baldachino or arched shell-in-niche which covered the cult image within the temple. This could be brought to the facade for the same reason that the architrave was sometimes omitted — the better to show the cult image. Much more rarely three 'interior' arches are also brought out to the facade with the cult images to show that a triad of deities was worshipped, and that the cella was divided into three chapels. Three niches, sometimes abbreviated to one, appear on the 'stoa' of Sebastopolis, Pontus. Heracles, who alone is shown, was here worshipped in a sanctuary of most unusual form, divided into three separate parts. As a result of the



Fig. 10 CAESAREA PANIAS,
Syria: Sanctuary of Pan (Julia
Maesa A.D. 218–225) Berlin.



Fig. 11 CAESAREA PANIAS,
Syria: Grotto and sanctuary of
Pan (Elagabalus A.D. 218–222)
BM.



Fig. 12 CAESAREA PANIAS,
Syria: Grotto of Pan (Elagabalus
A.D. 218–222) Berlin.



Fig. 13 CYME, Asia: Aedicula of Artemis, the architrave
supported by Caryatids (Nerva A.D. 96–98) BM.



Fig. 14 CAESAREA AD LIBANUM, Syria: Aedicula of
Artemis, the arch supported by Caryatids (Elagabalus A.D.
218–222) Paris.



Fig. 15 HADRIANOPOLIS, Asia: Gate to an altar court
(Hadrian A.D. 117-138) Berlin



Fig. 16 ALEXANDRIA, Egypt:
Combined view of gate and altar
(Hadrian A.D. 117-138) Paris

different coin types of Caesarea Panias in Palestine, we can restore the sacred precinct ^{Fig. 10-12} of Pan. In one type the statue of the god appears in a circular courtyard, clearly a bird's eye view of his sanctuary; in another he appears in a grotto above the sacred temenos; and in the third, the grotto alone is shown so that Pan may be better seen within his mountain home.

While a baldachino or aedicula is often brought out to the facade of a temple, it also ¹³⁻¹⁴ appears alone to represent the whole building. The artist allows the essential part, the holy of holies, to stand for the whole, so that in some cases the aedicula may even be an abbreviated view of the temple building itself. The recognition that interior details were deliberately brought to the exterior has facilitated our interpretation of many monuments.

In some cases, as at Amaseia and at Emisa, an altar stands for the cult image, ¹⁶³ suggesting that the altar itself was the focal point of the worship and this in turn ³⁰¹ implies that it stood in an open altar court. Elsewhere, we must peer, as it were, through the facade of a gate to understand the arrangement of the court behind. The altar of the great court at Pergamum, which is known to have been open to the skies, is ²¹⁷ placed by the die-engraver between the columns of the monumental entrance. The gate to the court at Neocaesarea is shown with a variety of statues and sacred objects, ¹⁶⁵⁻ in addition to the altar, within the facade. Hadrianopolis offers an example similar to that ¹⁷² of Pergamum. The stepped altar, while it may have stood at a considerable distance ¹⁵ from the gate, is shown between the centre columns. Most unusual is the combination of gate and altar at Alexandria in which the flaming altar appears to form the top part ¹⁶ of a columned portico. In fact, the figure of Tyche stands between the columns to identify the cult of the sanctuary, and the architrave of the 'gate' forms the top of a near eastern 'horned' altar.



Fig. 17 APERLAE, Lycia: Gate to an altar court (Gordian III A.D. 238–244) Berlin.



Fig. 18 APERLAE, Lycia: Bird's eye view of the altar court (Gordian III A.D. 238–244) Berlin.



Fig. 18A Detail of fig. 18.



Fig. 19 PHILOMELIUM, Asia: Temple of Dionysus and hexagonal court (Otacilia Severa A.D. 244–249) Trell collection.



Fig. 20 CYME, Asia: The gymnasium (Gordian III A.D. 238–244) BM.



Fig. 21 CNOSSUS, Crete: The labyrinth (3rd Cent. B.C.) BM.



Fig. 22 ZEUGMA, Commagene: Sanctuary of Zeus on the Acropolis (Philip II A.D. 244–249) BM.

Perspective

17-18 At Aperlae in Lycia we find not only a facade with the altar replacing the cult
 image, but also another coin which gives a bird's eye view of the court to show the
 271 altar in the centre and a columned arcade around. Similarly at Byblos, the walls of the
 court have been opened to bring out the splendid altar surmounted by its sacred stone.
 Such use of perspective which makes part of the design almost a ground plan appears in
 19 many views of harbours both on Roman and Greek coins. At Philomelium the
 148 hexagonal court in which the temple stood is shown merely as a line. The agora at
 Corinth with the temple arranged at the central point and the gymnasium at Cyme are
 20 particularly good examples; and a 'ground plan' is the obvious way to depict the
 21 legendary labyrinth at Cnossus.

A different kind of bird's eye view in which the whole of the front is also depicted is
 even more impressive. At Zeugma, the temple of Zeus certainly stood at the top of the
 22 mountain, with a portico at the foot, much as on Mt. Gerizim in Syria; but the
 302 colonnades placed on the coins at either side of the mountain, may well represent the
 courtyard in which the temple actually stood. In this case the artist has combined a
 perspective view of temple, forecourt, mountain, and portico into a single design. More
 immediately intelligible are the Colosseum at Rome, which is so open to the skies that
 one can all but see the performance, and the forum at Laodicea where even the paving
 110 stones are visible.
 23

Views of whole cities are shown on some coins, where the most important piece of
 architecture of the city, as a bastion of the Roman empire, was the wall that protected
 24 it against the invading Dacians or Goths. At Bizya and Marcianopolis, for example, the
 25 interesting details foreshadow later Byzantine art. The Greek engravers included the
 exquisite decorations of gates and towers, and placed within the walls stoas, temples,
 and other buildings.

An extreme variation of this type of view is a convention which had its roots in
 earliest Mesopotamia. This was to place above what actually stood behind. Just as the
 mediaeval artist arranged his angels in ranks one above the other, the better to show
 them, so the die maker placed one monument above the other. Errors of interpretation
 277 have often been made as the result of not recognizing the convention. At Sidon, a
 temple building is shown supported by two colossal columns, which would be
 inconceivable as an actual architectural structure. The temple naturally stood behind
 the columns which thus formed the entrance to the forecourt. In the case of Nicopolis
 26 ad Istrum, we must assume that the stoa-like building that weighs so heavily on a city
 gate, actually stood behind it; and through the gate we can see the facade of another
 93 building beyond. It is worth noting that the early die engraver at Sidon, who showed a
 ship immediately in front of the walls, could not give as many details as the later
 artists. Engravers certainly had difficulties with such multiple planes, but they could be
 27 overcome. An examination of the coin of Apollonia in Caria shows that the hands of
 28 the deities actually extend in front of the columns, and at Docimeum, a horseman
 appears from behind a column. There are some further remarkable representations of
 buildings in three-quarter view which almost seem to anticipate Uccello.

Fig. 23 LAODICEA, Asia: The Roman Forum. A temple, probably of the imperial cult, stands at the head of the forum, and the emperor is seen bestowing honours on the leading citizens (Caracalla A.D. 211–217) Courtesy Museum of Fine Arts, Boston. See colour plate p. 31



Fig. 24 BIZYA, Thrace: View of the city (Philip I A.D. 244–249) P. Bastien collection. See colour plate p. 101



Fig. 25 MARCIANOPOLIS, Thrace: View of the city (Gordian III A.D. 238–244) Sofia.




Fig. 26 NICOPOLIS AD ISTRUM, Moesia: Detail showing city gate with temple visible within, and above, a large public building, probably a sanctuary (Septimius Severus A.D. 192–211) B.M. See colour plate p.49



Fig. 27 APOLLONIA SALBACE, Asia: Temple of Apollo (Gallienus A.D. 253–268) Paris



Fig. 28 DOCIMEUM, Asia: Heroon? (early 3rd cent. A.D.) Vienna

Topography

Trees added to the scenes with temples at many towns in Greece emphasize the fact that the temples were placed in sacred groves, and thus reflect Greco-Roman pastoral painting. We should distinguish between the purely topographical elements which underline the position of the building within the city, and sacred trees actually worshipped for themselves, as part of the cult ceremonies, which did not necessarily stand in a pastoral setting. The former, more often found on purely Greek coins, would include mountain scenes such as at Pautalia and Corinth; but trees as sacred objects beside an altar or within an enclosure are also found in many places.

On the other hand the engraver often depicts two or more buildings on a single coin, without any intention of suggesting a geographical relationship within the city. This is done particularly when the "neocorate" temples are depicted, temples dedicated to the imperial cult, or to an important cult shared by the whole province which earned for the city the coveted title "neocoros." Although the architecture of such little representations of two or more buildings is very schematic, every attempt is made to identify each building, sometimes with the name of the emperor worshipped in the pediment, and therefore the coins play an important role in the history of the city.



Fig. 29 PAUTALIA, Thrace: View of sacred buildings and a cave within the sanctuary of the mountain (Macrinus A.D. 217-218) Vienna.



Fig. 30 PERGAMUM, Asia: The neocorate temples to Augustus, Caracalla, and Trajan with the names inscribed in the pediments (Caracalla A.D. 211–217) ANS.



Fig. 31 SARDIS, Asia: The sanctuary of Aphrodite Paphia, probably a building within the city of Sardis (Hadrian A.D. 117–138) BM.



Fig. 32 EUMENEIA, Asia: The temple of Artemis Ephesia. Note the prominent sculptured bases of the columns, and the figures in the pediment. (Hadrian A.D. 117–138) BM. See colour plate p. 120



Fig. 33 ALEXANDRIA, Egypt: An arch with prominent sculptured figure in relief on one side, copied from a Roman coin of Nero (Trajan A.D. 103) Paris.



Fig. 34 TYRE, Phoenicia: The Phoenician Queen Dido supervising the building of Carthage (Gordian III 238-244) BM.



Fig. 35 AEGEAE, Cilicia: Cadmus, the brother of Europa, in front of the gate of Thebes where he later settled (Macrinus A.D. 217-218) Paris.



Fig. 36 ABYDUS, Asia: Leander swimming to Hero's tower at Sestos, leaving his clothes and weapons on the Asian shore of the Hellespont (Commodus c.A.D. 177) BM.



Fig. 38 MAURETANIA: Gate to a sanctuary with three Atlas Caryatids; above three horned altars decorated with figures (Juba I 60-46 B.C.) Paris



Fig. 37 ILICI, Spain: Temple with dedication on the architrave to Juno (Augustus 31 B.C.-A.D. 14) BM.



Fig. 39 CHALCIS, Euboea: Shrine of Oriental form with flat roof in which sacred baetyl (1st cent. A.D.) BM.



Fig. 23



Fig. 5



Fig. 326



Fig. 238



Fig. 327

Fig. 5 ODESSUS: Temple of Fortune. BM.

Fig. 326 SMYRNA: Octastyle temple with figures decorating the parotids (Domitian A.D. 81 – 98) Berlin.

Fig. 238 TRIPOLIS: Phoenicia: The temple of Zeus Hagios with gate. (Caracalla A.D. 212) BM.

Fig. 327 PERGAMUM: Temple of Asclepius (Commodus A.D. 175–177) BM.

If the apparent geographical relationship within the city is illusory, did the artist ever represent monuments that were located beyond the limits of the mint city? At Pergamum and Sardis, shrines of Paphian Aphrodite are shown identical with her shrine at Paphos in Cyprus. Does this mean that such shrines actually stood within the cities, or that in celebrating the cult on the coins the artists chose to depict her well-known shrine hundreds of miles away? Again, at Eumeneia, we find an exact copy of the great temple of Artemis at Ephesus. Could such a small city afford to build so extravagant a building, or was this simply a die engraver's reference to the cult itself? Silver cistophori issued by the provinces illustrate some local buildings, but at least two show buildings at Rome and not within the province — the temple of Mars Ultor and the temple of the Capitol; and a coin of Alexandria similarly copies a Roman coin type to illustrate the arch of Nero which actually stood at Rome. There are several other such exceptions, but as a general rule it is buildings within the city that are illustrated on local coins.

There are certain mythological scenes which include buildings historically long removed from the artists of the Roman world — Dido supervising the walls of Carthage, Cadmus in front of the walls of Thebes, Hero awaiting her Leander in a tower at Sestos. With these we may also link the temple of Jehovah at Jerusalem which appears on coins sixty years after its destruction by the Romans. Furthermore, a recent study by Konrad Kraft of imperial coins of Asia Minor has led to the surprising theory that many cities did not mint their own coins, and that they even borrowed types, of little relevance to the city, from a central "mint" often hundreds of miles away! Much more evidence, however, will be needed before his conclusions become acceptable, but as far as buildings are concerned, while we may admit that stylized representations could be the result of such a minting practice, there is generally such close attention to detail, and so many obvious attempts to identify the building, that we must assume that in such instances the coins usually depict an actual piece of architecture within the city.

Eastern influences

With few exceptions therefore the monuments on the coins must have been, in the main, buildings situated within the mint city, and they illustrate particularly the influence of oriental forms in the Greek and Roman world. In the West, local coinage was suppressed in the mid 1st century A.D. and so there is little to show of the great cities of Africa and Spain. Excavations in these areas, however, have revealed more about Phoenician architecture than excavations in Phoenicia itself. In Syria and Anatolia by contrast, our knowledge of ancient buildings derives less from excavation than it does from the coins which give us a fascinating picture of oriental architecture and show its influence in the West. The coins indicate the three part division of the temple cella, associated with the worship of a triad of deities. This is found in the Capitulum in Rome and in the temple of Aphrodite at Paphos, both with ancient traditions which, it is plausible to assume, had a common origin in the East. Spanish coins emphasize the sacred portal; North African coins have the oriental flat roof with horned altars, caryatids, and narrow stairways. Similarly oriental characteristics are found on coins attributed to Chalcis in Euboea, Greece, where the cult object is a



Fig. 40 TYRE, Phoenicia: Portable shrine fitted with carry bars at its base, a typically oriental style of building (Volsian A.D. 251–253). Paris

Fig. 17–8 sacred stone or baetyl and the roof is decorated with crenellations. The appearance of a typically Semitic altar court on the coins of Aperlae in Lycia is also significant for new discoveries in the area. Added to the recent excavation of a shrine divided into three sections and of another that was both a tomb and a sacred building, it is now clear that Lycia was in some significant ways closer to north Syria than to the Greek world.

Some of these architectural conventions have parallels in earliest Mesopotamia and Egypt, such as windows in the upper storey of temple facades, and processional shrines. One class of portable shrine found on coins, with flat roof and unmistakably Eastern decorations underlines the oriental origin of such a class of shrines although coins depict it as far west as Megara in Greece. At Antioch, Syria, only the carry bars at the base of the shrine identify it as a portable shrine to be carried in procession through the streets of the city.

Art historians interested in the post-Roman period will be surprised to know that the prototype of Islam's mihrab can be found on the coins of Damascus, the city where one of Islam's first mosques was constructed. The coins actually show the shell-in-arch of the mihrab, a motif which had a wide history in the Graeco-Roman world. On this coin Tyche appears to be seated on the steps of the temple with the river god at her feet; but it must be clear to all that the artist has combined the cult image in its niche with the facade of the temple. Similarly, windows in the pediments of ancient temples were adopted by the Syrian churches of the 5th and 6th centuries A.D. which in turn directly influenced Romanesque architecture. The towers that are found on the temples of Capitolas and Abila had their origin in the ancient East, and their mediaeval descendants in the towers that decorate Notre Dame and Canterbury cathedrals. Again, the delightful convention of a sacred person holding a shrine — whether an ancient deity or a Christian saint — existed in the ancient Near East and the mediaeval West. How true it is that in all art and culture everything derives from the East — omnia ex oriente.



Fig. 41 MEGARA, Greece: Statue of Demeter carried in a processional shrine on a horse-drawn waggon (Septimius Severus A.D. 193-211) ANS.



Fig. 42 ANTIOCH, Syria: Shrine of the goddess Tyche (Fortuna) fitted with carry-bars at its base (Trebonianus Gallus A.D. 251-253) Trell collection.



Fig. 43 DAMASCUS, Syria: Temple of Tyche with shell decoration in the pediment (Macrinus A.D. 217–218) Paris



Fig. 44 PERINTHUS, Thrace: Tyche holding the two neocate temples of the city (Alexander Severus A.D. 222–235) Paris

Fig. 47 EPIDAUROS, Peloponnese: Round shrine of Elpis, probably the tholos found in the excavations of the sanctuary of Asclepius (Antoninus Pius A.D. 138–161) Berlin

Round Buildings

- Fig. Round buildings, although they are rare on coins as well as in excavation sites, appear surprisingly often on coins of mainland Greek cities. The round buildings in the sacred sanctuary of Cyzicus were copies of the 'Arsinoeion' of Greek Samothrace; and no less than three round buildings appear on the coins of the cities of the Argolid 198–202 Argos, Troezen, and Epidauros. At Epidauros the round shrine of Elpis is almost certainly the famous round 'tholos' found in the excavations of the sanctuary, the purpose of which is much disputed. From Nicopolis in Epirus comes a domed 'heroon', a most unusual two storey building which cannot yet be identified with certainty. It is clear that the round building had no place in a truly 'oriental' sanctuary, although by 45–47 no means all examples are from mainland Greece. At Prusa in Bithynia there is a fine 19 illustration of such a round temple, and others may be discerned at Philomelium and 470 Side.



Fig. 45 ARGOS, Peloponnese: Round shrine of Athena on a podium (Antoninus Pius A.D. 238-161) BM.



Fig. 46 TROEZEN, Peloponnese: Round temple with colonnade and prominent closed doors (Commodus A.D. 177-192) Berlin.



47



Fig. 48 NICOPOLIS, Epirus: Detail of 'Heron'. The structure is of two stories with elaborate lantern (Faustina I c.A.D. 141) Paris.



Fig. 49 PRUSA AD OLYMPUM, Bithynia: Sacrifice at an altar in front of a round shrine on podium, with prominent conical roof (Geta A.D. 211-212) Paris. See colour plate p.102



Fig. 50 PERSIS: Sacred 'fire-temple' (3rd cent. B.C.) BM.



Fig. 51 PERSIS: Sacred Portal to the temple surmounted by three horned altars (3rd cent. B.C.) BM.



Fig. 52 ETENNA, Pisidia: Caduceus monument flanked by two cult statues (Septimius Severus A.D. 193-211) BM.



Fig. 53 EPHEBUS, Asia: Isis Pharia and a flaming beacon (Gordian III A.D. 238-244) Paris.

Tower-altar-shrines

Fig. A new class of ancient monument was only recently recognized when the so-called tower-altar was excavated in the sacred court of the temple complex at Baalbek. A similar altar can be seen on the coins of Persis which in turn has been equated with the famous fire "temple" near Persepolis. A more striking equation should be made between the horned altars on the flat roof of the shrine of Persis and the similar details on the coins of Juba I of Mauretania in Africa. Many other altar-shrines should be added to the list — the altars of Bostra, Parium, Selge, the sanctuary at Sagalassus, and the stele monument on the coins of Etenna, and even the flaming towers at Ephesus and Magnesia and the "pyres" of Roman coinage. The relationship between the tower-altar-shrine and a tomb shrine such as the Mausoleum at Halicarnassus is now the subject of fascinating speculation. The coins will play a part in that inquiry.



Fig. 54 CAESAREA, Cappadocia: Mount Argaeus placed on an altar within the temple (Commodus A.D. 177-192) Paris.



Fig. 55 NEAPOLIS, Syria: Mount Gerizim in sacred procession with the stone of Elagabal from Emisa on a carriage drawn by four horses (Elagabalus A.D. 218-222) B.M.



Fig. 56 PELLA, Syria: View of the city with the great temple terrace crowning the Acropolis (Commodus A.D. 177-192) Paris. See colour plate p. 172.

Sacred Mountain sanctuaries

Eastern cities worshipped many sacred objects, from the simple stone to the highest mountain, and we are shown such objects on the coins. The Bible gives testimony of very early sacred mountains and there is certainly no ambiguity about the testimony of the coins: Mt. Argaeus is placed on an altar between the columns of a temple; Mt. Gerizim is found in a procession with horses. In both cases the mountain itself is the cult object. On other coins, the mountain appears decorated with an altar or a temple at its top in addition to sacred ways and other sacred buildings — at Zela, Zeugma, Baalbek and many other cities. The coins clearly show that the “bamah” of the Old Testament was literally a “High Place” like the ziggurat, which as a mountain substitute was needed to make the temple sacred. Roman architectural forms are naturally combined with the eastern traditions. The substructure of the temples shown on the coins of Zeugma, Pella, and Neapolis is similar to structures actually found, for example, at Pergamum. In contrast to the eastern sacred mountains are those shown on coins of Greek cities, Athens, Corinth, Pautalia, etc. For the ancient Greek, the sacred monument was the temple building, and the mountain, as we have said above, was no more than a setting for the sanctuary. There is no suggestion that the mountain itself, as was the case in the East, was worshipped.



Fig. 57 CAESAREA GERMANICA, Bithynia: View of the harbour (Pescennius Niger A.D. 193–194) Paris. See colour plate p. 50.



Fig. 58 Lead token, probably Egyptian: View of a harbour entrance (mid. 2nd. cent. A.D.) Courtesy of Municipal Museum of Ancient Art, Haifa.

Harbours and Lighthouses

Fig. Long before underwater archaeology became a popular discipline, harbours and lighthouses were known from the coins. In some cases, harbours are engraved in bird's eye view, with indications wharves and installations. It is interesting to find that in many examples a temple stands at the end of the jetty; actual temples have been found as part of harbour installations. An exceptional view on a lead token shows a harbour entrance seen from within the bay, flanked by towers similar to those at the end of a modern breakwater. Harbour buildings as well as ships are shown in several instances with most interesting details at Aegina, and at Patras. The most unusual is the construction, the upper part of which represents the gate to the city at Vienne, which seems to stand on the ship's deck but which actually stood on the shore behind.

The Pharos of Alexandria gave its form and name to later 'light-houses', and on the coins of Corinth, Heracleia, Berytus, and Laodiceia, the characteristic receding stories are shown. In some cases, however, unless a ship is present in the design, it is not possible to distinguish a lighthouse from a simple tower. At Aegeae in Cilicia, for example, the lighthouse is such a tower of masonry blocks. To declare that the building on coins of Panormus cannot be a lighthouse because it has no openings, is to misinterpret the evidence. Indeed the function of such buildings is not beyond dispute, as discussed below in connection with the Pharos of Alexandria. It is important to note that at Berytus and Aegeae guards stood on the tower as the ships passed.



Fig. 59 AEGINA, Greece: View of the harbour with steps leading through the colonnades on the shore (Julia Domna c.A.D. 200-210) Berlin.



Fig. 60 PATRAS, Peloponnese: View of the harbour from the sea, the city and temples behind (Commodus A.D. 177-192) BM.



Fig. 61 PATRAS, Peloponnese: View across the harbour from the jetty (Geta A.D. 198-211) Berlin.



Fig. 62 VIENNE, Gaul: Harbour buildings and city gate beyond the prow of a ship (Augustus 31 B.C. - A.D. 14) BM.



Fig. 63 HERACLEA PONTICA, Bithynia: Lighthouse in three receding stories, with the second story hexagonal, and the top story round (Gallienus A.D. 253–268) Oxford.



Fig. 64 BERYTUS, Phoenicia: Galley rowing past the lighthouse on which a guard is posted (Septimius Severus and Caracalla A.D. 198–211) Paris.



Fig. 67 PANORMUS, Sicily: Tower or lighthouse (early 1st cent. A.D.) BM.



Fig. 65 LAODICEA, Syria: Lighthouse reached by a flight of steps; two stories surmounted by a statue (mid. 2nd cent. A.D.) BM.



Fig. 66 AEGEAE, Cilicia: Galley sailing past the lighthouse, a single crenellated tower (Trajan Decius A.D. 249–251) BM.



Fig. 68 ROME: The nymphaeum (Alexander Severus A.D. 222–235) BM.



Fig. 69 HADRIANOPOLIS, Thrace: The decorated facade of the nymphaeum (Septimius Severus A.D. 193–211) Paris.



Fig. 70 NICOPOLIS AD ISTRUM, Moesia: The nymphaeum (Septimius Severus A.D. 193–211) Berlin. See colour plate p. 49.



Fig. 71 NEOCAESAREA, Pontus: Elaborate portico, with the city goddess in the gateway (Alexander Severus A.D. 222–235) BM See colour plate p. 14



Fig. 72 PELLA, Syria: Nymphaeum (Elagabalus 218–222) Paris.



Fig. 73 AKE-PTOLEMAIS, Phoenicia: Nymphaeum with pavement in front (Elagabalus A.D. 218–222) Courtesy of Municipal Museum of Ancient Art, Haifa.

Fountains

- Fig. The nymphaeum, a temple of decorative type dedicated to the nymphs often including a watering place, was not found, as far as we know, in every city. Comparatively few examples are known and of many of these little or nothing remains. Five coin buildings have been termed monumental nymphaea, at Rome, Hadrianopolis, 68–72 Nicopolis, Neocaesarea, and, in Syria, Pella. The last, which is so inscribed, can be identified with certainty, but the building at Neocaesarea resembles a gate more than a fountain and certainly does not have the spouts at the base to indicate the nature of 73 the monument. Another coin building, however, of Ptolemais in Phoenicia, although published as a harbour, appears to have such spouts as well as a court in front. Smaller fountain houses and free-standing fountains are also found on coins. Particularly 74 striking is the one at Patras with water pouring down a series of catchment basins, and 75 that found at Troezen where the water cascades from a lion's mouth. Others equally 112, 76 interesting are found at Rome, the Meta Sudans and its copies in Greek cities, and at 139, 77 Corinth, the fountain house of Peirene. At Alexandria, Heracles is shown using a fountain with gushing water to clean out the Augean stables.



Fig. 74 PATRAS, Peloponnese: Fountain with water cascading from lion head spouts. The statue is that of Heracles (Domitian A.D. 81–96) BM.



Fig. 75 TROEZEN, Peloponnese: The 'fountain of Heracles': water pours from the lion's mouth into an elaborate basin (Septimius Severus A.D. 193–211) Berlin.



Fig. 76 NICOPOLIS, Epirus: The fountain of a 'Meta Sudans' type, possibly a copy of that at Rome (Hadrian A.D. 117–138) Berlin.



Fig. 77 ALEXANDRIA, Egypt: Heracles at a fountain (Antoninus Pius A.D. 138–161) Berlin.



Fig. 78 DORYLAEUM, Asia: Aqueduct above reclining river god (Alexander Severus A.D. 222–235) BM.



Fig. 79 ROME: The Aqueduct of Trajan with the river Tiber reclining below (Trajan A.D. 104–111) BM.



Fig. 80 BUTHROTUM, Epirus: Aqueduct: A rank of huge piers supporting arches above (Nero A.D. 54–68) BM.



Fig. 81 ANAZARBUS, Cilicia: Aqueduct with swimming river god below; the upper structure indicates the presence of a sluice gate or settlement tank (Alexander Severus A.D. 222–235) BM. See colour plate p.50.

Aqueducts and Bridges

By one of the strangest literary quirks in history we know more about aqueducts ^{Fig.} than about any other ancient monument; for the authority Frontinus, dull as he is, has left us the fullest possible details about the most utilitarian building of the ancient world. In the Greek world, only three aqueducts appear on coins. At Dorylaeum, the ⁷⁸ representation is identical to that of the Aqua Traiana on Roman coins, and at ⁷⁹ Buthrotum, the building has normally been regarded as a bridge. The former almost ⁸⁰ certainly commemorates the erection of an aqueduct in the city; the latter, which lacks the normal characteristics of a bridge, may also do so. The most impressive is that at Anazarbus which can be directly related to the ruins of an aqueduct still standing at the ⁸¹ site of the city. The coin shows the bridge-like structure with central tower which may represent a sluice gate, and the relevance to water is provided by the presence, below, of a river god. The examples of bridges at Antioch and Mopsus, and on Roman coins, ⁸²⁻⁸⁴ emphasize that great arches usually dominated the end of the bridge. Very few such arches are extant. On a series of Roman denarii celebrating Augustus' repairs of the roads in Italy, bridges are shown with arches at both ends and even in the middle.

Arches and gates

Several triumphal arches and gates have survived; but for their appearance in ancient times one must again look to the coins. They tell us, as we know from the cuttings in the stones of the preserved structures, that the arch served as a support for an elaborate ⁸⁵⁻⁸⁷ quadriga or other piece of statuary. Many arches, such as the arch of Nero at Rome, are types known only from coins. A provincial issue from Callatis indicates, like the arch ⁸⁸ of Nero, that sometimes a single heroic and spectacular figure in relief decorated one ¹⁰⁷ side of the arch or gate. No such decoration is otherwise known. It is interesting that as early as the 1st century A.D., coins of the eastern provinces show arches with three gateways. Such arches are not found that early at Rome. The only extant example of similar antiquity is in Gaul. The windows and pediment above the arches of an Alexandrian coin are certainly an inheritance from local religious architecture. ⁸⁹

It will already have become evident that architectural coin types do not at a stroke solve all problems connected with the buildings they depict. As with any other form of evidence, they must be used with care. Where design is extremely complicated or the building of an unusual form, we can only point to the coins as problems which later research or excavations may solve. They do, however, provide a remarkable contemporary guide to the architecture of the Graeco-Roman world. The coins with all their varieties remain as fascinating vignettes for the map of the Roman empire, similar to the vignettes of the Peutinger table, but with far greater reliability and detail. We can determine from the coins details of hundreds of buildings which have been lost beyond hope of recovery by the spade of the archaeologist.



Fig. 82 *ANTIOCH AD MAEANDRUM*, Asia: Bridge over the Maeander river (Gallienus A.D. 253–268) BM. See colour plate p. 50.



Fig. 83 *MOPSUS*, Cilicia: Bridge over the river Pyramus (Valerian A.D. 253–258) BM.



Fig. 84 *ROME*: The Aelian bridge over the Tiber (Trajan A.D. 104–111) BM.



Fig. 70



Fig. 169



Fig. 244



Fig. 328

Fig. 70 NICOPOLIS AD ISTRUM: The nymphaeum. Berlin

Fig. 169 NEOCAESAREA: The gate to the sanctuary. Berlin

Fig. 244 SARDIS: The great altar of Zeus Lydios. Paris

Fig. 328 SARDIS: The two neocorate temples (Septimius Severus A.D. 193-211) Paris.



Fig. 57



Fig. 82



Fig. 81

Fig. 57 CAESAREA GERMANICA: View of the harbour. Paris.

Fig. 82 ANTIOCH AD MAIANDRUM: Bridge. BM.

Fig. 81 ANAZARBUS: Aqueduct. BM.



Fig. 85 MARCIANOPOLIS, Moesia: Triumphal arch surmounted by four figures on pedestals (Macrinus and Diadumenian A.D. 217–218). Berlin.



Fig. 86 *AUGUSTA TRAIANA, Thrace: Military gateway to the city with three towers, one placed centrally over the door (Caracalla A.D. 211–217) Berlin. See colour plate p. 14*



Fig. 87 *ANCHIALUS, Thrace: City gate with two towers; above, a 'warrior', and beyond a temple facade (Septimius Severus A.D. 193–211) Berlin.*



Fig. 88 *CALLATIS, Moesia: City gate with male statue on the right hand tower (Geta A.D. 198–211) Berlin.*



Fig. 89 *ALEXANDRIA, Egypt: Gate or triumphal arch. The decorative elements include windows, Doric entablature and pediment (Trajan A.D. 111) BM.*

EARLY ARCHITECTURAL TYPES

With a few exceptions the coins to be discussed in detail in this book are of the Roman imperial period, issued either by Rome herself, or by the cities of the Roman empire around the Mediterranean basin. The earliest coins to show an awareness of architectural motifs, however, are rare silver pieces of the early 5th century B.C., struck by one of the islands of the Dodecanese, which use a palmette, possibly an antefix from a tiled roof, as a coin type. Later in the same century, we find fountain houses within the sanctuary of a local goddess at Himera; with charming and natural perspective a Silenus wades knee deep in the basin below the lion head spout. The little Silenus can be compared to the long necked bird which sits upon the surface of a fountain pool of a later coin of Terina. It is surprising that of all the religious and secular buildings of a city, fountains should first have been chosen; but they can be paralleled on many Greek vases and reliefs to show their importance for the peoples of the ancient world.

A 4th century B.C. coin of Sidon in Phoenicia represents the walls of the city with a galley drawn up on the slipway in front. The close attention to detail, both in the ship and in the crenellations of the towers, shows careful observation of the original scene. In a slightly later view of a city on the coins of Tarsus, we can see a much less realistic treatment, more symbolic of the power of the city.

Two temple-shrines, also of the 4th century B.C., represent the first purely religious buildings to be illustrated on coins. At Hierapolis Bambyce in Syria, the god is shown in a vaulted shrine, the columns of which have marked Ionic capitals, a Greek detail, which presumably gives a vague outline of the actual building. In spite of the Greek influence, the oriental tradition maintains a flat roof on the shrine. At Tarsus, greater detail is paid to the shrine of the god Anu, in which the local satrap Datames is shown worshipping the cult image. The shrine is flat roofed as at Hierapolis Bambyce and the edge of the roof itself is decorated with palmette antefixes such as have been found on many ancient sites and can be seen on seals and other artefacts of more than a thousand years before. At Tarsus, but at a later date, we have a shrine of the god Sandan. The deity stands on the back of a horned beast, in the typical pose of an eastern god, familiar today from Hittite sculptures. On either side of him are conic baetyls, sacred stones, and the group stands on a base decorated with garlands. A pyramidal structure, or canopy, supports a lantern surmounted by an eagle. Without doubt this is the cult image of the great god of Tarsus, as he would have been seen in his sanctuary.

Several altars are depicted on coins, larger, but not much more substantial than the small altar or puteal visible on the fountain type of Himera. While in the Roman period there are depicted altars which must have been of a monumental nature, in the Hellenistic world they are usually too insignificant to be classed as "architecture." At Parium, for example, the altar is shown to be little larger than the jug which stands beside it; yet the type probably symbolizes the great altar of Hermocreon, one of the largest and most famous altars of antiquity.



Fig. 90 *UNCERTAIN*, Caria or Dodecanese: Palmette of an architectural form (c. 490 B.C.) BM.



Fig. 91 *HIMERA*, Sicily: Silenus at a fountain within a sanctuary, in which the local nymph pours a libation (c. 450 B.C.) BM.



Fig. 92 *TERINA*, Italy: Winged Victory (Terina) seated at a fountain; a bird swims in the pool (c. 420 B.C.) BM.



Fig. 93 *SIDON*, Phoenicia: Galley drawn up on a slipway before the walls of the city; below, two lions (c. 390 B.C.) BM.



Fig. 94 TARSUS, Cilicia: Lion attacking a bull; below, the walls of the city (c. 340–335 B.C.) BM.



Fig. 95 HIERAPOLIS–BAMBYCE, Syria: Shrine of Hadad, with flattened roof (c. 335 B.C.) Oxford.



Fig. 96 TARSUS, Cilicia: Shrine of Anu, the flat roof decorated with antefixes (c. 375 B.C.) BM.



Fig. 97 TARSUS, Cilicia: Shrine of Sandan (Demetrius II of Syria 129–125 B.C.) BM.



Fig. 98 PARIUM, Asia: Flaming altar in front of which vase (c. 300 B.C.) BM.



Fig. 99 NORTH INDIA: Stupa of Buddha with colonnade of Hellenistic form (Sivadasa, probably late 1st cent. B.C.) BM.



Fig. 100 ROME: The Rostra decorated with ships' trophies, sometimes identified as a harbour installation (45 B.C.) BM.



Fig. 101 ROME: View of the walls and Acropolis at Eryx, Sicily (57 B.C.) BM.

From the far east of the Greek world we can illustrate a temple the existence of ^{Fig.} which on coins has never been recognized. This is a stupa, or shrine of Buddha. One coin, very stylized, shows that the sacred mountain of Buddha, associated with his birth, a simple man-made pile of rocks, was itself his earliest shrine. Another type, probably minted in the 1st century B.C., represents the shrine as a domed ⁹⁹ structure above a rectangular Hellenistic colonnade. The dome may have been of wood, since no real domes in stone are known until late in the Roman empire. But there is also a possibility that the coin represents a type of stupa, of which actual examples are known, a building cut deep into the interior of a hillside with rock cut columns under a rock cut stone dome. Later sculptured reliefs show the continuation of the type, but the coins themselves are the earliest representations.

Architectural types are sporadic in the Hellenistic world before 30 B.C., and it is the Romans, themselves great engineers and architects, who began to use such types regularly on their coinage. It is not true to say that they invented the use of architectural coin types but they certainly exploited it; and probably as a direct result of the appearance of buildings on the silver denarii of Rome, other cities saw the attraction of celebrating their own famous buildings in the same way. To illustrate Rome's contribution during the late Republican period, two denarii have been chosen for their particular interest. The coin of the moneyer Palicanus shows a curved set of ¹⁰⁰ arches with the prows of three ships set within them and with a magistrate's seat of office above. The coin could represent either the rostra (public platform) at Rome which Sulla had rebuilt in a curved form and which was decorated with ships' trophies, or less probably, some harbour installation showing the ships within their covered slipways. The second coin shows the city walls of the Sicilian town of Eryx with the ¹⁰¹ acropolis topped by the temple of Venus, famous in antiquity. This is reminiscent of our earlier coin of Sidon. The difference in time and technique, however, is emphasized ⁹³ not only by the attention to detail in the walling and gateway, but also by the definite perspective produced by the mountain and the temple on it. The city is identified by its name engraved on the scene.

We are now on the threshold of the Roman Empire founded by Augustus who metaphorically "left a city of marble which he had found built of brick." The commemoration of great building projects in Rome on coinage and the commemoration of similar activity in cities throughout the empire leave us with an impressive picture of one of the greatest periods in the history of architecture.



Fig. 102 ROME: The Macellum (Nero A.D. 64-66) BM.



Fig. 105 ROME: The Ara Pacis (Nero A.D. 64-66) BM.



Fig. 106 ROME: The temple of Janus (Nero A.D. 64-66) BM.



Fig. 107 ROME: The arch of Nero (Nero A.D. 64-66) BM.



Fig. 103 ROME: The temple of Vesta (Nero A.D. 64-68) BM.



Fig. 104 ROME: The Circus Maximus (Trajan A.D. 104-111) BM.




Fig. 108 ROME: The Forum of Trajan (Trajan A.D. 112-117) BM.



Fig. 109 PERGAMUM: The 'temple' of Mars Ultor, an imaginary view (19-18 B.C.) BM.



Fig. 110 ROME: The Colosseum with the Meta Sudans to left and the Baths of Titus to the right (Titus A.D. 80–81) BM. See colour plate p.67




Fig. 111 ROME: The Colosseum. Detail of the relief sculpture from the Haterii Sarcophagus in the Lateran Museum, Rome. (Late 1st. cent. A.D.) Fototeca Unione no. 4753.

ROME

THE COLOSSEUM

This Flavian amphitheatre requires no introduction for it is one of the most ^{Fig.} fascinating of the secular buildings of the ancient world. The grotesque grandeur of the ¹¹⁰ performances presented there was matched by the building itself. The well-known coin commemorating its dedication by Titus in A.D. 80 gives an excellent view of the architecture, and especially of the tiers filled with spectators watching the sport. In the centre of the audience a single arched opening marks the imperial box from where the decisions of life or death were given. The detailed design of the niches on the exterior of the building and the main entrance surmounted by a chariot group have parallels on a relief in the Lateran Museum. The relief shows that statues of divinities decorated the ¹¹¹ lower rank of niches, and imperial eagles the second tier. The eagles are, perhaps, symbols of the deified members of the imperial house. The coins show statues in both tiers of niches, and additional decoration above which is omitted on the relief. The actual remains indicate, not niches, but a band of decorations divided into squares. The coins show the rank of squares thus providing a closer guide to the actual architecture than the relief. The wall of the building must have been surmounted by a structure, possibly the trappings for an awning that protected the spectators. On the relief this appears almost as crenellations with cloth stretched between them. On the coins we can see only posts around the top of the wall, a small detail but important enough in the mind of the ancient artist to be included.

The Colosseum coins depict in addition two other monuments which may be linked to the rebuilding programme of Titus. On the left is the Meta Sudans, a conical fountain famous in antiquity. This should be compared with another fountain on ¹¹² Roman coins from which water spurts through the two mouths of the head of Janus set at its apex. The coins emphasize that the Meta Sudans was part of Titus' plan for Rome although it was not completed until after his death. Copies of such a fountain ¹¹³ can be seen on coins of Corinth and Nicopolis. Today the brick core has been ⁷⁶ completely removed to make way for Rome's growing traffic.

Balancing the Meta Sudans on the opposite side of the Colosseum, the coin engraver has depicted tiers of columns which must represent the monumental portico of the Baths of Titus, leading up to the top of the Oppian Hill. Although the plan and architectural details of this building have been preserved by the famous Renaissance architect, Palladio, only the stubbed foundations of the portico can be seen today. It is ¹¹⁴ strange that this equation of the columns on the coin with the Baths of Titus has never been suggested. Yet Titus dedicated the Baths in A.D. 80, the date of the Colosseum itself. Both these buildings and the Meta Sudans must have been part of the same building programme.



Fig. 112 ROME: Fountain, possibly the Meta Sudans itself. The water spouts from a head of Janus (Titus A.D. 80-81) BM.



Fig. 113 CORINTH, Peloponnese: A fountain of the Meta Sudans type, with sculptured decoration of the base (Domitian A.D. 81-96) Berlin.



Fig. 114 The foundations of the Baths of Titus seen to the right of the Colosseum (A.D. 80). Fototeca Unione, no. 3207.



Fig. 115 ROME: The Capitulum (Vespasian A.D. 76) C.M. Krazy collection.



Fig. 116 ROME: The Capitolium with details of the statues on the roof and of the inner cellae (Vespasian A.D. 71) C.M. Kraay collection.



Fig. 117 ROME: The Capitolium with three prominent doors (78 B.C.) BM.

Fig. 118 Marcus Aurelius as Triumphator performing the ritual in front of the Capitolium. Relief in the Palazzo dei Conservatori (mid. 2nd. cent. A.D.) Fototeca Unione no. 14822.



ROME

THE CAPITOLIUM

The temple of the Capitol, shrine of the Rome triad, Jupiter, Juno, and Minerva, *Fig. 19*, disappeared from the surface of the earth late in antiquity, leaving hardly a trace for posterity. The archaeologists have recently found enough evidence of the original Etruscan building (late 6th to mid-5th century B.C.) to draw the ground plan and elevation and in many respects the coins bear a remarkable resemblance to this early temple. Differences, however, among the various examples of the coin type have led some investigators to conclude that because the temple was rebuilt several times, its style was changed and the coins were issued to commemorate these building programmes. We can show that the coins do portray the original temple and that despite any rebuilding there were little or no important architectural changes to its general form. We know that stone was substituted for wooden portions. But we also know that the Romans had received due warning that the gods did not want the ancient forms changed.

The ground plan and elevation show a building remarkably similar to the description of an Etruscan temple by Vitruvius, the Roman historian of architecture. Squarish in form, the edifice had three separate sanctuaries, the centre one for Jupiter Optimus Maximus Capitolinus, the side halls for Juno and Minerva. The deep porch of eighteen columns, the high podium, the closed back wall, gave prominence in typical Etruscan fashion to the front of the building.

It is the facade of the temple which is shown on all the coins in the Capitoline series. ¹¹⁵⁻¹¹⁷ By the normal artistic convention, the die engravers have in some cases brought the cult images out of the interior to the facade. This not only identifies the building itself, but also recalls the practice of showing the deity in the facade in an epiphany, a practice that goes far back in early Near Eastern history. That the Capitoline deities were housed in separate shrines is indicated on some examples by showing on the facade the arched baldachinos which covered each of the cult images in the interior. On other examples, the artist has depicted on the facade the three doors which led to the interior.

The die maker of the earliest coin in the series, of the moneyer Volteius, reduced the number of columns in order to show the three doors which in actual fact must have been hidden behind a veritable forest of columns. The same three doors appear on the well-known relief of the 2nd century A.D. where the emperor, Marcus Aurelius, is seen ¹¹⁸ as typical Etruscan triumphator, performing the sacrifice before the Capitolium. To the die-maker of the Volteius coin, the important characteristics of the building to be recorded were the three doors and the decorations of the sloping roofs. The archaeologists in their turn considered the roof decorations interesting because they ¹¹⁹ found Etruscan fictile ornaments that resembled them and were dated to the same period as the early Capitolium. The artist was not working from memory. The building which he illustrated was there for him to see and copy. The coin of 78 B.C. represents the actual decorative details of the original temple building.

FIG. It has never been noticed that the Volteius representation was closely copied by a provincial city, the difference being that the coin of Carallis in Sardinia bears the legend VENERIS. This coin is an exact copy of the Roman type, but the legend indicates that Venus held prime position in the worship of the temple. Even so, the three doors may represent separate sanctuaries; and the Sardinian coin shows how great an impression the ancient Etruscan shrine made in the first century B.C. on an island, distant from the Capitol. This same kind of influence is shown by the use of the Capitolium types in Corinth and in Asia.

Because of an ancient report that the pediment of the Capitolium was at one point in time made higher, it was suggested that a strange coin with a pediment-like design was issued to celebrate the new tympanum. The monster illustrated is a lesser god named Summanus who, the legend had it, was struck by Jupiter. The same deity appears in the pediment of the Anatolian issue. Cicero tells us that, in 278 B.C., a statue of this god decorated the pediment of the Capitolium and was struck by lightning. There is no firm evidence of any rebuilding during the first century B.C., and so the reason offered for striking the coin is not valid.

It is often assumed that architectural types on coins of Rome were issued to commemorate the building, or dedication, or rebuilding of an edifice. This was by no means necessarily so, and such thinking can lead to absurd theories. The Capitoline temple appeared first on coins long after it was constructed, not because it was rebuilt in 78 B.C. but because the Roman world had just begun to use architecture as coin types. The Capitolium was chosen because it symbolized the most important cult of the city. Once adopted, it was repeated as a type with the usual die-makers' variations. In the case of coins bearing a special legend such as the reference to the restoration of the Capitolium in A.D. 82, commemorated on the coin of the province of Asia, the Anatolian issue mentioned above, the motive for the issue is self-explanatory: The building was destroyed by fire in A.D. 80 and was rebuilt by the emperors Titus and Domitian. It should be noted that restoration does not necessarily imply a change of style or design. All the other types in the Roman Capitoline series have no legend. Their variations were all inspired directly or indirectly by a common design, the original temple building itself.

From the coins we can assume that there was a quadriga at the apex, bigae or single horses as corner acroteria and figures along the raking cornices. There were six columns on the facade and three main doors to the three cellae. The difference in the number of columns and in the style of the capitals is immaterial since the coins did not always emphasize these particular details. The modern elevation, based on actual finds, literary evidence, and the style of Etruscan ornaments, has adopted the quadriga, the decorated cornices and the acroteria shown on the coins. The statues along the roof are definitely in the Etruscan tradition.

The main difference between the coins and the Etruscan temple is in the pedimental sculptures. Also the temple of the coins appears to be a typically Greek or Hellenistic building, not as on the Volteius coin, or on the late provincial type of Asia Minor, both of which present a squarish, stunted Etruscan building. There is no evidence that an



Fig. 110



Fig. 130



Fig. 133

Fig. 130 ATHENS: The Acropolis. BM.

Fig. 133 ATHENS: The theatre of Dionysus and the buildings of the Acropolis. BM.




Fig. 119 Elevation of the facade of the Capitoline temple (6th–5th cent. B.C.) Courtesy E. Gjerstad.



Fig. 120 CARALLIS, Sardinia: Temple of Venus/Tanit (Late 1st. cent. B.C.) BM.



Fig. 121 ROME: Denarius sometimes said to depict the pediment of the Capitulum (69 B.C.) BM.



Fig. 122 ASIA: Silver cistophorus celebrating the restoration of the Capitolium at Rome (Domitian A.D. 82) BM.



Fig. 123 ROME: The Capitolium with figures apparently reclining in the pediment (Vespasian A.D. 77-78). BM.

Fig. Etruscan temple was decorated with figures either in the round or in high relief before the 4th century B.C. Thus if there were any decorations in the tympanum of the Capitolium when it was first constructed, they were almost certainly in low relief, as indicated on some of the ancient models of temples which have survived. The decorations would not be the figures in the round shown by the Roman series. A further remarkable fact should be noted. The figures in the coin pediments duplicate the cult images below. When the cult images between the columns are standing, they are shown standing in the pediment; when Jupiter is portrayed seated and the others standing, the die-maker repeats the composition in the pediment above. An exceptional case is where the two goddesses are shown in the pediment recumbent, but on the facade they are standing. Cult images do not change their positions; it is the die makers 123 who change them when they intend to reproduce something other than an absolutely realistic picture of the temple. Yet we should note the very distinct similarities in the pedimental sculptures between the coin of Vespasian (115) before the destruction, and the relief sculpture of the mid 2nd century A.D. (118). Although much on the coins is truly representative of the actual building, the figures of the pediment, their postures, and the decidedly Greek look of the facade may well be misleading. The Roman citizen who used the coins was not shocked that the familiar Capitolium was pictured as a slender Greek temple. He was used to the mixture of Greek and Roman styles fashionable in all art at that time. One fact must be emphasized that although the coins show a number of variations, the style of the temple itself, symbol of Roman power, remained solidly unchanged.

ROME

THE CURIA

The Curia is one of the best preserved buildings in Rome, one of the few still complete edifices along a street of beautiful ruins in the Forum. It owes its preservation to the very religious movement that tried to destroy it. It was turned into a church. The building was planned by Julius Caesar as a meeting place for the Senate, but despite its secular nature, we know from literary sources that it resembled a temple.

The coins which are said to show the Curia, and the Curia as it stands today are, however, patently different. The coin type resembles a temple, although not a typical Roman temple; the present day Curia does not. The unusually well-documented



Fig. 124 View of the Curia Julia, as restored (End 3rd cent. A.D.) Fototeca Unione 13.



Fig. 125 ROME: The Curia (Augustus 29-27 B.C.) BM.




Fig. 126 The temple of St. Ouen-de-Thouberville, France; reconstruction (1st. cent. A.D.) Courtesy A. and J. Picard.



Fig. 127 Reconstruction of temple II at Elst, Netherlands (late 1st cent. A.D.) Courtesy Staatsijigeverij, Netherlands



Fig. 128 CAESAREA, Mauretania: The Temple of Augustus (Juba II A.D. 6) BM.

history of the building not only allows us to explain this anomaly, but permits us to introduce a series of coins issued in North Africa, the pertinence and importance of which have passed unnoticed.

Caesar undertook to build a new Senate house in the fateful year, 44 B.C. His great nephew and heir, Augustus, completed and dedicated the building in 29 B.C. and in Caesar's honour, named it the Curia Julia. The "Curia" coin was issued at Rome not long after this event. Augustus also dedicated an altar of Victory as an especial reminder of his crushing defeat of Antony and Cleopatra in 31 B.C. and had it installed in the building. The die maker of this coin has placed on top of the building a statue of Victory which in all likelihood represents the Victory dedicated by Augustus, and which actually stood within the Curia. Such shorthand conventions have been discussed in the introduction. They helped the engraver to compress a life-size monument into a very limited space. What is remarkable is that the public could immediately recognize the monument through these engravers' conventions, which today so complicate the interpretation of such coins.

Fig. 126-7 What of the further differences between the coin and the building as it stands? It is not possible to know what kind of edifice Caesar was planning; it is possible to hazard a guess. The facade as it is today is so much like that of Gallic temples that it is no wonder that some have thought the coin actually represented some such building and not the Curia in Rome. Temples at St. Ouen, at Autun, and several other similar Gallic buildings are dated to the end of the 1st century B.C. or to the 1st century A.D. Caesar spent almost ten years in Gaul, and it is reasonable to assume that he planned a Curia that would resemble a Gallic building as a permanent reminder of his own great triumphs. He planned the windows in the upper part of the facade, the door, and the pediment which exists on both the coins and the building as it stands today. It is worth noting that in the eyes of the pious Republican Roman, the use of a pediment was restricted to sacred buildings.

The coin does not show the most characteristic feature of the Gallic temple, the gallery with pitched roof. Instead, it shows that the Curia was surrounded by an arcade made of low columns, spanned by an horizontal architrave. But the strange openings on the actual Curia building appear to be exactly like those which were found on the core of a temple at Autun, obviously used to receive the beams of a Gallic gallery. Instead of a high pitched gallery, the Curia, as finished after Caesar's death, had a peripteral arcade. The archaeologists have recently announced that they have found evidence of such columns, thus proving the validity of the coins.

128 A fascinating extension of our interpretation brings in a series of coins issued in A.D. 6 by the vassal King Juba II of Mauretania in North Africa. The building on these coins exactly matches the building on the Augustan coin of Rome, except that the inscription honouring Caesar is replaced with one honouring Augustus and a star and crescent, symbol of Juba's Phoenician domain, replaces the statue of Victory on the roof. On some issues of Juba's coins, the surrounding arcades are removed so that the die maker could exaggerate the size and decoration of the door. We know exactly what the door of the Roman Curia looked like because it has survived to the present day, and literary references note that it was something exceptional. The North African die makers emphasized this detail. Juba's father committed suicide after his defeat by Caesar at the Battle of Thapsus in 45 B.C., and as a young boy, Juba II himself was forced to take part in the triumphal march of Caesar through the very Forum where later the Curia Julia was built. The rest of his life is even more dramatic: Augustus befriended him and allowed him to take part in the campaign against Antony and Cleopatra. Juba II subsequently married the daughter of these ill-starred lovers. It is unlikely that Juba's coins represent the Curia at Rome which was so closely associated with the victories of Julius Caesar. Furthermore, provincial cities, with few exceptions, featured their own buildings on their coins. It is certainly possible that Juba II built a temple in honour of Augustus when he moved his capital to Caesareia, and that it was constructed on the model of the Rome Curia.

The well-preserved Curia building stands today among the noble ruins of the Roman Forum much in the same form in which Diocletian restored it. The coins show us how the Curia looked in the golden age of Augustus, a permanent and living record of the building itself.

ATHENS

In contrast to Rome, the coins of Athens record few of its magnificent buildings so famous in antiquity. Yet two coins, in spite of their somewhat indifferent workmanship and small size cannot fail to stimulate our interest, representing as they do some of the best known monuments of the ancient world, the buildings of the 129 Acropolis and the theatre of Dionysus. The coins were struck as late as the third century A.D., seven hundred years after the Persian destruction of Athens had forced the citizens to plan again for the adornment of their city, and to crown their citadel with a new temple to their goddess Athena, the Parthenon. Even when these coins were designed, these buildings were ancient, revered in the same way as a Gothic cathedral today.



Fig. 129 ATHENS: Aerial view of the Acropolis from the North, showing the prominence of the Erechtheum and the caves below Propylaea. Courtesy Greco-Posters Ltd., Athens



Fig. 130 ATHENS: The Acropolis shown from the North, with the Erechtheum, statue of Athena, and Propylaea. The steps of the sacred way lead past cave sanctuaries (mid. 3rd. cent. A.D.) BM. See colour plate p.68



Fig. 132 ATHENS: Statue of Athena which conforms most closely to the Athena Promachos shown on the Acropolis coin (mid. 3rd. cent. A.D.) BM.



Fig. 131 ATHENS: A variant view of the Acropolis with prominent gateway below the lip of the hill (mid. 3rd. cent. A.D.) BM.

The depiction of the whole Acropolis is fascinating, in spite of some stylization, ^{Fig.} since we know the buildings so well today from the ruins. The long stairway, following ¹³⁰ the line of the famous Panathenaic way from the Agora, climbs up to the Propylaea, the monumental 5th century B.C. entrance to the sanctuary. There are many versions of this coin, some of them the right way round on the die, others back to front, and the most striking variation occurring in the representation of the main gateway. This is often shown with only two columns and set so far below the lip of the hill that it must ¹³¹ be the gateway of the Roman period — the Beulé gate — intentionally omitting for a reason that may have been clear to the Athenian citizen the more impressive early Greek propylaea which is situated higher up the hill. On fig. 130 the columns clearly depict the Greek portico and they flank a squat rectangular object which represents the great wooden doors that could shut off access to the sanctuary.

On passing through the propylaea, the visitor in ancient times would have been at once impressed by the gigantic bronze statue of Athena Promachos, sculptured by Pheidias, which stood directly in front of the entrance. This monumental figure, of which nothing remains today, dominates the die cutter's representation of the Acropolis and the same statue appears on another contemporary coin which shows ¹³² better the general pose of this masterpiece. The remaining building on the hill, a temple with its altar placed at the East end, presents a problem of identification. One would expect to find there the most famous temple of the Acropolis, the great temple of Athena, the Parthenon. The sides however are shown as solid masonry instead of the usual peripteral colonnade so well known to every visitor today, and although the coins show columns at the East end, there is no evidence of the Parthenon's West columns. At other cities, die makers found no difficulty in showing side columns and there is no reason why they should have lacked the art of doing so at Athens. On the coins depicting the theatre of Dionysus, the columns of the Parthenon are seen clearly, crowning the hill. We must therefore consider seriously whether the artist intended to depict a building other than the Parthenon. Indeed, the structure resembles the Erechtheum, the smaller temple to the North of the Parthenon, famous for its Caryatid porch which does have columns on its East facade, as well as a solid masonry wall on the North. The building occupies so prominent a position in the design and the walling has been so carefully drawn that we must assume that the die maker intended to show, not the Parthenon, but the Erechtheum. The reason is that this building housed not only the ancient cult of the hero Erechtheus, but also the shrine of Athena Polias. It was the "temple of the archaic image," no less important than the Parthenon itself in the cult of the goddess Athena. Some of the coins may have been struck to commemorate the important renovation of the Erechtheum which certainly took place in Roman times; but the significance of the building would have been clear to the Athenians of the 3rd century A.D.

The coins plainly show the North wall of the Acropolis much as it is today. In addition, the artist deliberately distinguished between the masonry of the wall and the rough rocks of the hill below. Here we find two interesting niches at the side of the stairway which must represent cults of the deities worshipped in caves on the side of the Acropolis. One of these was surely the cave of Apollo, situated "just below the gateway" where the god was supposed to have violated Creusa, the daughter of

^{Fig. 133} Erechtheus. The other famous cave on the hillside was the Grotto of Pan, situated as on our coin near the cave of Apollo. Thus these remarkable coins, in spite of their small size and comparatively poor workmanship, give us a fair impression of the Acropolis in Roman times.

¹³³ Equally interesting is the view of the theatre of Dionysus, a unique design in Greek coinage, showing the auditorium and stairways rising between the seats just as it may be seen today. An upper section of seats is clearly visible. Above these is the cave ¹³⁴ which now forms the chapel of Our Lady of the Cavern where once stood the choregic monument of Thrasyllus who had dedicated the cave to Dionysus. The buildings of the Acropolis above seem to be a forest of columns as they must have appeared in Roman times. By raising the central portion above the rest, the artist has cleverly created three "buildings." The Parthenon itself appears in the centre with its colonnade and roofing directly above the theatre. On the right is depicted the small temple of Roma and Augustus, the foundations of which are still to be seen to the East of the Parthenon. Balancing this on the left are the columns of either a sanctuary on the South side of the Acropolis or of the Propylaea itself.

The contribution of the Athenian coins is a considerable one. For those who doubt the reliability of coins — among these are not a few archaeologists — the Athenian series provide simple, interesting, and yet unexpected view of the Acropolis. They show in a most convincing way that Roman Athens was no less proud of her architectural glory than are the modern Greeks today.



Fig. 133 ATHENS: The theatre of Dionysus with the buildings of the Acropolis above (mid. 3rd. cent. A.D.). BM. See colour plate p. 68



Fig. 134 View of the theatre of Dionysus, Athens, with the cavern in the rock of the Acropolis above.

CORINTH

From its foundation by Julius Caesar in 44 B.C., the Roman colony of Corinth ^{Fig.} possessed an active mint which produced a large and diverse coinage. Architectural types recur frequently and, together with the recent American excavations of the area, provide a good impression of the main buildings of this great city. Pausanias' description of his visit in the middle of the 2nd century A.D. unfortunately leaves much to be desired, but he does name a number of monuments which can be compared profitably with the coins.

Dominating the area is the hill of Acrocorinth on which are still to be seen remains of the famous temple of Aphrodite. This naturally caught the imagination of the ¹³⁵ designers of the coins and we find not only the temple itself and the cult statues depicted, but also the whole hill with details of its main features: The temple of Aphrodite at the summit, a tree and a rock-cut grotto at lower left which mark the famous fountain of Peirene whose cool waters still provide a fountain for the villagers. On the right there is a gateway probably denoting a sanctuary which has not yet been identified.



Fig. 135 CORINTH: View of the Acrocorinth surmounted by the temple of Aphrodite and with fountain ? buildings at the foot (M. Aurelius A.D. 161-180) BM.



Fig. 136 CORINTH: The nymph Peirene giving water to Pegasus; behind, the Acrocorinth (Septimius Severus A.D. 193-211) BM.



Fig. 137 The Acrocorinth with masonry of the fountain of Peirene in the foreground.

Fig. The fountain of Peirene is also depicted separately on the coins. One shows the
 136 nymph of the fountain, personified, pouring water from a jug for the Pegasus, for it
 was this legendary winged horse who while drinking at a fountain was tamed by
 Bellerophon. Beside the nymph and Pegasus is a tree and in the distance the
 137 Acrocorinth surmounted by the temple of Aphrodite. Another coin shows the same
 138 nymph with the figure of Scylla in front of her. The connection between the nymph
 and Scylla is explained by a third coin which, previously unrecognized, shows a
 139-139A straightforward architectural view of the whole Peirene fountain: At the top is the
 arcaded facade of the grotto, behind which are catchment basins; flanking this are two
 statues which may be Tritons; below, in front, is the rectangular basin with steps
 140 leading down to it at the far end. This is exactly as we see the fountain today except
 that the statue of Scylla, now lost, is shown on the coin in the rectangular basin of the
 forecourt. The excavators found a rough-hewn statue base which stood in front of the
 fountain facade and past which the water cascaded on either side into the forecourt.
 They assumed that it was a statue of the nymph Peirene, but we can now show that it
 was probably a statue of Scylla which occupied this prominent position in the
 fountain. The coin itself may have been struck to commemorate the large-scale
 embellishment undertaken during period VI, to use the archaeologists' terminology,
 which considerably enlarged the fountain's facilities. This, on the basis of the coins,
 would have taken place during the reign of Septimius Severus.

CORINTH



Fig. 138 CORINTH: The statues of the nymph Peirene and the monster Scylla (Septimius Severus A.D. 193–211) BM.



Fig. 139 CORINTH: The fountain of Peirene showing arcade, court and steps leading down (Septimius Severus A.D. 193–211) Berlin.



Fig. 139A CORINTH: The fountain of Peirene (Septimius Severus A.D. 193–211) Courtesy of the Director of the Corinth Excavations.




Fig. 140 The fountain of Peirene as it is today. The columns were Byzantine additions to the arcade; but steps and court are as on the coins.

- FIG. 10. Pausanias underlines the great number of fountains to be found in the city of Corinth and two coins, not previously recognized as fountains are important in this connection. The first shows a statue of Poseidon with a dolphin at his feet which fits
 141 Pausanias' description of an impressive bronze fountain and which the archaeologists believe once stood at the West end of the Agora, water gushing out of the dolphin's mouth. At the end of the 2nd century A.D. the fountain was removed to make way for two temple buildings. The second coin, not at once recognizable as a fountain, is an
 113 exact copy of Rome's famous fountain, the Meta Sudans, which we have previously discussed under the Colosseum. There is no literary evidence or remains of such a fountain at Corinth. The Corinthians may have built one after the Roman model, perhaps near their own amphitheatre or near the stadium of the Isthmus, but a similar
 142 coin copying the Capitulum at Rome suggests that they are Roman not Corinthian monuments represented.

- Of the temples represented on the coins, that of Hermes can be identified with the remains of an important shrine at the Northwest corner of the Agora. A temple on
 143 coins dated circa A.D. 25 dedicated by an inscription on the architrave to the Gens Julia is probably the temple of "Octavia" mentioned by Pausanias "above the market
 144 place." A temple of Artemis Huntress, with prominent half fluted columns, cannot now be identified although the tree indicates a rural setting. On another coin, a tree in a masonry enclosure suggests a cult of non-Greek form. The well-known temple of
 145 Poseidon at the Isthmus, the central shrine of the Panhellenic Isthmian games, can be identified on the coins by the statue of the sea-monster Tritons which decorated its roof and which caught the attention of Pausanias. The coins not only show the Tritons but also a tree to indicate the line of fir trees which stood on one side of the road leading up to the sanctuary. On either side of the Isthmus were the harbours for Corinth, at Lechaëum and Cenchreæ. These harbours are found on the coins both as
 146 personifications and also as actual architectural structures. Cenchreæ is identified by the statue of Isis Pharia whose cult shrine actually stood at the end of one jetty, with a



Fig. 141 CORINTH: The Poseidon fountain (Commodus A.D. 177-192) BM.



Fig. 142 CORINTH: The Capitulum at Rome (Domitian A.D. 81-96) BM.

CORINTH



Fig. 143 CORINTH: The temple of Gens Julia (Livia c. A.D. 25) BM.



Fig. 144 CORINTH: The temple of Artemis Huntress (Plautilla A.D. 202-205) BM.



Fig. 145 CORINTH: The temple of Poseidon at the Isthmus (Geta A.D. 198-211) Vienna



Fig. 146 CORINTH: The harbour at Cenchreae (Antoninus Pius A.D. 138-161) BM.



Fig. 147 CORINTH: Galley passing the lighthouse at Lechaëum (Commodus A.D. 177–192) Berlin.



Fig. 148 CORINTH: The Agora showing the stoas to North and South (Caracalla A.D. 198–211) ANS



Fig. 149 CORINTH: The column marking the tomb of Lais (Geta A.D. 198–211) ANS.

temple of Asclepius balancing it at the other side of the coin. The lighthouse building ^{Fig.} which appears on other coins seems to have no place at Cenchreae and may belong to ¹⁴⁷ the Lechaum harbour. It has always been assumed that the Lechaum harbour is represented on another coin which shows a temple flanked by two colonnades. But the ¹⁴⁸ rectangular arrangement with the strange position of the temple is most unusual, and instead of galleys which normally indicate the water of a harbour, there are two statues both of which seem to be fish-tailed deities holding dolphins, possibly the Tritons which we noticed on the Peirene fountain. It is much more reasonable to suppose that the coins show the main agora of the city with shops down either side. Even the roof tiles are depicted. The temple engraved at the West end, trees growing within its boundaries, is quite clearly the archaeologists' temple E. In spite of a coin of Caligula found in the foundations, the position of the temple fits closely that of Pausanias' temple of Octavia, mentioned above. It stood beyond the actual limits of the Agora and was reached by a flight of stairs. The altar which is shown to the far left of the temple should probably be envisaged as standing between the stairs and the facade.

Other coins of Corinth illustrate many monuments both of the city and of the surrounding country. The tomb of Lais, one of the famous courtesans of antiquity, was ¹⁴⁹ a major tourist attraction at the time of Pausanias' visit. He describes the tomb as it appears on the coins; a statue of a lioness with a ram between her forepaws set on a fluted column. The altar of Melicertes stood in a pine grove by the shore at Cromyon. It appears on coins as a large circular structure on a high podium covered by an ¹⁵⁰ ornately tiled canopy with dolphin acroteria. A door leads through the podium, ¹⁵¹ presumably to allow access to the statue group of the boy Melicertes lying on a dolphin. Legend had it that the dolphin brought the body of the boy to shore at this spot.

"The gateway from the Agora on the road to Lechaum is surmounted by two gilded chariots. In one stands Phaethon, son of Helios, and in the other Helios himself". This notable gateway, described by Pausanias, is shown on coins as an ¹⁵² ornamental triumphal arch with the chariot groups clearly visible. Finally, one of the most striking monuments of the coins is a column supporting a heroic figure on a large masonry base decorated with equestrian statues. This structure has been identified as a ¹⁵³ lighthouse, but comparison with the unmistakable lighthouse of the harbour coin-type mentioned above shows that this is most unlikely. It is a quite different form of structure. It has been suggested that it is the so-called circular monument which dominated the East side of the Agora at the end of the centre row of shops, one of the most important monuments in the market place. But the archaeologists have rejected the identification. If it is not that structure, however, it must have been a similar monument somewhere else in the city.

The coins given in this short survey present a truly amazing picture of the grandeur of Roman Corinth in its heyday. We have suggested on the basis of the coins the identification of several important buildings. More will be possible when further remains are unearthed by the archaeologists to become the basis of comparison with the coins.



Fig. 150 CORINTH: The shrine of Melicertes at Cromyon (M. Aurelius A.D. 161-180) Paris.



Fig. 151 CORINTH: The shrine of Melicertes with a doorway in the podium (Septimius Severus A.D. 193-211) BM.



Fig. 152 CORINTH: The gate to the Lechaean road (Hadrian A.D. 117-138) Oxford.



Fig. 153 CORINTH: Monument or Heroon (Septimius Severus A.D. 193-211) BM.

DELPHI

THE TEMPLE OF APOLLO

The representations of the temple of Apollo seem at first glance to be stylized, but there are several important points of interest which have been overlooked. The temple, the third building on that site of which remains have been found, dates from the middle of the 4th century B.C. It replaced a famous late 6th century shrine which had been completely destroyed circa 370 B.C. by earthquake. The third temple took many years to complete and was not officially opened until 305 B.C. In the Hellenistic period, a world of great monarchies and power politics, Delphi never resumed the position of authority which she had held earlier. It was, nevertheless, a unifying centre for the states of Greece and was held in reverence until the Roman conquerors began to despoil the sanctuary of its treasures. For a hundred years it was a prey to this pillage which ended when the emperor Domitian set about making extensive repairs to the temple circa A.D. 84. Finally time brought the crumbling buildings to ruin and the whole site was in the 19th century covered by a village which had to be removed before the archaeologists could once more reveal the great sanctuary. Fig. 154



Fig. 154 Delphi before the excavations: from H.W. Williams, *Select Views in Greece*, London, 1829.



Fig. 155 DELPHI: The temple of Apollo in three-quarter view, with the statue of Apollo Pythios (Faustina I c. A.D. 145) BM.



Fig. 156 DELPHI: The temple of Apollo showing the famous pedimental sculptures and "Mystic E" between the central columns (Septimius Severus A.D. 193-211) Paris.



Fig. 157 DELPHI: The altar (Hadrian A.D. 117-138) BM.

The actual temple had six columns on the facade and fifteen on the flanks. The three-quarter view on the coin displays the usual numismatic abbreviation perfectly intelligible to the citizens who knew the temple well. The temple is that of Apollo Pythios whose image stands in the facade and this identifies for us with exceptional clarity the pose of that particular cult statue. This type of Apollo recurs all over the Greek world.

The frontal view of the temple, identified by the mystic E between the columns, gives clear indication of the sculptures which we know from literary sources to have decorated the tympanum. These have recently been re-excavated in Delphi museum. The columns are shown as Doric and on the three-quarter view the roof displays the unusual detail of three horizontal rows of decoration, on the ridge pole, on the tiles, and at the cornice (sima). These have never been shown in a modern reconstruction. It is possible that they belonged to Domitian's renovation, and not to the original temple; but they certainly existed at the time the coins were issued. Such spiky objects, particularly if brightly painted, would have been striking, even dazzling to the onlooker. The frontal view shows standing figures as acroteria.

Another coin of Delphi which has rarely been discussed is that of Hadrian showing an "altar." It is difficult to escape the conclusion that this must represent the great altar of the sanctuary, the altar dedicated by the Chians. In favour of the identification is the fact that the structure is placed on a most unusual podium, exactly as the altar of the Chians appears when seen from the Sacred Way. The coin also definitely shows that the altar had a pediment, an unusual architectural feature for an altar but by no means unknown. No modern reconstruction, however, has acknowledged this exceptional detail. It is entirely possible that the pediment was a false one, decorating the eastern facade of the altar, and thus dominating the Sacred Way. Insufficient stones of the upper courses survive so that we cannot know whether this pediment was a Roman addition to the original Greek structure.



Fig. 158 The altar of the Chians and the temple of Apollo, Delphi, as restored by the excavators



Fig. 159 AMASEIA: View of the city on the mountainside with temple and altar of Zeus Stratiotes above (Alexander Severus A.D. 229) Price Collection. See colour plate p. 101.



Fig. 159A AMASEIA: The city defences under construction (Alexander Severus A.D. 229) BM.



*Fig. 160 View of the city of Amaseia from across the gorge. From G. Perrot and E. Guillaume, *Exploration archéologique de la Galatie*...exécuted en 1861, Paris, 1862-1872.*

AMASEIA

"Our city lies in a deep and impressive gorge through which the river Iris runs; and it has been built with so marvellous a combination of skill and nature that it serves both as a habitation and as a fortress. The high cliff falls sheer to the river; at the foot, on the banks of the river, there is a wall which supports the town itself, and on either side the fortifications rise to the very tops of the mountain. For there are two actual summits, connected by a spur to each other which are both splendidly fortified. Within the wall which surrounds the town are to be found the palace and the tombs of the Pontic kings. The summit may be reached only by a path on a narrow ledge and whether you come from the river or the outskirts of the town, the ascent is still some five or six stades; and there is a further steep climb of one stade to the summits which can be defended easily against any attack."

Strabo, Geography III, 39.

The city of Amaseia is described today as one of the most impressive sights in Turkey; and the description of the Roman geographer Strabo of his own home town makes a most poignant commentary on the fine coin of the city issued in A.D. 229/30. The walls are not depicted there as continuous stretches of masonry as at Bizya and in other city views, but as independent towers. A previously unpublished coin shows these under construction and a look at the terrain will show that fortifications at strategic points on the sheer face of the mountain were all that were necessary or practicable. The city itself lay at the foot of the mountain with two bridges only across the river. Dominating it was the ledge some way up the mountain side, on which stood the palace of the Pontic kings, and which still has Hellenistic walling supporting the Turkish fortress. On the coin, this position is taken by a large temple with six columns on the facade. There is no clear identification of this building, but it probably represents the temple of the Imperial cult for which the city was endowed with the coveted title *Neocoros* in the middle of the second century A.D. Certainly no better position in the city could have been found as a mark of respect to the Roman emperors.

To the left of this temple the coin shows a strange niche in the rock, fully explained by Strabo's remarkable description, and visible on the mountain side from across the gorge. It is one of the famous rock cut tombs of the kings of Pontus, some of which



Fig. 162 AMASEIA: View of the city (Domitian A.D. 81-96) BM.



Fig. 161 One of the rock-cut tombs of the kings of Pontus, Amaseia. From G. Perrot and E. Guillaume, *Exploration archéologique de la Galatie...* Paris 1862-1872.

Fig. were placed within the walls and some outside. If it represents a particular tomb, that
161 of Mithradates I, the founder of the dynasty, is the most probable.

At the top of the design is another temple, placed in three-quarter view, with an altar in front of it to the right. The side wall of the temple can be made out behind the topmost tower. This sanctuary was most certainly dedicated to the chief deity of Pontus, Zeus Stratios. Close inspection, however, reveals that it is not actually standing on the mountain. If you remove it entirely from the design, the mountain top appears with the twin peaks exactly as described by Strabo and as it appears today. The temple and altar were not on the mountain. Another example of the coin proves this:
162 temple and altar are shown; only the two mountain summits are seen.

The presence of the sanctuary on some of the coins is easily explained. It was placed there by the same numismatic convention we have so often seen used, showing above what actually stood behind. The sanctuary of Zeus Stratios was not at Amaseia itself, but to the East, behind the mountain, on the high plateau at Buyuk Evlia. In order to show the temple of the high plateau, the die-makers have added it to the design. Mithradates the Great is reported to have sacrificed at the altar of Zeus Stratios and the flames of the altar were said to be visible from the Black Sea. The altar on the coin has flames clearly visible.



Fig. 164 AMASEIA: Temple of Zeus Stratios (?) (Trajan A.D. 116) Berlin.



Fig. 163 AMASEIA: The altar of Zeus Stratios with chariot of Helios above, and sacred tree (Caracalla A.D. 209) BM.

This great monumental altar of Zeus Stratios also appears as a coin type of the city, ^{Fig. 163} always accompanied by a tree or a flower which would seem to have some connection with the cult. As at Ephesus, Sardis, and in many ancient local cults, it may well be that an altar existed before the temple was built. The temple itself is probably the fine building shown on a coin of Trajan of A.D. 116/7. Such details as are clear fit with the temple as it appears in the city view. We should note the prominent parotids as on the Trajan temple at Pergamum. It is clear, therefore, that the great sanctuary of the plateau has been brought into the design of the city view to complete the picture of ^{Fig. 164} the religious life of the city. The three great monuments of its territory — the sanctuary of Zeus Stratios, the Neocorate temple, and the tomb of the Pontic Kings — are brought together within the protection of the walls of one of the most famous citadels of the ancient world.



Fig. 166 NEOCAESAREA: Gate to the sanctuary with open doors (Septimius Severus A.D. 209–10) Berlin.



Fig. 165 NEOCAESAREA: Gate to the sanctuary with closed doors (Caracalla A.D. 209–10) Berlin.



Fig. 167 NEOCAESAREA: Gate to the sanctuary with two radiate busts and decorated doors (Septimius Severus A.D. 205–6) Paris.

NEOCAESAREA

THE SANCTUARY OF MA

The pre-Roman name of Neocaesarea is not yet known with certainty. In the 3rd century A.D., it is clear from the coins that the town assumed considerable importance as a centre for the cities of Pontus. The focal point of worship of the Pontic League was the monument which is found on numerous coins of the Severan family. Each engraver gives us different details and so it is therefore necessary to consider each variety in the search for the true reconstruction. No other building on coins has attracted so many different details. 165-172

With few exceptions the coins show a tetrastyle facade usually with carefully delineated Corinthian capitals. One variety depicts a building of five columns which is unknown in actual architectural remains. This may indicate the exact number but could also be attributed to an artist's carelessness. All show one and the same building. The altar in the centre of the columns is the key to the function of the monument; for when the die maker used it, he intended to represent, not a temple, but a gate, as on the several examples listed in the introduction. All the architectural details and figures shown in the facade actually stood behind it. The variety and multiplicity of cult objects and images presuppose a large sacred area. The monument of the coins, then, is a gate; not the door of a temple, but the gate of a sanctuary.



Fig. 168 NEOCAESAREA: Altar and radiate bust within the gate to the sanctuary of Ma (Geta A.D. 209-10) BM.



Fig. 169 NEOCAESAREA: Niche within the gate to the sanctuary (Septimius Severus A.D. 209-10) Berlin. See colour plate p. 49.



Fig. 170 NEOCAESAREA: Three busts between the columns of the gateway (Geta A.D. 209-10) Vienna



Fig. 171 NEOCAESAREA: Statues and busts within the gate to the sanctuary (Geta A.D. 209-10) Vienna



Fig. 172 NEOCAESAREA: Gate with bust and door knocker (Septimius Severus A.D. 209-10) BM.



Fig. 173 NEOCAESAREA: 'Pentastyle' gate to the sanctuary (Septimius Severus A.D. 209-10) BM.



Fig. 174 NEOCAESAREA: Statue of Ma/Zeus on a pedestal within the gateway (Caracalla A.D. 209–10) BM.



Fig. 175 NEOCAESAREA: Temple of Zeus (Gordian III A.D. 238–244) Paris.

We are dealing with a sanctuary of an inland city of Pontus where Iranian influence ^{Fig.} persisted throughout the Roman period. The standing statue in the centre of the coins ¹⁷⁴ is identifiable as Zeus, who, as the great sky god, was a celestial divinity. He appears ¹⁷⁵ again seated, on a later coin, with a rosette sun-symbol in the pediment. The radiate bust may well represent the great local sky god, Ma ('she' was both male and female), who dominated the beliefs of indigenous Oriental Pontus and the duplication reflects perhaps Zeus' dual role in the Dioscuri. Her standing figure appears on other Pontic issues, of Comana, associated with the eagle of Zeus in the pediment. Ma was the ¹⁷⁶ object of the celestial cult of the Pontic kings whose coins are decorated with stars and crescents. It would appear therefore that the coins show the gate of a sanctuary dedicated to the worship of the supreme sky god, Ma, the Magna Mater of Pontus, associated with the celestial, Graeco-Roman Zeus. ¹⁷⁷

On the question of cult, the coins have even more to offer. One example shows what must be an imperial bust within a niche; another, three busts. The simplest explanation ^{169–70} is that these are the busts of the emperor Septimius Severus and of his two sons Caracalla and Geta. If so, we have the imperial cult inextricably linked with the local ¹⁷⁸ cult of Ma/Zeus. This appears to be confirmed by the fact that later the city can boast ¹⁷⁹ two neocorates under Severus Alexander, the first of which must have been given by Septimius Severus.

Thus from the coins which at first seemed so enigmatic, we may deduce that the main sanctuary of Neocaesarea was dedicated to Ma in whom the Greeks recognized Zeus, and under the Roman empire this was shared by the imperial cult. The artistic treatment of the facade on the coins has enabled us to lift the veil from this strange persistence of Oriental traditions into the Roman period.



Fig. 176 COMANA, Pontus: Temple of Ma (Trajan A.D. 98-117) ANS.



Fig. 177 PONTUS: Silver tetradrachm depicting the celestial deity, Ma (Pharnaces I 185-159 B.C.) BM.



Fig. 178 NEOCAESAREA: Two neocorate temples (Alexander Severus A.D. 234-5) BM.



Fig. 179 NEOCAESAREA: Two neocorate "temples" with altars within (Alexander Severus A.D. 226-7) BM.

NICAEA

The city of Nicaea, mentioned in Pliny's letters quoted in the preface, has left a rich series of coins on which architectural types play a notable part. At least four different temples are shown, as well as gates and a view of the walls, and they tell us a good deal about the city itself. Architecturally, ancient Nicaea was most noted for the gymnasium which formed the central focal point of the city, and for the colonnades which were erected along the main thoroughfares in early imperial times. Fig.

Two coin issues under Claudius may well refer to this programme of adorning the city: One shows a double storied arcade sometimes with no roof decoration and sometimes with a roofline of two half pediments sloping inwards and a rounded moulding as a barrelvault. The second coin type shows a similar structure but with a normal pediment and sometimes an arcuated lintel on the second story. While it is possible that these are but two variants of the same type, with the engraver of the first merely doodling at roof level, it seems more probable that there is an intended difference. It may be suggested that the half pediments are to be seen as continued to left and right of the building, the whole forming a continuous line of pediments and arches at the roofline of an arcade — the famous colonnades in fact along the main streets. The second type, more clearly a single structure, has walling clearly delineated on some examples at either side. It is a gate much like the gate of the Athena Polias sanctuary at Pergamum, and the steps would suggest that it is the gate, not of the city, but of another main building. At the cross roads of the main streets stood the gymnasium, and it is here that this gate would be most suitable, at the end of the colonnaded streets shown by the other coins. The relieving arch on the upper storey is clearly seen on the existing remains of one of Nicaea's city gates. 180-3

Most of the temples on the coins can be identified either by the cult figure or by an inscription mentioning the deity; but the buildings are usually undistinguished. That most commonly present is the temple of "Agathe Tyche" which together with the imperial cult clearly formed the central point of the city's worship. The capitals are of the Ionic order, and it is therefore possible that the fine three-quarters view of an Ionic temple represents this one. A fine coin, uncertainly attributed to Nicaea, depicting a monumental altar of Zeus which must have been as imposing as the Ara Pacis of Rome, should be noted. It could be that Nicaea was the mint city of this Bithynian issue since the altar of Zeus Litaos, found on other coins of Nicaea, shows the importance of the cult there. 186-7

A most unusual building, apparently religious in nature, occurs on a unique coin in Paris. It looks more like a gate than a temple, having two decorated pilasters at the side, with capitals of the Corinthian order and a heavy superstructure pierced by three windows. Its identification, not as clear to us as to the ancients, is given by three statues which stand in the openings in the facade. The central figure is an imperial statue of the so-called Prima Porta type, hand outstretched. This must be the emperor Septimius Severus, traces of whose name are inscribed around the coin. To the left, there is a similar figure in similar pose but hand not outstretched. The other figure on 189



Fig. 180 NICAEA: Arcade with garland on the upper story (Claudius A.D. 41-54) Berlin.



Fig. 181 NICAEA: Colonnade with line of alternate pediments and arches at the roofline (Claudius A.D. 41-54) BM.



Fig. 182 NICAEA: Gate reached by a flight of steps (Messalina A.D. 41-48) BM. See colour plate p. 14.



Fig. 183 NICAEA: Gate with walling on either side (Messalina A.D. 41-48) Paris.



Fig. 24



Fig. 159

Fig. 24 BIZYA: View of the city. Berlin.

Fig. 159 AMASEIA: View of the city. Price coll.



Fig. 329



Fig. 201



Fig. 49



Fig. 330

Fig. 329 TYRE: Baldachino or shrine with caryatid figures (Gallienus A.D. 253–268). Berlin.

Fig. 201 CYZICUS: The sanctuary of Demeter. Paris.

Fig. 49 PRUSA AD OLYMPUM: Scene of sacrifice before the round building of a shrine. Paris.

Fig. 330 ZELA: Portico within which altar (Caracalla A.D. 206/7) ANS.

NICAEA




Fig. 184 Gate to the sanctuary of Athena Polias from Pergamum (2nd. cent. B.C.) Pergamum Museum, Berlin, DDR. Courtesy Elisabeth Rohde.



Fig. 185 The Istanbul Gate, Iznik. Courtesy Rudolf Naumann.



Fig. 187 NICAIA: Three-quarter view of an hexastyle temple (Maximinus A.D. 235-238) BM.



Fig. 186 NICAIA: Temple of Agathe Tyche (Commodus A.D. 177-192) ANS.



Fig. 188 BITHYNIA: Monumental altar of Zeus (Trajan A.D. 98-117) BM.

Fig. the right, also wearing a short tunic, has the attributes, thyrsus and cantharus, of the patron of the city, Dionysus. This is in fact Severus' son Caracalla in his role as Neos Dionysus. The figure on the left is Severus' other son, Geta. All the figures stand on low bases and the general appearance of the building is of a quasi-oriental altar court, although the inscription around the coin shows that it is in some way connected with the imperial cult. The exact identification must await further evidence.

190 The most dramatic of the architectural coins, however, are those which commemorate the construction of the walls of the city in the mid-third century A.D. In 256 the invading Gothic tribes from the north completely overran the city, destroying much of it. On their retreat, it was rebuilt with new fine walls completely encircling it, which are still well preserved today. The date of the rebuilding is given by an inscription on the gate of Yenisehir and this coincides with the issue of a series of coins which show the great walls, two main gates heavily fortified, with short stretches of a wall easily defended from the many towers. If few of the buildings illustrated by the coins of Nicaea have been preserved today, it is doubtless because of the devastation caused by the Gothic capture of the city; but as the result of this same event we are permitted to see one of the best examples of Roman city walls to survive.



Fig. 190 NICAEA: The city walls (Gallienus A.D. 253–268) Berlin.



Fig. 189 NICAEA: Entry to a sanctuary, with statues of Septimius Severus and his two sons Geta and Caracalla (Septimius Severus A.D. 193–211) Paris.



Fig. 191 The ancient walls of Iznik, built after the destruction of the city by the Goths. Courtesy Rudolf Naumann.




Fig. 192 Inscription on the Yenischir Gate, Iznik, commemorating the completion of the rebuilding of the walls by Claudius Gothicus A.D. 268–270. Courtesy Rudolf Naumann.



Fig. 193 The remains of the terrace of the temple of Athena, Troy. Courtesy C.H. Anscombe.



Fig. 194 Sealstone (Sard), depicting Achilles dragging the body of Hector around a Roman Troy (Imperial period) BM.



Fig. 195 II.IUM, Asia: The only surviving coin presenting the temple of Athena (M. Aurelius A.D. 161–180) Berlin.

TROY

THE TEMPLE OF ATHENA

"And when they came to the temple of Athena in the upper city...she sent up her prayers to the daughter of Great Zeus: 'Oh, Goddess Athena, divine guardian of cities, break the spear of Diomedes and hurl him head-long from on high before the Scaean gates.'"

Homer, *Iliad* VI, 297 f.

Long after the great days of Homer's Troy, in the 3rd century B.C., the citizens built ^{Fig.} a new temple to Athena, proud of their sacred heritage and of their ancient cult image. The top of the hill on which the city stood was levelled to make room for a large sanctuary and the temple was erected within it. Parts of the surrounding colonnade and its gate have long been known and in recent years the foundations of the temple itself ¹⁹³ have been uncovered. An imaginative view of the city is preserved on a small seal-stone. The victorious Achilles drags the body of Hector around the walls of an incongruously ¹⁹⁴ Roman Troy, as in the Renaissance Christ was pictured in an Italian setting. In spite of the fact that most of the buildings on this seal cannot be identified, the temple of Athena is seen standing at the left hand limits of the city, slightly marred by a crack in the seal-stone.

A coin issued by the city under Marcus Aurelius, today surviving in a single ¹⁹⁵ specimen, gives us a further more detailed view of the temple. The building has a facade of six columns just as the archaeologists have conjectured from the remains; sculpture which once adorned the pediment is represented by a shield. The famous cult image, the Palladion, is brought out to the front, and it is shown on the exceptionally high base that is characteristic of many other representations of it on coins. This detail emphasizes that the statue was not like the monumental statue of Athena at Athens, overpowering by its very size; but that it was a small image which could be easily carried off, as indeed it was in Homer's epic by that guileful pair, Odysseus and ¹⁹⁶ Diomedes, to assure the fall of Troy.

The reliability of the temple coin is confirmed by the representation of the temple of Athena on a famous marble relief of the Roman period, the *Tabula Iliaca*. Coin and ¹⁹⁷ relief together establish what the archaeologists subsequently found in the Graeco-Roman levels: A temple in the dominant position of the city, a colonnaded portico surrounding the sanctuary, and an altar in front of the temple. Although the



Fig. 196 ARGOS, Peloponnese: Diomedes carrying off the statue of Athena Ilias (4th cent. B.C.) BM.



Fig. 197 The Tabula Iliaca, showing the walls of Troy and the temple of Athena in the upper city (1st. cent. A.D. ?) Museo Capitolino, Rome. photo. Alinari 27113.

Tabula Iliaca was the work of a western Roman artist, there is no reason to doubt its accuracy. Troy was a tourist spot during all of its historic existence. Indeed during the Roman period, the city's coin types continuously hark back to the stories of the Homeric age in contrast to the standardized types of the nearby military colony at Alexandria Troas. It can truly be said that Troy was never forgotten. For centuries collectors searched through Europe for coins minted in the ancient city. It should be remembered that between 1453 and 1822, Turkey closed the way to travellers. It was not until Schliemann's world-shaking discovery at Hissarlik in 1870 that the actual city of Troy was given again to mankind.

CYZICUS

"Coin types are notoriously bad evidence for architecture". This scepticism coming from Hasluck, the early 20th century historian of Cyzicus, reveals an unfortunate misunderstanding of the material. The numismatic evidence not only records the existence of ancient monuments of the city now lost, but also clarifies the ambiguities in literary and archaeological sources. Five buildings are represented on the coins of this city: three of them are temples, to Hadrian, Caracalla, and Hermes. Another two, it will be seen, are monuments connected with the Mysteries, the most important cult at Cyzicus.

One of the buildings has been incorrectly identified as a sacrificial altar of the temple of Hadrian because on some examples it appears at the side of the temple. It 198-9 appears sometimes on the right and sometimes on the left of the temple. Such numismatic juxtaposition does not signify that the so-called altar necessarily stood in reality next to the temple. Furthermore, a sacrificial altar would normally require the presence of a burning fire which is never found on the many representations.

The coins show us a round building with plain masonry walls, a two-leaved door 200-1 unusually high up on the facade, no steps leading up to it. The structure has no roof; but three female figures holding up torches decorate the rim. On one example, two



Fig. 198 CYZICUS: The temple of Hadrian and the sanctuary of Demeter (Caracalla A.D. 198-211) Paris.



Fig. 199 CYZICUS: The sanctuary of Demeter and the temple of Hadrian (early 3rd cent. A.D.) ANS.



Fig. 200 CYZICUS: The sanctuary of Demeter surmounted by statues and flanked by snake entwined torches (early 3rd. cent. A.D.) Paris



Fig. 201 CYZICUS: A similar view of the sanctuary of Demeter (Hadrian A.D. 117-138) Paris. See colour plate p. 102.



Fig. 202 CYZICUS: The Demeter sanctuary surmounted by a chariot group and figures (Gallienus A.D. 253-268) ANS.



Fig. 203 Fragment of an inscribed stele from Samothrace (late 2nd. cent. B.C.) Courtesy J.R. McCredie.



Fig. 204 Manuscript of Cyriac of Ancona depicting an inscribed stele with the name Asklepiades (14th cent. A.D.). Courtesy the Bodleian Library, Oxford, Ms. Lat. Misc. d. 85, fol. 140r.

horses, possibly a chariot, seem to be running to the side between the figures. Fig. Snake-entwined torches, an unmistakable symbol of the mystery cult, always flank the 202 building. It is difficult to distinguish Demeter from Kore on coins. Here, however, one can say with certainty that both mother and daughter are represented at the top of the building, accompanied by another of the many female deities involved in the cult. The central group of horses could certainly be an illustration of the rape of Persephone (Kore).

For the identification of this so-called altar coin, we can draw on an unusual amount of non-numismatic evidence. It will turn out however that this evidence will not only throw light on the coins but will, by a kind of reflection, be itself clarified and strengthened by the coin. From Samothrace we have extant fragments of several reliefs which were copied by the famous traveller Cyriac of Ancona on his trip to the East in the 15th century, whose drawings are preserved in several manuscripts.



Fig. 205 Reconstruction of the Arsinoeion at Samothrace, (289–281 B.C.) From A. Conze, A. Hauser, G. Niemann, *Archäologische Untersuchungen auf Samothrace*, Wien, 1875.



Fig. 206 Elevation of the Sphinx tomb/shrine from Xanthos, facade B of Building H combined with pediment in the British Museum (470–460 B.C.) Courtesy H. Metzger and D.E.L. Haynes.

One of the Samothracian reliefs actually preserved was a stele dedicated by a citizen Fig. of Cyzicus, one Asklepiades, son of Attalos, late in the 2nd century B.C. Asklepiades 203 was sent to Samothrace for some purpose — the inscriptions are not clear on this point — connected with his profession as architect. The building engraved on his stele decorated other Samothracian stones, which were also the gifts of citizens from Cyzicus, and all these visitors from Asia Minor were initiates both at Cyzicus and at Samothrace.

It is surprising that the building pictured on the Samothracian reliefs and in the 204 manuscripts of Cyriac is so close to the so-called altar on the coins of Cyzicus, that it could easily be called the model for the coin-type. The manuscripts have some charmingly naive variations introduced by the copyists: male instead of female figures, staffs instead of small torches. These details are consistent on the coins. By a recognizable convention, the figures shown above on the roof could actually have decorated the interior of the building. The monumental torches shown to the side of the building on the coins were in reality, by a similar artistic convention, in front of the building as is clearly shown by the manuscript and relief.

The building on the Samothracian reliefs — in each case the badge, as it were, of citizens of Cyzicus — is exactly the same as that found on the coins of Cyzicus. More important, the fact that the building is found on coins minted in Cyzicus also means that the building was situated in Cyzicus. Mrs. Lehmann has recently recognised in this a "Samothrakeion" and has described it as a copy of the famous Arsinoeion of Samothrace, derived from the great cult of the island.

In its style of architecture, the Cyzicus building bears some resemblance to the 205 Arsinoeion, dedicated by Queen Arsinoe at Samothrace in the early 3rd century B.C. In adopting the form of a round building, Cyzicus deliberately imitated the Samothrace Rotunda. But there the similarity ends. Missing is the most unusual part of the Arsinoeion, the upper drum of solid masonry, decorated with engaged columns and a rank of windows. Missing also is the domed roof with a prominent lantern at its top, restored by the archaeologists on the roof of the Arsinoeion. In addition, the door positioned as if it was a window means that the Cyzicus monument did not serve the same purpose as the Arsinoeion: The Samothracian building with its steps was obviously accessible to the outside world, while the Cyzicus building does not appear to have been.

What was the function of the Cyzicus monument? The door-window itself, curiously enough, supplies the answer. Just such a detail has been found on actual buildings and is represented on coins and other objects. Called a "sacred portal," it was from prehistoric times onward the symbol of structures that were tomb/altar/shrines at one and the same time. One reconstructed most recently is the Sphinx monument at Xanthos where a series of false door-windows, framed with typically Near Eastern receding frames or embrasures, decorates the facades and pediments. The Cyzicus monument, if it has a roof at all, undoubtedly had a flat roof which may be compared with the eastern altar/shrines, such as the so-called Fire Temple on the coins of Persia, 50-1



Fig. 207 Detail of the relief from the gravestone of Artalos (mid. 2nd. cent. B.C.) Louvre. Courtesy photo. Musées nationaux, Paris



Fig. 208 CYZICUS: The round aedicula of Demeter (c. A.D. 200) Paris

and it may therefore itself have been a tomb/altar/shrine, a most appropriate edifice for ^{Fig.} a mystery cult that celebrated the death of Persephone.

By a rare coincidence, there is preserved a grave relief of another citizen of Cyzicus, named Attalos, son of Asklepiodoros, who was not only an architect, a devotee of the Samothracian and Cyzicene Mysteries, but also the father of our first architect, Asklepiades. The miniature building of the relief in the hands of a female figure is ²⁰⁷ without doubt a copy of the Arsinoeion. It is not the tomb/altar/shrine of Cyzicus. The upper drum with engaged columns, the hallmark of the Samothracian Rotunda, is clearly depicted. More important, the very top of the miniature building, obviously broken off, was a lantern which duplicated the lantern of the actual Samothracian Rotunda, a truly exceptional detail. All other known examples of such lanterns are found only on coins and ancient models. Why the father-architect was favoured with the Samothracian monument, and the son with the Cyzicene building, approximately 150 years after the Arsinoeion was constructed, even the good Cyriac obviously could not know.

The lantern above a domed roof, however, is found on another coin-type of Cyzicus. ²⁰⁸ It appears on an open round building with peripteral columns. Tie-beams between the columns form a balustrade around the whole building. In the centre, the cult image of Demeter or Kore stands on a prominent base. Although the building resembles the Arsinoeion in some respects, it lacks the enclosing walls, stairway, peripteral steps, and the very characteristic upper drum and windows. But the domed roof with lantern of the Rotunda is a close architectural parallel.

It follows, therefore, that in the cult of Demeter at Cyzicus, there were two sacred buildings, both used in some way or other for the Samothracian Mysteries and both with architectural forms inherited from Samothrace. One may have been a tomb/altar/shrine. The other may have had the same function as the Arsinoeion. Unfortunately, as in all mysteries, what took place in Arsinoe's sacred building has not yet been revealed.

It is possible that Cyriac saw these two cult buildings at Cyzicus. The creatures of the Mystery cult, Demeter, Kore, horses, and others of the Samothracian records, appear in Cyriac's report of the temple of Hadrian at Cyzicus, the manuscripts even preserving the same kind of errors, mixing up the sexes (the three graces are shown as males!), changing torches to staffs, etc. The manuscripts do not make it clear whether the statues of the deities involved in the Mysteries decorated the sanctuary of Demeter and Kore or the temple of Hadrian, or both. Very little of the temple has been found; its unmistakable octastyle facade, however, is confirmed by the coin representations. Crypts, for the practice of Mysteries, were discovered under the temple and Cyriac's drawings suggest that the temple was also used in the celebration of the ritual.

The connection between the Imperial and Mystery cults was close: emperors and empresses were initiated and thereby achieved mystic union with other deities. Faustina at her death was worshipped as a new Kore Soteira, the principal deity of the




Fig. 209 Drawing of the temple of Hadrian at Cyzicus in the Destailleur copy of Cyriac (14th cent. A.D.) Courtesy B. Ashmole.



Fig. 210 CYZICUS: Temple with herm as the cult image (Faustina I c. A.D. 145) Paris.

city and of the Mystery cult. Hadrian may also have had a place in this Pantheon as a neos Hermes. In Cyriac's drawing of Hadrian's temple, the circle of the pediment is filled not with the bust of the emperor, as has always been assumed, but with a head set on a herm. This fact is confirmed by the Byzantine author Malalas who reports — the Greek has always been translated without a close look at the drawing — that ²⁰⁹Hadrian placed a marble herm with his own bust at the "top of the temple." A herm ²¹⁰with the head of the god Hermes appears as the cult image of another Cyzicus coin-type. Although herms of rulers are known, the herm of an emperor in this context is so extraordinary that it must have had some meaning. Was Hadrian also honoured in the temple of Hermes, the god of the Mysteries, the god who played the part of guiding the dead to the kingdom of Hades? Caracalla also had a temple at Cyzicus which appears on the coins; but whether he too played a part in the Mysteries is not known.

Nearly all the coins of Cyzicus show that the imperial cult was inextricably linked to the worship of the great gods of Samothrace, the sacred island that gave Cyzicus its cult, its religious conventions, and, to some extent, its architecture.

PARIUM

THE TOMB/ALTAR/SHRINE

Some of the most adventurous, although not the most artistic of Anatolian die^{Fig.} engravers, produced the series of 3rd century A.D. coins of Parium. By using the convention of "above instead of behind," they were able to show on a single coin both an arch and portions of a monumental altar court behind it.

Several different examples represent the triumphal arch, made of masonry blocks,²¹¹ with four columns on the facade, and three entrances between the columns. An elephant chariot group is shown above the arch, an unusual motif for arches. One other, known from coins, is the arch of Domitian at Rome, and Malalas described yet another²¹² at Antioch in Syria. Several other details are shown as well on the arch-coins. One is a naked male figure with spear of staff who seems to stand above the elephants on one example, or between their heads and tails on another. Two statues appear either above²¹³ the arch or at the sides on apparently separate columns.

The whole design becomes clearer when the arch is removed, as it were, to show what is behind. This occurs on another series of 3rd century A.D. coins to reveal an altar which is quite unlike any other found on coins. Here the two statues on columns appear attached to the masonry wall of a court in which an altar stands. The male figure also pictured on the arch-coins is now shown decorating the altar. The monument itself is set high above the pavement of the court and is reached by a flight of steps.



Fig. 211 *PARIUM*: Gateway, surmounted by elephants and figures (Gallienus A.D. 193-208) Berlin



Fig. 212 *ROME*: Arch (Domitian A.D. 81-96) Paris



Fig. 213 PARIUM: Gateway showing elephant heads and statues (Gallienus A.D. 253-268) Berlin

- Fig. Some examples show a chariot group above the altar instead of the male figure.
- ²¹⁵ Within the chariot stands a radiate figure who could be Apollo Helios or the Roman emperor. As mentioned previously, by far the best known building at Parium was the altar which Hermocreon built from stones taken from an oracular temple of Apollo Aktaios and Artemis that stood outside the city. This was famous in antiquity for its size and beauty. The Apollo Aktaios of the city's Hellenistic tetradrachms shows that this cult was probably the leading cult of the city. It is tempting to connect the "Apollo" of the chariot group on our coin with Apollo Aktaios and so suggest that this monument is the altar of Hermocreon. Regrettably there is insufficient evidence.
- ²¹⁶

The identity of the nude male figure, however, is revealed by several examples of the coin which show him flanked by snakes. He is Parius, one of the Ophiogeneis, who were changed from snakes to human beings, the legendary founder of the city which bore his name. He appears here in the very moment of metamorphosis from snake to human. As a hero, his cult was chthonic, his tomb was an altar. Athenagoras reports a tomb at Parium. The passage is admittedly garbled because at one point he seems to refer to Alexander, inventor of snake-shaped Glycon, and at another to Paris of Troy where Athenagoras quotes Homer, in both cases apparently referring to the same person. But he may even have meant Alexander the Great whose father, according to legend, was Zeus in snake form! The names Paris and Parius are almost the same in Greek, as well as in other languages. Both had equal antiquarian relevance for Athenagoras. But the coins would suggest that the tomb was almost certainly that of Parius.

The altar dedicated to the cult of Parius may also have been dedicated to Apollo who lost his temple outside the city. That the famous altar of Apollo Aktaios stood within an altar court is suggested by Strabo's remark that its sides were a stade in length. Strabo was undoubtedly referring not to an altar but an altar court. The altar on the Hellenistic coins which was discussed previously is assumed usually to be ⁹⁸ Strabo's monument; but it is only a small puteal for sacrifices, the vase and fire indicating the small size. As an altar court with a tomb/altar/shrine, the Roman coins of Parium depict a typical preellenic structure, the artistic origin of which is in the oriental, non-Greek world.



Fig. 217



Fig. 221



Fig. 32

Fig. 221 EPHESUS: The temple of Artemis. BM.

Fig. 32 EUMENEIA: The temple of Artemis Ephesia. BM.

PARIUM



Fig. 214 PARIUM: Altar surmounted by a statue of the hero Parios set within an open court (Gallienus A.D. 253–268) Paris



Fig. 215 PARIUM: The altar of Parios surmounted by a chariot group (Gallienus A.D. 253–268) BM.



Fig. 216 PARIUM: Silver tetradrachm depicting Apollo Aktaios at an altar (c. 150 B.C.) Paris.

PERGAMUM

THE ALTAR OF ZEUS

"And to the angel of the Church in Pergamum write: These things saith he which hath the sharp sword with two edges. I know thy works, and where thou dwellest even where Satan's seat is....where Satan dwelleth...."

Revelations II, 12, 13

The great "altar" of Pergamum shown on the coin of Septimius Severus was ^{Fig.} thought to be the seat of Satan mentioned in Revelations. There is no way of proving ²¹⁷ or disproving this, yet it is noteworthy that the concept of an altar as a throne is known from very early times. A century after St. Paul, the Latin writer, Lucius Ampelius, called the Pergamum altar, one of the wonders of the world, and it is certainly one of our most interesting numismatic wonders because so much of the famous monument has been discovered. It must be said at once that the term "altar" used for the building is misleading: The structure is a monumental colonnaded altar court on a terrace with a very elaborate entrance portico.

An early 20th century numismatist insisted that the coin did not help in the reconstruction of the altar court, but that the monument, once restored, helped to explain the coin! The opposite, as it turned out, was actually the case. The first reconstruction of the marbles in the Pergamum Museum of Berlin, made without an understanding of the coin conventions, was universally recognized to be incorrect. Even as the altar court appears now in the recent reconstruction, to some extent based ²¹⁸ on the coins, there is more than a suspicion that the die maker's image and conventions were not sufficiently analyzed.

At one time the altar court was set up with two stairways in the facade of the entrance. Now the entrance has one monumental flight that leads up to the colonnade of the court terrace. The coins display the sacrificial altar in the centre of the facade, but this altar actually stood behind within the court. The steps shown below the small altar, spreading out as they descend, were taken to represent the monumental entrance stairway.

A question will immediately arise in the mind of the reader. If the altar itself should be considered as an object brought out from the interior, why wasn't this true of the stairway immediately below it? The answer is that the steps should perhaps be considered exactly in that way and the small altar may be reconstructed with the steps as a stepped altar, a form well-known in ancient art and one which appears on a good ¹⁵ number of coin-examples. Thus the steps themselves would serve the double function ²⁵⁷

of showing the exterior and interior of the building. The tiny sacrificial altar of the ^{F19} actual reconstruction in the Museum does not begin to measure up in size to the altar as indicated on the coins and, of course, it lacks the stepped podium just suggested. The die maker seems to have been especially impressed with the size of the altar and its podium. The baldachino was undoubtedly of bronze and was probably erected in the Imperial period when a Roman altar replaced an earlier Hellenistic round edifice. On the tomb of the Haterii there is found a good example of just such a baldachino which ²¹⁹ provides an answer to those who doubt the practicality of such an arrangement.

In addition to the sacrificial altar and baldachino, the artist has also emphasized on the coin the colonnades and bulls. The columns seemed far more important to him than the famous sculptured frieze which holds an honoured place in every book on Hellenistic art. The bulls shown in front of the monumental portico screen the famous sculptured frieze of the portico from our vision. We may suppose that they have been given this prominence because to the visitor they were indeed typical of the altar itself. Possibly we have here a remnant of a familiar Near-Eastern tradition, lines of facing animals framing the sacred way to the sanctuary. Just as at Didyma we have lines of facing figures, so at Pergamum we may have had a line of facing bulls.

Another objection to the Berlin reconstruction concerns the statues placed on top of the colonnade at roof level. In this instance the archaeologists followed too trustingly the picture on the coin, without recognizing the numismatic convention of "above instead of behind." In other words, the statues now on the colonnade should have been placed behind in the courtyard. Fragments of figures found in the excavations identify the Pergamene figures as Poseidon, Cybele, and priestesses of Athena. The coins of ¹⁶⁵⁻⁷² Neocaesarea show a similar altar-court entrance and indicate that there were various statues in the court behind the gate.

No other coin type is exactly like the Pergamene issue, but another building never associated with it before is amazingly similar: The temple of the Severi in Leptis Magna ²²⁰ in North Africa. There is every reason to believe that the same artist who built it worked on the repair of the Pergamum altar in about 200 A.D. The architect, the master builder of the North African Severan city, is reported to have come from the Near East; the marble for his temple at Leptis was actually imported from near Pergamum. In regard to two architectural elements, the monumental stairway with spreading steps, and the double podium which supports the columns, the temple is similar to the "altar." The temple has the usual uninterrupted facade of columns which in proportion to the platform are much taller than those of the reconstructed altar. This, we might suggest, should perhaps be altered in the latter building.

The whole design of the Pergamum "altar" is typically Near Eastern, with prototypes in Hittite, Mesopotamian, and Iranian art, where men worshipped in sanctuaries open to the skies. The interpretation of the coins is perfectly intelligible in the context of the conventions outlined elsewhere in this book, and they lead to a more plausible reconstruction of the altar than did the archaeological remains alone.



Fig. 217 PERGAMUM: The altar of Zeus. The portico has been opened to insert the stepped altar and baldachino (Septimius Severus A.D. 193–211) See colour plate p. 119.




Fig. 218 The reconstructed altar of Zeus from Pergamum (180–160 B.C.) Pergamum Museum, Berlin, DDR. Courtesy Elisabeth Rohde.

PERGAMUM



Fig. 219 Altar and baldachino from the Haterii sarcophagus (late 1st. cent. A.D.) Lateran Museum, Rome. photo Anderson 1875 B.




Fig. 220 Restoration of the temple of the Severi at Leptis Magna (c. A.D. 216). Courtesy J.B. Ward-Perkins.



Fig. 221 EPHESUS: Newly discovered coin showing the temple of Artemis, with details of sculptures in the pediment, at the base of the columns, and within the cella (Maximinus A.D. 235-238) BM. See colour plate p. 120.



Fig. 222 Elevation of the facade of the temple of Artemis at Ephesus made by S. Shaw in 1945. The steps in fact continued across the facade, and there were no parotids. Courtesy Metropolitan Museum of Art.

EPHESUS

THE TEMPLE OF ARTEMIS

"For a certain man named Demetrius, a silversmith which made silver shrines for Diana....said...."This Paul has persuaded and turned away much people."..... and they were full of wrath and cried out saying, "Great is Diana of the Ephesians."

Acts 19, 24-28

A recently discovered coin preserves one of the most exciting views of the great temple of Artemis of Ephesus which was once reckoned amongst the seven wonders of the world. The Artemisium was built in the 4th century B.C. on the model of an earlier temple erected in the time of Croesus, which had been burned to the ground by the infamous Herostratus. Virtually unchanged thereafter, the coin of the 3rd century A.D. shows us how the temple looked at the time of St. Paul's visit to the city. Today the temple of Ephesus is preserved only as a line of foundations and a few beautiful architectural fragments.

The reconstruction is based on a number of different coin types, as well as on the finds in the excavation of the site. The features that impressed Pliny the Elder were the sculptured drums and pedestals, fragments of which are now in the British Museum. One of the drums is nearly complete. Early reconstructions of the temple placed the round sculptured drums upon the square pedestals as decorations of the columns of the facade. The only coin which might suggest an arrangement is a silver cistophorus, ornately decorated, which shows prominent horizontal bands at the base of the columns. We believe that the artist wished to indicate in this way that there was decoration in this position — not that this was a decorated drum on a square plinth. The facade columns were decorated only with the round drums; the rectangular pedestals stood elsewhere. The Ionic order of the capitals shown on the coins is also confirmed by the finds in the excavations.

Further details appear in the pediment of the coins. Three windows figure prominently and in addition there are four statues, two recumbent in the angles and two probably female standing on either side of the central window. Each has one arm raised towards the window and one lowered. These may have been the famous Amazons which decorated the 5th century B.C. altar and which may have been moved to the pediment of the 4th century temple in the rebuilding. The large circular detail in the apex of the tympanum appears to be a head of Medusa decorating the end of the great beam that supported the roof.



Fig. 223 Column base from the temple of Artemis, as originally reconstructed on a rectangular plinth. Courtesy D.E.L. Haynes.



Fig. 224 EPHESUS: The temple of Artemis, a decorative representation on a silver cistophorus (Hadrian A.D. 117–139) Corpus Christi College Cambridge



Fig. 225 MAGNESIA AD MAEANDRUM, Asia: Temple of Artemis Leukophryene (Trajan A.D. 98–117) Righetti collection.



Fig. 226 LAODICEA, Asia: Caracalla sacrificing in front of a hexastyle temple with windows in the pediment (Caracalla a. A.D. 215) Berlin.



Fig. 227 Clay model of a shrine from the Argive Heraeum (c. 700 B.C.) Courtesy National Museum, Athens.



Fig. 228 Model of a shrine of Ashtoreth from Beisan, Palestine. (12th cent. B.C.) Courtesy the University Museum, Philadelphia.



Fig. 229 EPHESUS: Temple of Artemis with a priestess (Prytaneia) in the central window of the pediment (Antoninus Pius A.D. 138-161) Berlin.




Fig. 230 West facade of the church of Mshabbak, Syria (4th cent. A.D.) Courtesy Princeton University Press

Fig. Most important are the three windows. Recently, a door or window jamb which once formed one of the pedimental windows was discovered, built into the Byzantine church near the site of the temple. There are many parallels now known both on the coins and on actual buildings of the Near East, but the earliest known example is that of the Artemisium. Evidence of such pedimental openings, however, is available from earlier times: In the Greek world we have the Argive Heraeum model; from Egypt a tomb relief found at Saqqara; and from Palestine, a 2nd millenium model of a shrine. In each case, the window appears to have served a specific ritualistic function, an epiphany at which the deity or the deceased appeared. At Ephesus an epiphany is specifically mentioned in an inscription (Dittenberger SIG 867.35) and there are several parallel Graeco-Roman shrines with pedimental windows at which there was probably a similar epiphany. Pliny (Natural Histories XIV 1, 9) tells us that at Ephesus there was a staircase to the roof level which, for all practical purposes, should have led to those openings in the pediment. A coin, a single specimen in the Berlin collection, appears to show a figure standing in the central opening, in the very act of an epiphany.



Fig. 231 Frieze on the north side of the choir depicting the epiphany of Christ (?) at St. Paul-les-Dax, France (12th cent. A.D.). Courtesy Akademie Verlag, Berlin, DDR.

In front of the temple was a court in which a great altar stood, recently recovered and restored by the archaeologists. We can now visualize the people assembled before the temple waiting for the epiphany of the goddess or a symbol of her divinity in the windows. Such a ritual is known from remote Mesopotamian and Egyptian origins.

Christian architecture continued the tradition of Ephesus as Ephesus had continued the traditions of the Orient. Early Christian churches provide many close parallels. A tomb relief at St. Paul-les-Dax leaves no doubt about the functions of the pedimental window: Christ actually rises through the window. The windows of the cathedral of St. Pantaleon at Cologne are a vivid example of the medieval age. The tripartite design is still to be seen in the sanctuary windows of modern churches.

Traditions follow traditions: Long ago crowds of worshippers assembled in the courtyard of Uruk and of Babylon and of Ephesus. Today crowds wait in patient faith in the court in front of St. Peter's to receive the blessing of the Pope standing at the central window high above them.



Fig. 232 Facade of St. Pantaleon Church, Cologne (A.D. 980) Courtesy the Pharramt, St. Pantaleon.



Fig. 233 Crowd outside St. Peter's, Rome, receiving the blessing of Pope Paul, Courtesy Religious News Service, Wide World Photos.

SAMOS

THE NAISKOS OF THE TEMPLE OF HERA

One of the longest series of coins to depict a single building — from Domitian to Fig. Gallienus — represents the famous temple of Hera at Samos and her cult image. The 234-5 sanctuary was as ancient as it was renowned, for the site was considered sacred as early as 2500 B.C. The latest results of the excavations show that the gigantic Ionic octastyle temple of the 6th century B.C. stood at the West end of a vast temenos. An altar was in front, to the East of the temple, but their facades were not exactly in line. The sacred lygos tree, famous in antiquity, stood behind the altar within a separate courtyard. Between the archaic temple and the altar there was built a small Roman Doric shrine with six columns on its facade.

With the excavations now quite advanced, the coins play an important role in settling problems of the architectural scheme. They show the altar and tree either on 236 the left or right of a temple. This indicates, as we know from the excavations, that the altar and tree were in fact positioned in front (a good comparison is found on the coins 237 of Tyre which show altar and tree in front). An illustration of the convention used on the Samian coins is found on those of Tripolis where the gate of the sanctuary is 238 depicted to the side of the Temple of Zeus Hagios.



Fig. 234 SAMOS: The aedicula housing the cult image of Hera (Etruscilla A.D. 249-251) BM.



Fig. 235 SAMOS: The Ionic temple of Hera (Domitian A.D. 81-96) BM.



Fig. 236 SAMOS: The aedicula of Hera with altar and Lygos tree to the right (Gordian III A.D. 238-244) Paris.



Fig. 237 TYRE, Phoenicia: The temple of Astarte with altar and date palm in front (Elagabalus A.D. 218-222) BM.



Fig. 238 TRIPOLIS, Phoenicia: The temple of Zeus Hagios with the gate to the sanctuary on the left (Caracalla A.D. 215-6) BM. See colour plate p.32



Fig. 239 MILETUS, Asia: Naiskos of the temple of Apollo at Didyma (Gordian I, II, and Balbinus A.D. 238) Paris.

Some claim that the temple of the coins of Samos represents the large Greek Ionic temple, others, the small Roman Doric building. It has also been claimed that the roof of the Greek building was never completed and that the temple was abandoned in the Roman period and turned into a picture gallery. Because the Roman architect Vitruvius called the temple of Hera a Doric shrine, it was inferred that during the Roman period the goddess was housed, not in the Greek building, but in the Doric. There is, however, no archaeological evidence that the Ionic building was ever abandoned. On the contrary, there is proof that a monumental entrance stairway was constructed to the complex during the Roman period. Also we know that many temples beside housing the deity were, like modern cathedrals, the focal point of tourists, treasure houses of the arts. Fig.

The image of Hera shown on this long series of coins was the actual cult statue of the earlier Greek period. It is the typical figure created in the Hellenistic period, based on the prehellenic type like so many Anatolian cult images. The 'temple,' unusually stereotyped for such a long series, is invariably shown with Ionic capitals, never with Doric; and with the exception of the earliest series it appears with an arcuated lintel. Furthermore, when fluted, the columns almost always appear with spiral fluting, a distinctly Roman form. The building cannot represent the 6th century B.C. Ionic temple, nor on the other hand, the Roman Doric temple. The details are so consistent that the type with arched lintel must refer to an interior, free-standing naiskos or aedicula in which the cult image was housed in Roman times. The coin of Domitian 235 alone shows the facade of the Ionic temple. There is a very strong possibility that the arched lintel, so rarely found in actual architecture, was present on this structure. At Miletus, similarly, the coins show not the great facade of the famous Didymaion, but the naiskos that housed the cult image within the open courtyard. In the same way the artists at Samos could have been hinting that the great archaic shrine was actually open to the skies, as some archaeologists have suggested, and as was certainly the case at Didyma. 239

It does not seem possible that a city would have celebrated a temple on its coins with such regularity if the temple had not been the principal shrine of the principal deity. Nor do we believe that the architectural details would be so consistent if they were not recognizable as indicating an actual structure. Altar, Lygos tree, and Ionic facade are all accounted for by the coins. These must therefore illustrate for us the naiskos, the Holy of Holies, in which the cult image of the goddess stood, the essential element in the worship of the sanctuary.



Fig. 240 SARDIS: Cult image of Artemis/Kore with pomegranate and corn ears (Commodus c. A.D. 175) BM.



Fig. 241 SARDIS: The temple of Artemis/Kore, symbol of the city on a medallion struck for the League of Ionian cities (Aurelius c. A.D. 140) Paris



Fig. 242 SARDIS: The three neocorate temples of the imperial cult, and the temple of Artemis/Kore (Elagabalus A.D. 218–222) BM.



Fig. 243 EPHESUS, Asia: The four neocorate temples – to Artemis, Hadrian, Caracalla, and Elagabalus (Elagabalus A.D. 218–222) BM.

SARDIS

Through the work of archaeologists in recent decades, we now know that many of ^{Fig.} the great cities of Western Asia Minor had a history as ancient as Troy's. Such a city is Sardis, the site of one of the largest excavations of modern times. Although a considerable number of monuments has been found, only one temple has so far been excavated. It was dedicated to Artemis and was the centre of the main cult of the city. The coins show us her cult image in a strange pre-Greek form, decorated with ears of corn and pomegranate, which, as the archaeologists have surmised from other evidence, link her in turn with the neighbouring cemetery. For these are the attributes of Kore, ²⁴⁰ the goddess of the Mysteries.

The temple of Artemis/Kore was erected in the Hellenistic period. It was once thought that it was originally constructed with two separate cellae and that it was also dedicated to Zeus Lydios, but the archaeological evidence suggests that the cella was not divided until a later period. A colossal head of Faustina the Elder was found near the centre of the temple together with a portion of the base *in situ*. Faustina, whose daughter at Cyzicus became identified with Kore Soteira, was thus at Sardis given a place in the temple of Artemis/Kore. Kore herself, as we know from the coins, continued to be the main deity of the shrine late into the Roman period, and her cult image stood on a base found in the western cella. Recent excavations at the West end of the temple revealed a stepped altar. Its foundations are dated to the 6th century B.C., and the whole site had an even earlier history as a sacred area. The coins of Sardis show Artemis/Kore in her temple, and it is her temple that is used on the coins of the ²⁴¹ League of Ionian Cities, as a symbol of Sardis, with the cult image of the goddess dominating the facade.

The temple of Artemis/Kore is also represented on coins which show it with other temple buildings. One issue represents four buildings, two of them identified by cult images of Artemis and an emperor. The inscription around the coin demonstrates that Sardis was honoured three times with the neocate title, probably under Hadrian, Antoninus Pius, and Elagabalus. Unlike the great Artemis of Ephesus, the people of Sardis did not gain the prized neocate for the temple of Kore. A comparison of the coins of Sardis with the numismatic conventions of other cities shows without any doubt that the four-temple-type does not represent four aspects of the shrine of ²⁴²⁻³ Artemis/Kore as was supposed by the early archaeologists and by writers of recent handbooks. The coins show that there are at least three temples dedicated to the Imperial cult, still to be discovered by the archaeologists.

Another temple occurs on the coins of Sardis quite different in appearance. This is the shrine of Aphrodite of Paphos, clearly modelled on the well-known sanctuary in Cyprus and its prehellenic prototypes. The coin almost certainly represents a sanctuary located at Sardis, for it is rare that a city shows on its coins any but its local



Fig. 244 SARDIS: The great altar of Zeus Lydios, with the cult statue and a tree to the right. Fine figure sculpture is shown as the relief decoration on the altar (Elagabalus A.D. 218–222) Paris. See colour plate p. 49



Fig. 245 SARDIS: The great altar of Zeus Lydios with statues of Heracles and Zeus Lydios (Philip I A.D. 244–249) Courtesy Museum of Fine Arts, Boston.

SARDIS



Fig. 246 SARDIS: Statue of Heracles and the bull (Caracalla A.D. 211-217) BM.



Fig. 247 A and B SARDIS: Zeus Lydios and Heracles on the two sides of the same coin (c. A.D. 225-250). BM.

monuments. In the same way, the shrine of Aphrodite Paphia on the coins of Pergamum illustrated her sanctuary in Pergamum, not Cyprus. But the architectural pattern of a traditional Oriental tower and courtyard was dictated by the ancient cult of Cyprus and the great temple there.

By far the most spectacular coin of Sardis is that which shows a monumental altar, the size of which is emphasized by the statue of Zeus Lydios on a pedestal beside it. The accompanying tree refers to a pastoral setting much as is found on many other coin types. The decoration of the altar consists of three statues in high relief seen against a masonry wall. The coin is precious evidence for other altars such as the Hellenistic altar at Priene where only one such statue has survived, and the 5th century B.C. altar at Ephesus, which was decorated with the famous Amazons sculptured by Pheidias, Polycleitus, Cresilas and Phradmon.

The altar of Zeus Lydios is identified by the god standing on a pedestal next to it, a prehellenic deity worshipped widely in the cities of central Asia Minor. Among the numerous archaeological references to this god at Sardis is a head recently found and thought to have been the head of a cult image. It is also suggested that this cult image was of Zeus Poleus or Zeus Olympios. However, no cult image or cult building of Zeus Lydios has as yet been discovered at Sardis. Given the great antiquity of the cult of the deity, the altar may have stood alone, open to the skies in a sacred grove, symbolized by the tree, at a distance from the city. The altar itself would then have been the focal point of the worship of the god.

A variant of the coin places a statue of Heracles dragging a bull by the horns to the left of the altar, thus balancing that of Zeus Lydios on the right side. The same Heracles and bull, undoubtedly a statue group, appear more clearly on another coin.



Fig. 248 SARDIS: Queen Omphale of Lydia dressed in Heracles' lion skin (c. A.D. 175) BM.



Fig. 249 SARDIS: The bull of Heracles before two altars on which snakes (mid. 3rd. cent. A.D.) BM.



Fig. 250 Heracles and the lion on the back of a model depicting a shrine of Cybele (mid. 6th. cent. B.C.) Courtesy G.M.A. Hanfmann.

Fig. 249. And still another issue represents Zeus Lydios, so named by legend with his image on
 247 the obverse and Heracles on the reverse. So many coins represent the famous hero that
 he must have played as important a part in the life of the city as Zeus Lydios. Mythology in fact explains this. Heracles was sent as a slave to the Lydian Queen Omphale
 to expiate the murder of Iphitus, brother of Iole, one of his loves. A coin of Sardis
 248 illustrates his affair with the legendary Omphale in dramatic manner: the hero appears
 on one side, the Queen on the other, naked except for Heracles' lion skin draped
 around her shoulders. From this compromising scene, we can understand how the
 legend grew that Croesus and the whole dynasty of Lydian Kings were descended from
 Heracles and Queen Omphale. Thus both Heracles and Lydian Zeus belong to the local
 Lydian cycle of Sardis' history.

Numismatic evidence also links Heracles with another prehellenic cult of Sardis. The
 249 same bull which formed part of the Heracles-statue group, appears on another type, in
 the same attitude, vainly stretching its forefeet in resistance. But this time the bull is
 shown with two snakes on low pedestals. The snakes were without doubt part of the



Fig. 251 Facade of the same model as Fig. 250, showing the image of Cybele flanked by snakes (mid. 6th. cent. B.C.) Courtesy G.M.A. Hanfmann.

same group as the statue on the altar-coin. Since Heracles appears so early in the myth-history of Sardis, his snakes can be associated with two equally unusual snakes that decorate a 6th century B.C. model recently found at Sardis. The snakes frame the figure of Cybele portrayed in half-round on the long side of the rectangular model. Heracles and the lion appear on the back of the shrine. The other sides are decorated with figures of moving females and lions in panels. This decorative pattern can be paralleled in Hittite art and Cybele, as Magna Mater, also goes back into pre-history. On the eastern bank of the river Pactolus, the archaeologists have discovered an altar together with a Lydian graffito naming Cybele. Lions decorated its corners, as lions decorate the model. It seems reasonable to conclude that the model was a representation of the altar which stood alone and open to the skies almost exactly in the manner of the Zeus Lydios altar of the coins. The Lydian monument was undoubtedly an altar/shrine.

The altar-coin which linked Zeus Lydios, the great male god of earliest Lydia, with Heracles, the founder of the Lydian royal dynasty, is now linked with an equally early deity worshipped at Sardis, Cybele, Magna Mater. In addition, the altar represented on the Roman coin, purely Greek in style but similar in function to the pre-Greek altar of Cybele on the hillside (the Hittite Magna Mater always emerged from a mountain!) illustrates the continuity of an ancient form and ritual for over a thousand years. Myth and legend grow into history as archaeology makes discoveries. We may yet find remains that will throw further light on the prehellenic cults and monuments of Cybele, Heracles, and Zeus Lydios. Meanwhile, the main cult within the city was that of Artemis/Kore — a goddess whose attributes show that her origins were shrouded in the prehellenic past. As at Ephesus and Perga and other cities, she assumed a Greek name and a Greek temple; and it was her building that the people of Sardis recognized as a symbol of their city.



Fig. 252 SELGE: Sanctuary of Zeus and Heracles on a high masonry terrace (Alexander Severus A.D. 222–235) Berlin. See colour plate p.154.



Fig. 253 SELGE: Sanctuary of Zeus and Heracles (Alexander Severus A.D. 222–235) Paris.



Fig. 254 Painting with scene of ritual between sacred trees, from Mari on the Euphrates (18th cent. B.C.) Louvre. Courtesy A. Parrot.

SELGE

THE PREHELLENIC SANCTUARY

The most extraordinary monument found on the coins of Anatolia is the one at Selge. Many attempts to identify the structure have been unsuccessful. The tree-like objects on high pedestals are set on a high terrace. In front of each stands an altar and to the left and right are columns supporting eagle and Nike. A high substructure supports the terraced platform reached by a monumental stairway to the right. Some examples show two ranks of steps.

The thunderbolt and club symbolize Zeus and Heracles, but the cult objects and the architectural form of the monument point to prehellénic deities. The cult trees have generally but incorrectly been called styrax trees; the styrax flower was said to have produced incense or perfume. The cult trees, however, are without doubt sacred trees, not pastoral ornaments. Hittite sources mention an "eya tree" on which a bag of gifts was hung. The duplication of the trees and of the columns takes us even further back arranged as they are in so-called Mesopotamian symmetry. Two such sacred trees are found on the painting from Mari of the 18th century B.C., framing a ritual scene in a sacred area. Two trees, not as well-known, frame the tripartite shrine with characteristic semicircular court on an early geometric vase from Cyprus.



Fig. 255 Geometric vase depicting tripartite shrine and sacred trees (18th cent B.C.) Courtesy Director of Antiquities and the Cyprus Museum.



Fig. 256 SAGALASSUS, Pisidia: Double shrine in which two altars with their baldachinos (Valerian A.D. 253-258) BM.



Fig. 258 Drawing of an Akkadian seal, depicting a deity seated upon an altar of flat stones (c. 2000 B.C.) Courtesy B. Goldman.



Fig. 259 SELGE: Shrine in which round cult object entwined by snakes; below, thunderbolt of Zeus (Aurelian A.D. 270-275) BM.



Fig. 257 BOSTRA, Arabia: Altar of Dusares on a terrace (Trajan Decius A.D. 249-251) Paris.



Fig. 260 SELGE: Star entwined by snakes (Faustina A.D. 160-175) BM.



Fig. 262 SELGE: The sanctuary of Zeus and Heracles with a barrier in front (Commodus A.D. 177-191) BM.

Fig. 261 SELGE: The sanctuary of Zeus and Heracles with the "mystic E" inscribed on the platform (Etruscilla A.D. 249-251) BM.

Twin columns or pillars also have a long history in the Near East. The most famous^{Fig.} are the twins, Jachin and Boaz, which were free-standing in front of the Phoenician temple of Solomon at Jerusalem. Very like the columns described in the Bible are the decorated pillars on the Sidon bronze coin.²⁷⁷

The architectural and religious traditions of Selge can be seen elsewhere in Pisidia. At Sagalassus, two altars are shown within a gate or aedicula, decorated with elaborate²⁵⁶ columns. The stars over the altars symbolize a Near Eastern celestial cult related to the Greek Dioscuri. It is clear from the many examples of altars within portals on coins that this type at Sagalassus indicates a cult shrine situated within an open courtyard.

Closest to the monument of Selge is that of Bostra. The coins show a high terrace²⁵⁷ reached by steps on which the altar of Dusares rises above, but by convention actually standing behind, three small altars or baetyls. He must have been a humourist, the numismatist who years ago described the flat stones as a pile of cakes. That they are the artist's device for showing an altar is evident from an Akkadian seal where a deity is²⁵⁸ shown seated on an altar portrayed by means of the same type of stones.

The substructure at Selge is surprisingly like that at Baalbek. It is noteworthy that at Baalbek, twin columns stood on either side of a monumental altar/shrine in the open court above the crypt. Both at Baalbek and Selge, the god was an early deity who became Zeus/Jupiter. At Baalbek, the rites of both a mystery cult and an oracular cult²⁶⁶ were practised in the substructure. The same can be deduced for Selge.

A simple aedicula on a Selge coin has a strange cult object, a shield decorated with²⁵⁹ snakes. A similar shield is found on earlier Hellenistic coins, as are the attributes and heads of Zeus and Heracles. A flower-like object, surrounded by snakes, a star — it is²⁶⁰ not the styrax bloom — also appears on the coins. The shield was clearly of special significance at Selge, since a great many shields decorate building blocks still to be seen at the site. Snakes, in their turn, may indicate a chthonic mystery cult as we have seen in the Sacred Sanctuary at Cyzicus. That the cult of Selge involved an oracle is further suggested by the mystic epsilon, the strange sacred letter of the oracle at Delphi,²⁶¹ engraved on the platform.

The sanctity of the enigmatic monument is emphasized by a low barrier occasionally²⁶² shown in front. The most famous barrier of this type is the one which stood in front of the temple of Solomon ostensibly to keep out the gentiles. One found at Zela closes²⁶³ the gateway itself. At Sebastopolis a barrier stands at the entry to a court flanked by²⁶⁴ 8-9 columned porticos. Similar structures are found on a Roman coin in front of the temple of Antoninus Pius and Faustina, and from the area of Pisidia itself, on the temple of²⁶⁵ Men on the coins of Antioch, and on the subject of our next section, the temple of Aphrodite at Paphos.

Much more will be learned about this strange monumental altar complex when Selge is further explored. Future archaeologists must be fully aware that Selge continued her preellenic religious beliefs and preellenic architectural forms into the Roman imperial period.



Fig. 263 ZELA, Pontus: Temple with barrier across the entrance (Caracalla A.D. 206/7) Paris



Fig. 264 ROME: Temple of Antoninus Pius and Faustina. An altar stands between the barrier and the facade of the building (Antoninus Pius A.D. 141–161) BM.



Fig. 265 ANTIOCH, Pisidia: Temple of Men with barrier in front (Gordian III A.D. 238–244) BM.



Fig. 266 CYPRUS: The sanctuary of Aphrodite at Paphos (Septimius Severus A.D. 193–211) BM. See colour plate p. 154.

PAPHOS

THE SANCTUARY OF APHRODITE

"But Aphrodite, lover of laughter, went to Paphos in Cyprus, where were her priests and her altars of incense."

Homer, *Odyssey* VIII 361-2

Of all the great cults in the ancient Greco-Roman world that which preserved its ^{Fig.} prehellenic characteristics most clearly was at Paphos in Cyprus. Today, only the site and a few stones of the portico may be seen; but in Homer's day it was believed to be the authentic birthplace of the goddess Aphrodite, the home to which she returned in shame after being discovered with her lover, Ares, by her husband, the limping blacksmith god, Hephaestus. The coins show us the temple in the 2nd century A.D., a ²⁶⁶ strange oriental-looking building which owes practically nothing to the Greek and ²⁶⁸ Roman cultures. Everything in its style bespeaks the Bronze Age.

The central feature of the tripartite structure is a tower, opened to reveal the cult image within, the sacred stone-baetyl. The three windows in the top storey of the building are reminiscent of the pedimental windows of the temple of Ephesus, which ²²⁹ we have suggested were used in the ritual of an epiphany. Here at Paphos, the openings likewise recall the triglyph frieze of later Doric architecture. Are they the origin of this decorative motif? The line of the two outer pilasters is continued above the roof of the tower, surmounted by crenellations symbolic of horns of consecration, the typical prehellenic objects of adoration in the East. The building has three parts: On each side of the tower are side porticos with doves perched on the roofs; these birds were sacred to Aphrodite. Inside each of the two porticos are the "altars of incense" of Homer, thymiateria or incense burners, on tall stands, to show the ritual purpose of the shrine.

The whole complex is on a low platform, and a semicircular courtyard, shown on gems as well as on coins, is enclosed by an open lattice-work fence with gates at the front. The stone slabs of the court are clearly delineated by the die engraver: On them he has placed a long, low slab which was undoubtedly a table for offerings to the goddess, relished perhaps by her doves. To the right of this table, three circular details, always present and always in the same position, were also presumably places of offering or dedication. The whole design is crowned with the star and crescent, the symbol of an Eastern celestial cult, in ancient as well as in modern times.

Nothing of the 6th century shrine has been discovered. The coins and gems, the sole ²⁶⁷ evidence for the temple, not only show its appearance in ancient times, but also help to trace the development of its extraordinary architecture up to Roman times. The tripartite design and prehellenic cult objects appear on Minoan and Mycenaean ²⁶⁹ documents. A model from Lemnos delineates a later shrine, a divided entrance behind the typical semicircular court. This indicates that the shape of the court was not ²⁷⁰



Fig. 267 Gold plaque showing the shrine of Aphrodite at Paphos, with details of the courtyard. (Imperial period) Courtesy Ashmolean Museum, Oxford.



Fig. 268 PERGAMUM, Asia: Sanctuary of Aphrodite Paphia (mid. 3rd. cent. A.D.) Berlin.



Fig. 269 Gold ornaments from Mycenae, each with a tripartite shrine (16th century B.C.) Courtesy National Museum, Athens.




Fig. 270 Model of a shrine from Lemnos (7th cent. B.C.) Courtesy National Museum, Athens

dictated by the shape of the coins: Such a form actually existed. A similar tripartite^{F19} structure is pictured on a vase of the Geometric period, forming a link between the²⁵⁵ Bronze Age and the Hellenic examples.

The tripartite design is also known in early North Syria. Actual remains have not yet been found in mainland Phoenicia; but the evidence of the coins, summarized below under Sidon is clearly important for the history of architecture; and in the lands under North Syrian influence we have temples with three cellae. Again actual tripartite temples have been excavated at Xanthos and in the Phoenician West. It is no coincidence that the sacred Eastern baetyl is found as an object of adoration both in Phoenicia and in Cyprus.

The fame of Paphian Aphrodite was world-wide and on coins we have two further illustrations of her cult at Pergamum and at Sardis, both emphasizing the semicircular²⁶⁸ court in front of the temple. The former coin issue identifies the temple with the word³¹ "Paphia." But neither at Pergamum nor Sardis are the side colonnades of the Cypriot complex shown: instead there are free-standing torches or incense burners, and columns surmounted by doves. Partly because of these differences, it is reasonable to suppose that the shrines depicted on the coins of Pergamum and Sardis are illustrations not of the sanctuary at Paphos, but of local shrines to Paphian Aphrodite, based on the design of the great Cypriot sanctuary. It would follow that the worship of Paphian Aphrodite required a special ritual which dictated the architectural form.




Fig. 271 BYBLOS: Detail from a coin depicting a view of the sanctuary of Aphrodite (Macrinus A.D. 217-8) BM. See colour plate p. 153.




Fig. 272 The temple of the obelisks, Byblos (18th cent. B.C.). Courtesy Nina Jidejian.

BYBLOS

THE SANCTUARY OF APHRODITE

"And I also saw a great sanctuary in Byblos, that of the Aphrodite of Byblos, and in it they celebrate the ritual of the death of Adonis....First of all they weep for Adonis, as if for a corpse, but on the next day, they declare that he is alive."

Lucian, *De dea Syria*, 6.

From Byblos, a city where Eastern influence was always strong, comes a monument^{F19} that is unlike any other on coins. We do not know where the original building was²⁷¹ located since no remains of such a sanctuary have been found. The impression from the coins is of a most unusual architectural arrangement. It is most probable that the literary references to the celebration of the death of Adonis at Byblos should be linked with the sanctuary of this coin.

An equally exceptional sanctuary has actually been found at Byblos, dated to approximately 2000 B.C. and known as the Temple of the Obelisks. A large number of²⁷² sacred stones or baetyls, arranged strangely in a rectangle, were found on the site. Ordinarily only one such baetyl was used as a cult object. Otherwise the plan was like other Semitic sacred areas. Almost contemporary with this shrine is the sanctuary of²⁷³ Nini-Zaza at Mari on the Euphrates which is remarkably similar to the courtyard pictured on the Byblos coin; for in both there is a single baetyl in the centre of the open area. Thus the Byblos coin type, like that at Paphos, is a direct descendant of the Bronze Age sanctuaries. It is interesting to note that a later development of the same arrangement is the Islamic shrine, the Mosque at Mecca with its Ka'ba.

The details of the coin have provoked much comment and one of the points of controversy is the porch portrayed on the left. It is sometimes claimed that this was an ancillary building, reserved for the temple priests. It has even been thought that it was a separate temple. However, the coins clearly show that the building is joined to the side of the courtyard. It will be further noted that there is an altar pictured in the facade of the porch and, as we have seen, this invariably identifies the building as an entrance way, not a temple or shrine, or for that matter a separate room for temple priests.




Fig. 273 Restoration of the temple of Nini Zaza, Mari (18th cent. B.C.) Courtesy A. Parrot.

Fig. If this porch is the entrance, what is the colonnaded structure reached by steps that fills the lower side of the court? This colonnaded structure is not attached to the rest of the arcade of the courtyard. Further it is shown surmounted by a "horned" altar and this in turn is once more surmounted by the baetyl. In order to show this complicated monument, the die maker deliberately opened up the enclosing wall of the courtyard and replaced the wall with this structure which in reality stood inside the court. The baetyl on the horned altar is shown above although in reality it stood behind the colonnaded portico reached by a flight of steps. In effect, this colonnade acted as a barrier within the large central court and behind it stood the sacred baetyl either on the horned altar or behind it. The porch, the monumental Graeco-Roman portico, delineated to the side, may be envisaged as filling the fourth side of the court.

- ²¹⁴ Thus interpreted, the Byblos monument is very like the tomb/altar/shrine of Parium. As an essentially oriental sanctuary, the altar/shrine complex is remarkably like the great court sanctuaries at Pergamum and Baalbek, and effectually links them as well to the Bronze Age temples of Byblos and Mari.



Fig. 271



Fig. 252



Fig. 266

Fig. 252 SELGE: The sanctuary of Zeus and Heracles. Berlin.

Fig. 266 CYPRUS: The sanctuary of Aphrodite Paphia. BM.




Fig. 274 Reconstruction of the temple, Kasr Fira'un, Petra (2nd cent. A.D.). Courtesy J. B. Ward-Perkins



Fig. 275 BERYTUS, Phoenicia: The temple of Astarte (Diadumenian A.D. 217-218) BM.



Fig. 276 BERYTUS, Phoenicia: Marsyas within a gate surmounted by horned altars (Elagabalus A.D. 218-222) BM.

SIDON

THE TEMPLE OF EUROPA—ASTARTE

And there is even another large sanctuary in Phoenicia, one which the Sidonians possess. They themselves say it is dedicated to Astarte, but I myself think Astarte was Selene; and as one of the priests explained to me, it was dedicated to Europa, the sister of Cadmus..... And Zeus in the form of a bull took Europa to Crete..., and the coins which the Sidonians use portray Europa on the bull, who is Zeus."

Lucian, *De dea Syria*, 4.

Fig. 277 One of the coins of Sidon, known through only a few examples, gives us a rare and extraordinary view of an oriental sanctuary. A simple form of perspective is adopted.

The temple building is shown directly above the columns that marked the entry to the sanctuary. Looking at the coins from an architectural point of view, there are four main elements. In the front stand the two great columns finely decorated with floral scrolls. Between the two columns, but actually behind, is an open courtyard in which the statue of Marsyas and the torchbearers on their pedestals are shown. The temple behind is open to reveal the main cult statue of Europa on the Bull and smaller figures in the side aisles. Colonnades stand rather incongruously on the roof of the side chapels.

The columns at the entrance of the sanctuary are in the same tradition as the twin columns "Jachin and Boaz" set up by Solomon's architect in front of the Temple of Jerusalem, the capitals of which were also decorated with a floral pattern. Similar columns are known from many Near Eastern documents and are the hallmark of a sacred area. The Phoenician architect of Solomon's Temple, Hiram, came from Tyre and the legendary temple of Melqart-Hercules of that city also had such columns. The temple of Europa at Sidon, like so many other Syrian temples, has a tripartite 275-6 sanctuary. The two small figures appear to be cult images which stood in the side chapels. The columns on the facade have been opened to show these small cult images and the curious arrangement of columns on the second storey may be compared with 274 a temple at Petra where the two columned chapels are parts of an elaborate adyton.

The legend which brought Europa to Crete, there to become the mother of King Minos, clearly reflects the penetration of Near Eastern influences into the Greek mainland and islands in the Bronze Age. The Greek Europa can through mythology be identified with the early Semitic Asherat whose name was later Hellenized to Astarte or Atargatis. This Mother-goddess was a member of an early Phoenician triad. The coins show Astarte in numerous Graeco-Roman temples, often accompanied by figures



Fig. 277 SIDON: The sanctuary of Astarte/ Europa. Two decorated columns mark the entrance to the court, and the cult image is shown within the temple (Elagabalus A.D. 218–222) BM. See colour plate p.13.

of celestial nature, such as the celestial twins whom the Greeks called the Dioscuri, best known under their Roman names Castor and Pollux. Here, at Sidon, the two cult figures in the side chapels were such celestial divine beings, connected with the Graeco-Roman cult image of Europa on the Bull. The torchbearers emphasize the celestial nature of the cult as does the Silenus Marsyas, the devotee of the great male sky god, Dionysus. This comic little figure with his wine skin is North Syrian in origin but is best known as the Silenus from Phrygia who challenged Apollo to a contest in playing the pipes. Just as Silenus accompanied Dionysus in the Greek world, so Marsyas was found with Astarte in the Near East. In contemporary Roman thought, he had been adopted as the symbol of the freed slave, and thus of the freedom, the *jus Italicum*, enjoyed by certain Greek cities. His presence on this coin may have such overtones for Sidon, itself a Roman colony.

The coins which represent the temple of Sidon, and many others dedicated to Astarte, reflect a surface veneer of Graeco-Roman culture over the ancient forms of Phoenician ritual, religion, and sacred architecture. The great court in front of the temple is particularly characteristic of this Semitic sanctuary. This is dramatically illustrated in the story of Christ's cleansing of the Temple of Jerusalem. The money changers are "in the temple, those that sold oxen and sheep and doves....He drove them all out of the temple, and the sheep and the oxen... and overthrew the tables...." Money changers' tables, oxen and sheep certainly had no place inside a relatively small temple building. Even the worshippers may not have been allowed into the building itself. Thus it was not from the building that the money changers were driven out, but from the sacred courtyard, the place where the worshippers gathered.




Fig. 278 HELIOPOLIS: Detail depicting the temple of Jupiter (Septimius Severus A.D. 193–211) Berlin.

BAALBEK—HELIOPOLIS

An unlikely legend attributes the founding of Baalbek to King Solomon and its destruction to Tamburlane the Great. It was, however, a Graeco-Roman city founded apparently no earlier than the Hellenistic period. Many years have been spent excavating to uncover and restore the monumental sanctuary and the other buildings that attract travellers today from all parts of the world.

The sanctuary was dedicated to a Semitic-Roman divine family, Hadad-Jupiter, Atargatis-Venus, and Simios-Mercury. The temple of Jupiter, dating from the end of the 1st century B.C., appears on several coins identified by the accompanying inscription I(ovi) O(ptimo) M(aximo) H(eliopolitano) and by its decastyle facade. The high podium with the flight of steps on the main facade is typical of a Roman building while the typically oriental window fills the centre of the pediment. This window was reconstructed in the tympanum of the large temple on the basis of the coins and because a similar pedimental opening was actually found on the smaller temple just outside the great sanctuary of Jupiter.



Fig. 279 View of the sanctuary of Jupiter Heliopolitanus, Baalbek. The reconstructed columns at the rear of the complex mark the temple of Jupiter. Courtesy George Taylor.



Fig. 281 HELIOPOLIS: The temples of Venus and Jupiter (Valerian A.D. 253-268) Paris

Fig. 280 HELIOPOLIS: The temple of Jupiter with rays projecting from the eaves and prominent pedimental window (Septimius Severus A.D. 193-211) Paris

Fig. On the rare frontal view of the temple on coins appear strange decorations along the
 280 raking cornices, the importance of which has not been recognized. It is usually claimed
 that they are rudely depicted statues such as are found on the coins showing the
 Capitulum at Rome. They were in fact added and deliberately slanted to symbolize
 the rays of the sun, and to identify the building as the shrine of a deity who in one of
 his aspects was the god Helios, from which the Greek name of the city derives.

The temple of Atargatis-Venus, today called the shrine of Bacchus, was built in the
 middle of the 2nd century A.D., parallel to the larger temple of Jupiter. It was
 dedicated to the same Triad, but here a private mystery cult, associated with the
 worship of Bacchus was also practised. It appears somewhat stylized in detail combined
 281 with the main temple; but the die maker, although a poor artist, was an adventurous
 one. Instead of making the two temples exactly the same, which was often done with
 types of two or more temples, he tried to show what he saw, that one building was
 larger and set back from the other. The so-called temple of Bacchus had stairways to
 the roof or attic, and part of the roof was flat. It was once suggested that the window in
 the pediment was used to reach the eaves in order to clean away bird-droppings; for
 some of the temples at Baalbek without pedimental windows were protected by metal
 screens. It was also supposed that the sole purpose of the window was to let in light.
 The far more plausible function of the window is that it was purely ritualistic. The
 stairway, the partially flat terrace, and the window permitted a sacred object such as
 221 the cult image, or a copy of it, to be shown, as at Ephesus, to the devotees in the
 courtyard below. Such an epiphany is known at other sanctuaries in the Near East and
 in Egypt. At Edfu and Dendera, for example, the gods were carried up to the roof and
 there in the presence of the people, sacrifices and offerings were made to them.

Fig. 282 HELIOPOLIS: The sanctuary of Mercury on the hill. The temple shows marked similarities with the temple of Jupiter (Philip I A.D. 244–249) BM. See colour plate p. 171.



Fig. 283 The ancient stairway recently found on the hill of Shekj Addallah and depicted by the engraver of coin fig. 282. Courtesy George Taylor

Atargatis-Venus was the main deity of the Bacchus temple. The goddess is also shown on a coin which may represent the so-called round temple just outside the great sanctuary where she was also worshipped. The most junior member of the Triad, Mercury, also had a second shrine at a distance from the main sanctuary. A coin²⁸² depicting the temple is identified by a caduceus, Mercury's famous snake-entwined staff, and by a great stairway leading up the wooded hillside to a walled sanctuary at the top. Ruins of a temple were found in just such a position on top of the hill Shekj 'Addallah, and part of the stairway itself leading up to the sanctuary has also been discovered. The coin shows two characteristic details of Semitic architecture: By engraving a border around the temple, the die maker has emphasized the typical oriental court in which the temple stood; by indicating the great flight of steps, he has made allusion to the "High Places" referred to in the Old Testament, and to the hilltop worship so common in the East. It would not be surprising if this sanctuary were not older, if less sophisticated, than the great sanctuary of Jupiter in the plain below.




Fig. 286 Axonometric view of the sanctuary of Jupiter, Baalbek. Courtesy J.B. Ward-Perkins.



Fig. 284 HELIOPOLIS: Monumental stairway and portico to the sanctuary of Jupiter (Philip I A.D. 244–249) BM. See colour plate p.171.



Fig. 285 CAPITOLIAS, Syria: Gateway to the sanctuary of Zeus (M. Aurelius A.D. 166–7). BM. See colour plate p.13.



Fig. 287 The remains of the portico and court of the sanctuary of Jupiter, Baalbek. Courtesy George Taylor.



Fig. 289 Detail of a scabbard found at Mainz, showing a "Syrian" arch (A.D. 17) BM. Courtesy D.E.L. Haynes.



Fig. 288 ABILA, Syria: Gate to an altar court (Venus A.D. 161–168) R. Laurence collection.



Fig. 290 HELIOPOLIS: Temple of Jupiter, showing 10 columns on the facade and 17 on the sides (Philip I A.D. 244-249) Paris. See colour plate p. 171.

Fig. One of the most valuable of all coins depicting architecture is that showing the great
 284 gate and its flanking towers of the entrance portico to the enormous sanctuary of
 Jupiter. The remains of this portico were considerable and together with the coins
 provide good evidence for the reconstruction. However, it is worth noting that in the
 286 latest reconstruction the heavy lantern so prominent on the coins has been reduced to
 a mere coping stone of the pediment. The Baalbek coins must be compared with those
 285 of Capitolias and Abila to show that such towered monumental entrances were not
 uncommon in Syria and were as dramatic as the facade of a mediaeval cathedral. The
 coins of Heliopolis and Capitolias show that the central tower was clearly more
 86-8 prominent than the archaeologists would like to admit. One might even compare the
 three towers of the military gates in other parts of the empire. Both the towers and the
 287 arched gateway are inheritances from early Mesopotamia. The 'arcuated lintel' shown
 so clearly on the portico of the Baalbek coin, and found in the remains, is found as
 early as 1000 B.C., although it is best known from its reappearance in the 1st century
 289 A.D. The name given to this motif is 'Syrian arch,' but surprisingly one of the earliest
 examples of the 1st century A.D. is on a scabbard found in Mainz, but perhaps of
 eastern origin. The earliest example on a coin is probably the strange building at
 367 Caesarea, Samaria, under Trajan. This arched lintel so commonly found on coins is
 often not intended to represent architectural exactitude, but rather to indicate the
 arched or canopied aedicula over the cult image. Here, however, at Heliopolis,
 Capitolias, and Abila, it is clearly the mark of the gate to the sanctuary, and was almost
 certainly part of the actual architecture.



Fig. 291 Image of Jupiter Heliopolitanus (2nd cent. A.D.) Louvre. Courtesy musées nationaux, Paris.



Fig. 292 NEAPOLIS, Syria: Image of Zeus Hypsistos (M. Aurelius A.D. 161-180) ANS.



Fig. 293 HIERAPOLIS-BAMBYCE, Syria: Hadad and Astarte with shrine in which standard (Alexander Severus A.D. 222-235) Vienna.

The ear of wheat in the gateway symbolizes the nature of the deity honoured in the sanctuary. It is not the thunderbolt of the Graeco-Roman Zeus-Jupiter, but a reference to Hadad-Jupiter as god of creation and fertility. The same ear of wheat also appears at the side of the main temple of Jupiter of the coins mentioned above. A number of reliefs and statues show the cult image of Jupiter Heliopolitanus as a typical fertility deity; and in both shape and decoration, with registers of panels, it is like those of Egyptian mummy-cases. The immediate parallel for the style of the Baalbek figure was the cult image of Artemis Ephesia. It is important to note that the "window of appearance" is found on both temples. Flanked by bulls, the deities on coins of Syria, as at Chalcis and Neapolis, are close to the figure of Jupiter of Baalbek. At Hierapolis Bambyce we have Hadad seated outside his shrine also flanked by bulls. At Chalcis and Neapolis the images of the gods are anthropomorphic, but they both hold



Fig. 294 CHALCIS, Syria: Statue of Helios - Helios Hieros usually called Helioseiros (Trajan 98-117) Courtesy R. Myers.



Fig. 295 HELIOPOLIS: The ferculum (portable shrine) on which radiate bust of Jupiter (Gallienus A.D. 253-268) BM.

ears of wheat, and at Chalcis, the name of the deity is identified by the inscription on the coin — “Helioseiros” — a name clearly derived from, if not equivalent to, the sun god himself. Similar figures are found on the coins of Rabbathmoda, Dium, and Ascalon, supporting evidence for the wide-spread worship of such a celestial deity. At Baalbek, Jupiter was, as Hadad, god of storms and fertility, but also, as Helioseiros of Chalcis, the great sky god of Eastern Religion.

Two altars stood in the large court between the great entrance portico and the temple of Jupiter during the Roman period. The larger one, the tower-altar, stood closer to the entrance, its Semitic nature emphasized by the traditional twin columns that flanked it. The altar was so gigantic that it obliterated the facade of the temple from the view of someone entering through the portico. An ancient literary source refers to a “ferculum” at Baalbek, a portable shrine which carried a sacred object or image around the sanctuary. The pedimental window of the temple of Jupiter is no coincidence. As at Ephesus, Magnesia, and Nysa, the portable shrine can be linked with the epiphany of the deity at this high central window. Similarly the tower/altar derived from the ziggurat must have played a part in such an oriental ritual.

Such was the sanctuary of Baalbek, dedicated to an early Eastern cult with Graeco-Roman veneer, for which the coins supply invaluable evidence hardly appreciated heretofore.



Fig. 296 EMISA: Temple of Elagabal (Caracalla A.D. 215) BM.



Fig. 297 EMISA. Temple of Elagabal opened to reveal the cult stone above a prominent altar (Caracalla A.D. 216) Munich.



Fig. 298 EMISA: Temple of Elagabal (Caracalla A.D. 216) Paris.



Fig. 299 EMISA: Temple of Elagabal in three-quarter view, emphasizing the high podium (Caracalla A.D. 216) Paris.

EMISA

THE TEMPLE OF ELAGABAL

"The temple of Emisa, rising high, glistens in the first rays of the sun, the city spreads over wide fields, her towers reaching for the sky. Citizens with well-ordered, active lives worship the flaming Sun. Higher than the Lebanon peaks, green with opulent cedar, the temple of Emisa jealously competes, boasting of its tall triangular top."

Avienus, *Descriptio Orbis Terrae*, 1083ff.

The late Latin poet, Avienus, left us a grandiose description of the ancient city of ^{F19}Emisa, but in an archaeological sense, quite inadequate. In all the centuries between Avienus and today, no archaeologist has explored the city (modern Homs). The coins, ²⁹⁶⁻⁹however, show the main sanctuary in its original form during the Roman period. They are, therefore, the only available evidence for the existence and appearance of this famous temple.

The great sanctuary dedicated to the sun god, called by the Romans Heliogabalus, appears on several series of coins. A conflation of all of them gives us a clear picture of the over-all design of the building as well as significant architectural decorative details. The lower drums on the facade were decorated. The example that exists both on coins and in actual fragments is on the temple of Artemis of Ephesus discussed above. At ²²¹Emisa, we possess only the miniature reliefs of the coins which thus contrast with the majestic size stressed by Avienus.

The coins also show that the temple had a windowed-pediment similar to those at Ephesus, Baalbek, and elsewhere. The cult image in the centre of the facade is not the ²⁸⁰usual anthropomorphic cult figure, but the age-old Semitic sacred stone or baetyl ²⁹⁶which symbolized the divinity or the abode of the divinity. The eagle which decorates the baetyl symbolizes the supremacy of the sun god Elagabal, and also serves as a contemporary reference to the power of the Roman emperor.

Varius Avitus, a Syrian priest of the god Elagabal, a cousin and allegedly the bastard son of the Roman Emperor, Caracalla, became emperor of Rome through the intrigues of his grandmother and great aunt. Such was his devotion to the worship of Elagabal that he determined to make it the chief cult of the empire and had the god's stone ³⁰⁰transported from Emisa to the Capitol at Rome. His assumption of a divine name, and the orgiastic Eastern rites that came with it, shocked even the Romans. The activities



Fig. 300 ROME: Procession with the sacred stone of Elagabal (Elagabalus A.D. 218–9) BM.



Fig. 301 EMISA: The altar of the temple of Elagabal (Julia Domna A.D. 193–211) BM.

Fig. of this emperor are commemorated on the coins minted at this time: they depict, for example, the sanctuary at Emisa, the cult image, and the cortege bearing the baetyl to Rome.

Later in the third century, another claimant to the Roman throne, Sulpicius Urbanus Antoninus, also issued coins depicting the temple of Elagabal. By this time, the baetyl had been restored to its original place in the temple at Emisa. Another coin type shows the great altar of Emisa, one of few such monumental structures found on coins, decorated as it is with ranks of statues in round-headed niches. The altar is shown flaming and the presence of the window in the temple suggests that the altar was an auxiliary shrine in the court below the windowed facade much as at the sanctuary of Baalbek and of Ephesus discussed above. This may be the same altar which is shown underneath or in front of the baetyl within the temple facade, and, if so, it is possible that the court and temple could have been conflated into the same design. The interior of all Oriental temples, from the time of the ziggurats, was inaccessible to the general public. Only the priests were allowed into the Holy of Holies. At Emisa, therefore, we may surmise that the sacred object was brought out from its secret place into the open courtyard so that its worshippers could "behold and see."



Fig. 290



Fig. 282



Fig. 284

Fig. 290 BAALBEK: The temple of Jupiter. Paris.

Fig. 282 BAALBEK: The sanctuary of Mercury. Berlin.

Fig. 284 BAALBEK: The portico to the sanctuary of Jupiter. BM



Fig. 56



Fig. 302

Fig. 56 PELLA, Syria: View of city with temple of the Acropolis. Paris.

Fig. 302 NEAPOLIS, Samaria: Mount Gerizim with the temple of Zeus Hypsistos. Paris.

NEAPOLIS, SAMARIA

The remarkable medallions of Neapolis furnish details which the archaeologists can use to supplement the meagre remains of the monuments on the site. A conflation of all the varieties minted during the second and third centuries A.D. gives the following details: A peripteral temple on the top of Mt. Gerizim, standing on a large platform; an upright male cult image with arms raised between the central columns of the left facade of the temple; a horned altar to the right of the temple; an elaborate stairway descending from the temple to a colonnade at the foot of the mountain; several one-storeyed buildings on both sides of the stairway; a path with arches at both ends winding up the valley between the spurs of Mt. Gerizim; the right-hand peak crowned with an altar.

From ancient authors we learn that Hadrian commanded that a temple be built on top of Mt. Gerizim for the worship of Zeus Hypsistos, and that for its adornment the doors of the temple of Jerusalem be brought from the sacred city. Five hundred years earlier, in the time of Alexander the Great, the Samaritans under Sanaballet built a temple on the same mountain.

Recent excavations have uncovered the temple that Hadrian built. The coins show the correct orientation, north-south, but they have much of value to add since nothing but fragments of the superstructure remain today. They show that the building was a typical peripteral Graeco-Roman shrine, its main facade facing South.



Fig. 302 NEAPOLIS: Mount Gerizim surmounted by the temple of Zeus Hypsistos. Altars stand to the right of the temple and on another spur of the mountain; and a terraced stairway leads from a colonnade, past sanctuary buildings, to the temple (Antoninus Pius A.D. 138-161) Paris. See colour plate p.172.



Fig. 303 NEAPOLIS : Mount Gerizim. A variation of fig. 302 (Antoninus Pius A.D. 138–161) Paris



Fig. 304 ZELA, Pontus: Flaming altar on top of mountain (Caracalla A.D. 205/6) Vienna



Fig. 305 The arched terrace below the temple of Trajan at Pergamum. Drawing from the model in the Pergamum Museum, Berlin, DDR. Courtesy Elisabeth Rohde.

The coins do *not* show the statue of the god standing in *front* of the temple, as has been incorrectly proposed, nor was the temple necessarily tetrastyle. It was once thought that a structure found under the Hadrian temple was the pre-Roman Samaritan building, but it is now recognized that the rubble and other fragments form part of an altar or a podium dated many years earlier. There is no doubt, however, that this heap of rubble became part of an extended platform to support the larger Roman temple. The coins show the platform as an arched structure which resembles the podium prominently delineated on the coin of Pella in the Decapolis. Actual remains⁵⁶ of such a supporting platform have been found as the terrace of the temple of Zeus³⁰⁵ Philios and Trajan at Pergamum. The archaeologists who are still working on the site may be fortunate enough to find traces of these arches.

Remains were also found on the elaborate stairway variously described in the ancient sources as of three hundred or fifteen hundred steps. It consists of a series of small terraces up the side of the hill, connected by a short flight of stairs. Even this detail has been faithfully shown on some of the coins. The buildings on either side of the stairway stood on wider-terraced areas. Made up of two storeys, they were undoubtedly of a sacred nature belonging to the mountain-sanctuary itself, similar to those at Delphi. No remains of the colonnade have yet been found, but judging from the coins, it may have enclosed the whole sacred mountain complex.

The antiquity of the sacred nature of Mt. Gerizim is emphasized by the passage in the Old Testament (Deuteronomy 27.2). Joshua is charged to make the Israelites stand, some on Mt. Gerizim to bless the people, and some on Mt. Ebal to curse them. Similarly the altar on the right hand spur of Mt. Gerizim may be compared with an identical structure on a coin of Zela in North Turkey. The tradition that led to such³⁰⁴ sacred places on the top of mountains, the same tradition that influenced the style and construction of the ziggurat, is here shown to be very much part of Roman Neapolis.



Fig. 306 JUDAEA: Symbolic view of the temple of Jehovah, Jerusalem with barrier in front (Bar Kosiba A.D. 134-5) BM.



Fig. 307 Relief from the arch of Titus, Rome (A.D. 81) Fototeca Unione no. 14823.

JERUSALEM

THE TEMPLE OF THE JEWS

The temple of Solomon stood, as did its successor restored by Herod the Great, in the section of Jerusalem now dominated by the Dome of the Rock (the mosque Abd el Malik, the so-called mosque of Omar) and the mosque el Agha. The Old Testament and other ancient literary sources give generous descriptions of the temples but the written word is so ambiguous that there is no agreement on the appearance of these two famous buildings. When, however, the Jewish rebel, Bar Kosiba, sought a symbol for his coins to epitomize the idea of Hebrew freedom in his conflict with Hadrian, he chose to represent the great temple as it stood before its destruction by the Romans in A.D.70. ^{F19.}

The coins display a facade of four heavy columns and a flat roof sometimes surmounted by a wavy line. In the centre of the facade is the Ark of the Covenant, the sacred chest that held the Tables of the Law. Below the building, instead of steps, there is a fence which extends the full width of the facade.

The numismatic conventions are easily explained. The four-columned facade represents the main entrance of the temple. The Ark of the Covenant occupies the position between the central columns usually taken by the cult image on a Graeco-Roman coin. Since there was no "graven image" allowed to the Hebrews, they adopted one of the sacred objects used in the ritual. Here it was the Ark of the Covenant. The Ark in fact is shown as a portable shrine with dots marking the frontal view of the carry-bars. We know that in the triumphal procession of Titus at Rome, the Ark was carried high on the shoulders of slaves. On the walls of Santa Maria Maggiore, the Ark is seen being transported by soldiers. ³⁰⁷

The flat roof of the temple is typically Phoenician, consistent with the sort of building that the original Phoenician architect, Hiram, would have designed. The wavy line interprets itself as a row of Oriental crenellations such as appear on the shrine of Anu on the 4th century B.C. coins of Tarsus. A close parallel may be seen in the representation of the temple of Artemis at Ephesus depicted with decorative rather than architectural emphasis on a silver cistophorus. A fence is shown in the space below the building; in reality it stood in front. This is without doubt the barrier of stone which we know to have been set in front of the temple, engraved in Greek and Latin with a warning that Gentiles were not to pass into the sanctuary on pain of death. We have noted such a barrier on other coins in our study above of the sanctuary of Selge. ²²⁴ ²⁶³⁻⁶

The building on the Bar Kosiba coins is strikingly similar to the representation of the temple that has survived in the wall paintings of the synagogue of Dura Europos. However, here, on the tetrastyle facade, instead of an Ark, there is a representation of the Torah shrine with prominent doors. A similar picture of the Torah shrine appears ³⁰⁸



Fig. 308 Detail of a painted panel above the arch of the Torah shrine in the Synagogue at Dura Europos (3rd cent. A.D.) Courtesy Princeton University Press.



Fig. 309 Glass from the catacombs at Rome, depicting a Torah shrine between columns. Courtesy B. Goldman.

JERUSALEM



Fig. 311 AELIA CAPITOLINA (Jerusalem): Temple of Astarte (Diadumenian A.D. 217-218) Paris



Fig. 310 JUDEAEA: The seven branched candlestick on a coin of Mattatiah Antigonus (40-37 B.C.) BM.



Fig. 312 AELIA CAPITOLINA (Jerusalem): Temple of the Capitoline Triad (Hadrian A.D. 117-138) Paris

on a well-known glass from a Roman catacomb. For the die-maker, the symbol of the temple was the Ark of the Covenant; for the Dura and Catacomb painters, the Torah shrine. Both objects were used in the ritual of the temple. The die-maker could have chosen another symbol of Hebrew piety, the seven-branched candlestick, which was used as a coin type by Mattatiah Antigonus. Both candlestick and Ark decorate the arch of Titus at Rome. To this victorious emperor, they were symbols not only of Jewish religious belief, but also of the temple itself which he had destroyed.

The building on the Bar Kosiba coins is admittedly an abbreviated view of the great temple of Jerusalem although it does have a characteristically Phoenician facade and other Oriental architectural details. It is academic to insist either that the structure was the temple of Solomon, built in the 10th century, or the temple restored by Herod in the 1st century B.C. The later temple maintained the traditional scheme of the earlier, although it may have been enlarged to suit Herod's dreams of grandeur. But neither was extant at the time the coins were issued, Herod's temple having been destroyed sixty years before. Thus the coins commemorate a temple that not many men could have seen at the time of the revolt against Hadrian.

The coins really commemorate a sacred house of Jewish dreams of religious freedom like the temple of Ezekiel. But Jewish hope was lost soon after the coins were issued. Bar Kosiba was defeated. The Roman city of Aelia Capitolina was built on the ruins of Jerusalem. Today archaeological excavation of the sacred precinct is inhibited by the very sanctity of the site. Hopefully some day conditions may change and the great temple be brought to light again.



Fig. 313 ALEXANDRIA: The Pharos, the doorway reached by a long flight of steps (Antoninus Pius A.D. 142) BM.




Fig. 314 Lamp made in the shape of the Pharos of Alexandria (Imperial period) Courtesy Istituto della Enciclopedia Italiana.

ALEXANDRIA

THE PHAROS

The Pharos was the Tour Eiffel of ancient Alexandria. In spite of an abundance of^{Fig.} ancient and mediaeval descriptions and representations in many different media, the appearance of this famous monument is still a matter of debate. Although the coins³¹³ have always been used as important evidence for the statues, the stairway, and the division into storeys, there has been a remarkable neglect of the shield-like objects which appear without exception on every example of the coin type issued under successive emperors. These have been taken to be shorthand versions of rectangular windows.

The meaning of the shield-like details on the walls of the lighthouse becomes clear when they are compared to the round holes of Egyptian ceramic lamps which were³¹⁴ shaped to represent the Pharos. The lamps show that without any doubt the walls of the Pharos were pierced by circular openings and identical details decorated a glass vase found in Afghanistan.³¹⁵

Alexandria was always a fortified city. Under the Pharaohs, the Rhakotis on the Acropolis, later a sacred area, was used as a fortified post against sea raiders. In post-Roman times, the Pharos was rebuilt as a fortress. In the Hellenistic and Roman periods, the Pharos served both as a guide to incoming friendly ships as well as a watch tower against unfriendly ships. We know, for example, of a mirror which was used on the Pharos until the 8th century A.D. to give signals to the mainland of approaching vessels. Fortifying the Pharos was in the Egyptian tradition. The Greek architect, Sostratos, designed the Pharos for Ptolemy II (286—246 B.C.) at a time of considerable political disturbances. A mosaic shows the Pharos with defensive crenellations in two³¹⁶ tiers, identical to those of a city wall. Even the pylons of sanctuaries were protected against enemies, so that it should come as no surprise to find that the Pharos was a⁶⁴ fortified structure. For its function we can compare the look-outs and armed guards on⁶⁶ 'lighthouses' at Berytus and Aegeae.⁴⁸⁵

In describing the Pharos, a late Arab writer spoke of peep-holes in its walls. These then are the round openings shown on the coins, archer-holes through which arrows and other things could be hurled to cripple the crews of enemy ships entering the harbour. It is time that the high-rise dwelling proposed by Thiersch, and the modern³¹⁷ rectangular windows, be rejected. The Pharos was a fortified building with archer holes up and down its rectangular walls.



Fig. 315 Glass vase from Begram engraved with a view of the Pharos (mid. 3rd. cent. A.D.) Kabul Museum. Courtesy Imprimerie Nationale.



Fig. 317 The old reconstruction of the Pharos from H. Thiersch, *Der Pharos*, Leipzig/Berlin, 1909. Courtesy B.G. Teubner, Stuttgart.

Fig. 316 Detail from a mosaic depicting the Pharos as a crenellated fortress, Qasr-el-Lebia, Cyrene (6th. cent. A.D.) Courtesy H.G. Bray.

ALEXANDRIA

THE SANCTUARY OF SERAPIS

"In the city of Alexandria....the Serapeum is distinguished above all the other temples — because words are inadequate, this must be an understatement — the sanctuary is decorated with so many arcaded courts and life-like statues and so many other objects of art that, with the exception of the Capitulum in which Rome takes so much pride as a symbol of her venerable years and immortality, the whole world could point to no more splendid monument."

Ammienus Marcellinus, *Res Gestae* V, xxiii, 16, 12.

So many Alexandrian coins are extant that it is as if the sands of Egypt deliberately preserved them for posterity. Their abundance, however, and this applies to the architectural types as well, has not added to their reputation. The many representations of temples are very stylized, and have limited use as evidence since so little of ancient Alexandria has been excavated, lying as it does beneath the modern city. But one important area has been exposed and with it the famous sanctuary of Serapis, begun in the Hellenistic period. The coins, therefore, which represent the Serapeum, are invaluable. 318

The worship of Serapis, Isis, and Harpocrates, the main cult of Graeco-Roman Alexandria, satisfied all the polyglot citizenry. The Ptolemies, the Greek successors of Alexander the Great, had changed Osiris of the Egyptians into Serapis; Isis had been given "ten thousand names" to account for her various attributes, and Horus was transliterated into Harpocrates. The Roman temple itself was not the Serapeum, but part of it. The Serapeum was a large open sacred area with corridors, subterranean crypts, and a labyrinth of shrines.

The principal function of a Serapeum — we have evidence also from other similar sanctuaries in the Near East — was the practice of the mystery cult. An army of divinities, Greek and Egyptian, crowded into the temenos, all of them related in one way or another to Serapis, Isis, or Harpocrates. We know, for example, that in the Hellenistic period, there were three niches in the portico of the East wall of the sanctuary for the images of the three deities. In the Roman period a large base in the open court could have supported a statue group.

Most significant is a 1st century A.D. inscription found in the Serapeum: "...to Zeus, Helios the Great, Serapis, and the gods of the same temple." Julian the Apostate amplifies this and calls Serapis "one" with Zeus, Hades, and Helios, a version of "three



Fig. 318 ALEXANDRIA: The Serapeum (Verus A.D. 161–168)
ANS




Fig. 320 Stele with false door of appearance from the tomb of Nefer-Seschem-Ptah, Saqqara (2494–2345 B.C.) Berlin, Bildarchiv Foto Marburg no. 86916.



Fig. 319 ALEXANDRIA: Serapis in procession saluting his alter ego (Venus A.D. 166) Paris

divine natures in one God." He was Zeus to the Greek population and Helios to accommodate the creed of the Egyptians, in a mixture of traditions that can be seen in the extraordinary coin which represents the Serapeum.

This coin has rarely been equated with the great sanctuary. Yet it presents a conflation of both the facade of the sanctuary and the facade of the temple building itself. The head of the main deity, Zeus-Serapis, appears in the pediment. As Helios-Serapis, the god's head is engraved radiate in the transom window, thus positively identifying the building on the coin. We know from other sources that such a window was built in the facade of the temple building and that through it the sun entered to "kiss" the statue of the deity. A transom window is not known on any other coin, but is directly derived from the window of appearance of Egyptian funerary reliefs. At Ephesus, three windows decorated the pediment of the Roman Serapeum, an architectural detail borrowed from the temple of Artemis of Ephesus, but owing its ritualistic origin to the Alexandrian Serapeum.

Looking carefully at the coin, we can see drapery under the facade-window, the tell-tale mark of a portable shrine. With this detail the diemaker has indicated that during a festival the godhead was carried out of the temple in a portable shrine. Another coin of Alexandria shows the deity Serapis as Zeus in a processional car facing his alter ego, Helios, high above in the Heavens, a reference to the ritual associated with the Serapeum.

Three doors decorate the facade of the coin, signifying the presence of three chapels on the interior. The design at Kom Ombo is similar: here two doors led to the cella which was divided into two chapels. The two guardian figures on the coin appear to be male and female, the deities, Isis and Harpocrates perhaps. The facade is remarkably like the screen wall of a Fifth Dynasty tomb. Note the traditional "window of appearance" and the three false doors of Egyptian tomb architecture. Serapis himself was a chthonic deity associated with death.



Fig. 321 ALEXANDRIA: Personification of the Nile beside a domed Nilometer with steps (Antoninus Pius A.D. 133) ANS.



Fig. 322 ALEXANDRIA: The Nile reclining with a hippopotamus; above, a "genius" recording the level of the water on a stele (Trajan A.D. 114) ANS.




Fig. 323 Detail from a silver trulla with the representation of a Nilometer (6th. cent. A.D.) Courtesy Hermitage Museum.

ALEXANDRIA

THE NILOMETER

Throughout Egypt's history, the maximum rise of the waters of the Nile was ^{Fig.} measured, mainly to establish a tax rate based on the average flood height of the river. To some extent, the actual taking of the measurement was always a priestly ceremonial, and at various stations along the Nile there were curious structures used to measure the flood, usually near a temple, and later called by the Greeks "Nilometers."

Although numismatists many years ago identified the Nilometer on the coins, it is ³²¹⁻² now possible to equate it with an actual Roman building found in the excavations outside the gate of the Serapeum. The archaeologists have established that there was a long flight of stairs descending into a deep pit resembling a well, which must have been channelled to the Nile itself. The coins show that in addition to the steps and pit, the Nilometer included a domed superstructure. The steps leading to it can be made out below the domed building. But other examples of the coin type show only a tall pillar or stele. In both series, a little "genius" of the Nile is shown recording the level of the water. In both cases the Nilometer is reduced in size to accommodate it to the small space allowed at the side of the larger figure of the river god.

The difference in the coin types can be explained by reference to another document, a silver plate which is usually but incorrectly interpreted as a representation of the ³²³



Fig. 324 Mosaic from the 'Villa of the Nile', Leptis Magna (2nd-3rd cent. A.D.)



Fig. 325 Tapestry with the representation of a Nilometer (5th cent. A.D.) Louvre.
 Courtesy photo musées nationaux, Paris

Fig. Pharos. It is however quite clearly the Nilometer. The artist has deliberately raised the columned stele so that the viewer could see the "genius" marking it with Greek numerals. The stele actually stood within the building and within the pit, covered by the dome. It was a component part of the Nilometer and was displayed alone on some coins as an abbreviated view of the interior so that the "genius" could be shown. Such a stele associated with the god Nile is found on a mosaic of Leptis Magna. Another representation on an early Byzantine tapestry bears a striking resemblance to the domed structure of the coins, as does a lamp recently published and thought to be — in error — the pyramid-shaped tomb of Alexander the Great. To those who discovered the pit and stairway at Alexandria, it may come as a surprise that the Nilometer had a superstructure. The coins show it; the tapestry and trulla suggest it. The archaeologists have yet to find it.

VARIOUS BUILDINGS ARRANGED BY TYPE

(For figs 326–330 see colour plates)

DISTYLE TEMPLES



Fig. 331 **ARIASSUS, Pisidia:** Temple of Pergaeon Artemis. (J. Mamea A.D. 222–235) Trell collection.



Fig. 332 **MYLASA, Asia:** Temple of Zeus Osogoo (Elagabalus A.D. 218–211) Paris.



Fig. 333 **MYRA, Lycia:** Temple of Artemis (Gordian III A.D. 328–244) Paris.



Fig. 334 **PERGA, Pamphylia:** Temple of Artemis (Verus A.D. 161–168) BM.



Fig. 335 **ABDERA, Spain:** Temple with prominent door, fish replacing two columns, and neo-Punic inscription in the pediment (Late 1st. cent. B.C.) BM.



Fig. 336 GERMA, Galatia: Military standards and city Tyche in imperial temple (Commodus A.D. 177-191) Paris



Fig. 337 PERGAMUM, Asia: Shrine of Telesphorus on podium (Antoninus Pius A.D. 138-161) Paris



Fig. 338 PERGA, Pamphylia: Imperial eagle in shrine flanked by standards (Gallienus A.D. 253-268) Paris



Fig. 339 ANAZARBUS, Cilicia: City Tyche in shrine (Severus Alexander A.D. 222-235) Paris



Fig. 340 ARADUS, Phoenicia: City Tyche in shrine with marked shell in arch decoration (Elagabalus A.D. 218-9) ANS



Fig. 341 TANAGRA, Greece: Shrine of Dionysus with caryatids supporting a flat roof (Antoninus Pius A.D. 138-161) BM



Fig. 342 HADRIANOPOLIS, Asia: Temple with prominent bases in which oil basin (Hadrian A.D. 117-138) Berlin



Fig. 343 HERACLEA AD LATMUM, Asia: Temple of Tyche with marked antae (Caracalla A.D. 198-211) BM



Fig. 344 PERGA, Pamphylia: Temple of Artemis with barrier before the image (Tacitus A.D. 275-276) Paris.



Fig. 345 CREMNA, Pisidia: Temple of Luna (Gordian III A.D. 238-244) BM.



Fig. 346 CAESAREA, Cappadocia: Temple of Artemis of Perga, on a silver cistophorus (Trajan A.D. 112-117) Corpus Christi College, Cambridge.

Fig. 347 EDESSA, Mesopotamia: Temple within a gate? (Severus Alexander A.D. 222-235). Paris



Fig. 348 ALEXANDRIA, Egypt: Serapeum? (Antoninus Pius A.D. 149) ANS.





Fig. 349 PERGAMUM, Asia: Temple of Roma and Augustus (Early 1st. cent. A.D.) BM.



Fig. 350 APOLLONIA AD RHYNDACUM, Asia: Temple of Apollo, crater in pediment (Antoninus Pius A.D. 138-161) Berlin.



Fig. 351 COMANA, Pontus: Temple of Ma (Septimius Severus A.D. 198) Berlin.



Fig. 352 AMISUS, Pontus: Temple of Demeter (Caracalla A.D. 209-10) BM.

TETRASTYLE TEMPLES



Fig. 353 MYLASA, Asia: Temple of Zeus Labraundeus (Geta A.D. 198-211) BM.



Fig. 354 SILANDUS, Asia: Temple of Dionysus (Verus A.D. 161-168) BM.



Fig. 355 EPIDAUROS, Peloponnese: Temple of Asclepius (Antoninus Pius A.D. 138-161) BM.



Fig. 356 TEOS, Asia: Temple of Augustus (Augustus 31 B.C. - A.D. 14) BM.



Fig. 358 CAESAREA PANIAS, Palestine: Temple in which patera (?) On the podium an unexplained cruciform indentation (Herod Philip I 4 B.C. - A.D. 34) BM.



Fig. 357 COLYBRASSUS, Cilicia: Temple in which oil basin (Saloninus A.D. 258) Paris.



Fig. 359 SIDON, Phoenicia: Temple on a podium, flanked by columns of a colonnade: in front, altar (Early 1st. cent. A.D.) Paris.



Fig. 360 SAGALASSUS, Pisidia: Shrine of Tyche surmounted by mountain and two figures (Etruscilla A.D. 249-251) Paris.



Fig. 361 SIDON, Phoenicia: Temple of Astarte/Tyche (Elagabalus A.D. 218–222) BM.



Fig. 364 COMANA, Pontus: Gate with broken pediment (Septimius Severus A.D. 198) Berlin.



362



363

Fig. 362–3 ZELA, Pontus: Gate to an altar court (A.D. 209/10) 362, Oxford; 363, Paris.



Fig. 365 BLAUNDUS, Asia: Temple of Apollo (Philip A.D. 244–249) Paris.



Fig. 366 ATTUDA, Asia: Temple of Cybele (Mid. 3rd cent. A.D.) Paris.



Fig. 367 CAESAREA, Samaria: Altar, with barrier and temple of city goddess beyond (Trajan A.D. 98–117) BM.



Fig. 368 THYATEIRA, Lydia: Temple of Roma (Severus Alexander 222–235) BM.

ARCHED LINTELS



Fig. 369 CYPRUS: Temple of city Tyche with narrow, central stairway (Caracalla A.D. 211-217) In trade.



Fig. 370 METROPOLIS, Ionia, Asia: Temple of Ares, with steps to the cult image (Septimius Severus A.D. 193-211) ANS.



Fig. 371 HIERAPOLIS, Phrygia: Temple of Apollo (Philip I A.D. 244-249) Paris.



Fig. 372 LAMPSACUS, Asia: Temple of Priapus (Philip I A.D. 244-249) BM.



Fig. 373 TYRE, Phoenicia: Altar in front of temple of Astarte (Elagabalus A.D. 218-222) BM.



Fig. 374 DIUM, Arabia: Entrance to altar court (Caracalla A.D. 198-211) Paris.



Fig. 375 BYBLOS, Phoenicia: Temple of Astarte (Caracalla A.D. 198-211) BM.



Fig. 376 ORTHOSIA, Phoenicia: Tripartite temple of Astarte (Caracalla A.D. 198-211) Paris.



Fig. 377 TRALLES, Asia: Temple of Zeus (Venus A.D. 161-168) Paris.



Fig. 378 CAESAREA, Cappadocia: The neocorate temple of the imperial cult (Caracalla A.D. 206) Paris



Fig. 379 ANKYRA, Galatia: The imperial temple (Nero A.D. 54-68) Paris



Fig. 380 SARDIS, Asia: The temple of Dionysus? (Faustina I. c. A.D. 145) Paris



Fig. 381 ASPENDUS, Pamphylia: Temple of Serapis. (Macrinus A.D. 217-8) Trell collection.

Fig. 382 *HYPAEPA, Asia: Temple of Artemis Anaitis (Trajan Decius A.D. 248–251) BM.*



Fig. 383 *MARONEA, Thrace: Temple of Dionysus with broken pediment (Caracalla A.D. 211–217) Berlin.*



Fig. 384 *ZELA, Pontus: Temple or gate with broken pediment (Septimius Severus A.D. 206–7) BM.*



Fig. 385 DIOCAESAREA, Cilicia: Altar to the left of temple (Septimius Severus A.D. 193–211) Paris.



Fig. 386 MYRINA, Asia: Temple of Apollo at Grynium, with prominent Doric entablature with Corinthian capitals to the columns (Septimius Severus A.D. 193–211) BM.



Fig. 388 NYSA, Asia: Temple of Men (M. Aurelius A.D. 161–181) Berlin.



Fig. 389 HIERAPOLIS, Asia: Temple of the emperor? (Caracalla A.D. 198–211) Berlin.



Fig. 387 PHILOMELIUM, Asia: Temple of Asclepius (Severus Alexander A.D. 222–235) Berlin.

OCTASTYLE TEMPLES



Fig. 390 NICOMEDEIA, Bithynia: Neocorate temple (Geta 198–209)
BM.



Fig. 391 TRALLES, Asia: Temple of Mercury?
with elaborate figured acroteria (Augustus 31
B.C.–A.D. 14) Berlin.



Fig. 392 PATRAS, Peloponnese: Corinthian
temple with bust in roundel in the pediment,
and tall figured acroteria (Julia Domna A.D.
193–211) Berlin.



Fig. 393 *APOLLONIA, Pisidia: Imperial temple (Gallienus A.D. 253-268) ANS*



Fig. 394 *SAGALASSUS, Pisidia: Large bust above altar in temple (Volusian A.D. 253-258) Paris*



Fig. 395 *AEGEAE, Cilicia: Temple of Asclepius (Macrinus A.D. 218) Paris*



Fig. 396 *BITHYNIA: Imperial temple (Hadrian A.D. 117-138) BM.*



Fig. 397 *ERESUS, Lesbos: Imperial temple (?) (Antoninus Pius A.D. 138-161) BM.*

THREE-QUARTER VIEWS

*Fig. 398 APOLLONIA, Illyria, Temple of Apollo
(Caracalla A.D. 198-211) Berlin.*



*Fig. 399 ANKYRA Galatia:
Temple of Men (Trajan A.D.
98-117) BM.*



*Fig. 400 CORCYRA: Temple of Apollo (Plautilla
A.D. 202-205) Berlin.*



Fig. 401 ALEXANDRIA TROAS, Asia: Temple of Apollo Smintheus (Commodus A.D. 177-191) BM.



Fig. 402 NICOPOLIS AD ISTRUM, Moesia: Temple of Serapis (?) (Elagabalus A.D. 218-222) BM.



Fig. 403 HIERAPOLIS, Asia: Temple of Dionysus (Elagabalus A.D. 218-222) Paris.



Fig. 404 ARGOS, Peloponnese: Prostyle temple (Julia Domna A.D. 193-211) BM.



Fig. 405 DARDANUS, Asia: (Commodus A.D. 177-191) ANS.



Fig. 406 AEGEAE, Cilicia: (Valerian A.D. 253-258) Vienna.



Fig. 407 SIDE, Pamphylia: (Valerian A.D. 253-258) Paris.



Fig. 408 PHILADELPHIA-EPHESUS, Asia (Trajan Decius A.D. 249-251) Paris.

THREE-QUARTER VIEWS



Fig. 409 ROME: Prostyle temple of Neptune (41 B.C.) BM.



Fig. 410 DOCIMEUM, Asia: Corinthian temple (Macrinus A.D. 217-218) Paris.



Fig. 411 AEGINA, Greece: Prostyle temple (Septimius Severus 193-211) ANS.



Fig. 412 EPHESUS, Asia: Neocorate temple (?) (Nero, A.D. 54-68) BM.



Fig. 413 DAMASCUS, Syria:
Temple on podium over a spring;
an altar stands in front of the
steps (Ottacilia A.D. 244-249)
Paris.



Fig. 414 NEOCAESAREA, Pontus: Neocorate temple
(Gallienus A.D. 253-268) Berlin.



Fig. 415 TYRE, Phoenicia: Temple of Melqart
(Macrinus A.D. 217-8) BM.



Fig. 416 PHILIPPPOPOLIS, Thrace: Temple held by Apollo
and the emperor (Elagabalus A.D. 218-222) Berlin.

VARIOUS SHRINES



Fig. 417 NESIBIS, Mesopotamia: Seated city Tyche within pilastered facade (Philip I A.D. 244-249) BM.



Fig. 418 CARRHAE, Mesopotamia: Tripartite shrine of a celestial deity (Verus A.D. 161-168) Paris.



Fig. 419 RABATHMODA, Mesopotamia: Hadad-Ares standing on his temple (Septimius Severus A.D. 193-211) Paris.



Fig. 420 TRIPOLIS, Phoenicia: Tripartite temple of Astarte (Elagabalus A.D. 218-222) ANS.

Fig. 421 SABRATHA, Africa: 'Pentastyle' temple with cella extending above the architrave and supporting a pitched roof (Late 1st. cent. B.C.) BM.

Fig. 422 NEAPOLIS, Samaria: Temple of Astarte (Faustina II A.D. 158-9) Paris.

Fig. 423 EUMENEIA, Asia: Round ? naiskos of Artemis (Philip I A.D. 244-249) Paris.



421



422



423



Fig. 424 PATARA, Lycia: Aedicula with caryatids (Gordian III A.D. 238-244) Paris.



Fig. 425 SICYON, Peloponnese: temple or tall column flanked by herms (Julia Domna A.D. 193-211) Paris.



Fig. 426 AMISUS, Pontus: Altar and temple of Zeus (Hadrian A.D. 131-2) Paris.



Fig. 427 TANAGRA, Greece: Shrine of Artemis Huntress with ship below (Antoninus Pius A.D. 138-161) Paris.



Fig. 428 CLAUDIOSELEUCEIA, Pisidia: Snake on altar, with flaming altar to right of shrine (Tranquillina A.D. 238-244) Paris.

THE SHRINE AT ANAZARBUS



429



430



431

Fig. 429 (Maximinus A.D. 235-238) Paris

Fig. 430 (Maximus A.D. 235-238) Berlin

Fig. 431 (Maximus A.D. 235-238) Paris

Figs. 429-431 Various views of the tripartite shrine at ANAZARBUS, Cilicia.



Fig. 432 ROMÉ: Temple, with large figured acroteria, between colonnades (Trajan A.D. 104-111) BM.



Fig. 433 DAMASCUS, Syria: Shrine in which Marsyas and river in grotto (Otacilia A.D. 244-249) BM.



Fig. 434 PAUTALIA, Thrace: Two altars, Asclepius in tree, and tetrastyle temple of Asclepius (Caracalla A.D. 211-217) Paris.



Fig. 435 DALDIS, Asia: Mythological scene in front of the temple of Apollo (Gordian III A.D. 238-244) Paris.



Fig. 436 APOLLONIA, Illyria: Temple of Zeus (Julia Domna A.D. 193-211) Paris.



Fig. 437 SELINUS, Sicily: Sanctuary of the river god Hypsas (Mid. 5th. cent. B.C.) BM.



Fig. 438 EPHESUS, Asia: Altar and worshippers before the temple of the emperor (Macrinus A.D. 217-218) BM.



Fig. 439 PERGAMUM, Asia: Sacrificial scene before the temple of Caracalla as Dionysus Kathegemon (Caracalla A.D. 211-217) Paris.



Fig. 440 COLOPHON, Asia: Worshippers before the temple of Apollo at Claros (Valerian A.D. 253-258) BM.

Fig. 443 SEBASTOPOLIS—HERACLEOPOLIS, Pontus: Naiskos and altar of Heracles. See figs. 8–9 (Geta A.D. 198–211) Berlin.



Fig. 441 APOLLONIA, Thrace: Monumental altar (Faustina II A.D. 160–175) BM.



Fig. 442 ADRAA, Arabia: Altar of Dusares (Commodus A.D. 177–191) Berlin.



Fig. 444 CHALCIS, Syria: Naiskos of Helios (Trajan A.D. 98–117) BM.



Fig. 445 SELEUCIA PIERIA, Syria: Naiskos of Zeus Kasios (Trajan A.D. 98–117) BM.



Fig. 446 NICOMEDEIA, Bithynia: Galley with two neocorate temples above (Commodus A.D. 177-191) BM.



Fig. 447 TRALLES, Asia: Temples of Zeus and the imperial cult (Caracalla A.D. 198-211) Paris.



Fig. 448 CYZICUS, Asia: The two neocorate temples (Caracalla A.D. 211-217) Paris.



Fig. 449 ANKYRA, Galatia: The gates to two alter courts (Gallienus A.D. 253-268) ANS.



Fig. 450 PERGAMUM, Asia: Column and two imperial temples (Commodus A.D. 175–191) Paris.



Fig. 451 BEROEA ?, Macedonia: Column and two neocorate temples (Severus Alexander A.D. 222–235) Berlin.



Fig. 452 DAMASCUS, Syria: Two imperial temples, and aedicula of the city Tyche (Philip I A.D. 244–249) BM.



Fig. 453 SIDE, Pamphylia: The temple of Apollo and two imperial temples (Trebonianus Gallus A.D. 251–253) Paris.

THREE AND FOUR TEMPLES

Fig. 455 SMYRNA, Asia: The temples of Tiberius, Roma, and Hadrian (Caracalla A.D. 211–217) Paris.



Fig. 454 PERGAMUM, Asia: The three neocate temples (Caracalla A.D. 211–217) Paris.



Fig. 457 NICOMEDEIA, Bithynia: Galley with three temples (Valerian A.D. 253–258) ANS.



Fig. 456 NICOMEDEIA, Bithynia: Temple of Demeter and two neocate temples (Severus Alexander A.D. 222–235) BM.



Fig. 458 THESSALONICA, Macedonia: Four neocate temples (Trajan Decius A.D. 249–251) BM.



Fig. 459 EPHESUS, Asia: Horse drawn aedicula (Valerian A.D. 253-258) BM.



Fig. 460 SIDON, Phoenicia: Car of Astarte (Elagabalus A.D. 218-222) BM.



Fig. 461 ANAZARBUS, Cilicia: Elephants drawing carriage on which replica of temple (Julia Maesa A.D. 222-235) ANS.



Fig. 462 PALTUS, Syria: Shrine fitted with carry bars (Septimius Severus A.D. 193-211) Paris.



Fig. 463 PTOLEMAIS, Phoenicia: Flat roofed shrine of Hadad with carry bars (Macrinus A.D. 217-218) Berlin.



464



465

Figs. 464 and 465 TYRE, Phoenicia: Oriental shrine fitted with carry bars (Gallienus A.D. 253-268). 464, ANS; 465 Berlin.

PORTABLE SHRINES

Fig. 466 ASCALON, Palestine: Oriental shrine with receding embrasures (Antoninus Pius A.D. 150) Vienna.



Fig. 467 DAMASCUS, Syria: Shrine of Astarte-Tyche, fitted with carry bars; below image, rectangular area decorated with ram (Philip II A.D. 244–249) Berlin.



Fig. 469 LAODICEA AD MARE, Syria: Bust of Julia Domna in shrine (Septimius Severus A.D. 193–211) ANS.



Fig. 470 SIDE, Pamphylia: Shrine of Tyche with prominent conical roof topped with pomegranate (Salonina A.D. 253–268) Vienna.



Fig. 468 TYRE, Phoenicia: Shrine of Astarte-Tyche (Gallienus A.D. 253–268) BM.





Fig. 471 TOPIRUS, Thrace: Round monument (Antoninus Pius A.D. 138-161) Paris.



Fig. 472 TOPIRUS, Thrace: Round monument flanked by equestrian statues (Caracalla A.D. 211-217) Berlin.



Fig. 473 HERACLEA, Bithynia: Stadium building with temple at one end (c. A.D. 240) Berlin.



Fig. 474 ALEXANDRIA TROAS, Asia: Bouleuterion in session (Trebonianus Gallus A.D. 251-253) BM.

VARIOUS BUILDINGS

Fig. 477 ROME: Two storied portico: Basilica Aemilia (61 B.C.) BM.



Fig. 475 PAESTUM, Italy: Two storied building with pitched roof and arcade (Late 1st cent. B.C.) ANS.



Fig. 478 BURA, Peloponnese: Portico or arcade (Septimius Severus A.D. 193-211) Oxford.



Fig. 476 NYSA, Asia: Double storied arcade with large figures at roof level (Gallienus A.D. 253-268) Berlin.



Fig. 479 CORINTH, Peloponnese: Enclosure and tree (Vetus A.D. 161-168) BM.

*Fig. 481 SIDE, Pamphylia: Harbour and arcades
(Gallienus A.D. 253-268) BM.*



*Fig. 480 PTOLEMAIS, Phoenicia:
Harbour with colonnades around
(Elagabalus A.D. 218-222) P. Franke coll.*



*Fig. 483 SOLI-POMPEIOPOLIS,
Cilicia: Harbour and the god
Oceanus (Antoninus Pius A.D.*



*Fig. 482 MEGARA, Greece: Ornate gate and
the harbour at Pagae (Geta A.D. 198-211)
Berlin.*



*Fig. 484 MOTHONE, Peloponnese:
Harbour with statue at entrance (Geta
A.D. 198-211) Berlin.*



Fig. 485 AEGEAE, Cilicia: Ship sailing past a guarded tower (Trajan Decius A.D. 249–251) Paris.



Fig. 487 OLBA, Cilicia: Crenellated tower (Early 2nd cent. A.D.) Paris.



Fig. 486 ABYDUS, Asia: Heroic scene of ships with trumpeter in tower (Septimius Severus A.D. 193–211) Paris.



Fig. 488 ALEXANDRIA, Egypt: Fountain with three spouts in lower part, four columns above, between which three figures; flat roof decorated with eagle and acroteria (Trajan A.D. 100) Paris.



Fig. 489 ALEXANDRIA (Aphroditopolite Nome) Egypt: Shrine with two sacred cats on pedestals (Trajan A.D. 98-117) BM.



Fig. 490 AUGUSTA TRAIANA, Thrace: Shrine of Apollo (Caracalla A.D. 198-211) Berlin.



Fig. 491 ALEXANDRIA (Aphroditopolite Nome) Egypt: Shrine of Isis with sacred birds on pedestals (Trajan A.D. 112) Paris.



Fig. 492 ALEXANDRIA, Egypt: Shrine of Harpokrates of Mendes (Hadrian A.D. 134.) Paris.



Fig. 493 ALEXANDRIA, Egypt: Shrine with Canopi (Hadrian A.D. 134) Paris.



Fig. 494 ALEXANDRIA, Egypt: Shrine with griffin (Hadrian A.D. 137) ANS.



Fig. 495 MEGARA, Greece: Shrine with herm (Geta A.D. 198-211) Berlin.



Fig. 496 NICAIA, Bithynia: Tyche crowned with city gate (M. Aurelius A.D. 161–180) Paris.



Fig. 499 MARCIANOPOLIS, Thrace: City gate (Gordian III A.D. 238–244) Paris.



Fig. 497 BIZYA, Thrace: Ornate city gate (Antoninus Pius A.D. 138–161) Courtesy Dr. H.A. Cahn.



Fig. 498 PAGAE, Greece: City gate with figures (Septimius Severus A.D. 193–211) Berlin.



Fig. 500 TOMI, Thrace: City gate (Maximus A.D. 235–238) A.N.S.



Fig. 501 MARCIANOPOLIS, Thrace: Crenellated gate (Gordian III A.D. 238–244) Paris



Fig. 502 ISAURA, Crenellated gate with central tower (Septimius Severus, A.D. 193–211) Paris



Fig. 504, HADRIANOPOLIS, Thrace: City gate (Gordian III A.D. 238–244) ANS.



Fig. 502 SIDE, Pamphylia: Crenellated gate (Valerian A.D. 253–258) BM.



Fig. 505 PRUSIAS AD HYP'UM, Bithynia: City gate (Gallienus A.D. 253–268) P. Bastien coll.



Fig. 506 ROME: Ornamental triumphal arch (Trajan A.D. 104–111) BM.



Fig. 507 DIOCAESAREA, Cilicia: Arch with figures (Otacilia A.D. 244–249) Paris.



Fig. 508 MAURETANIA: Portico with narrow stairway: cella wall and roof visible above (Juba I 60–46 B.C.) Paris.



Fig. 509 ALEXANDRIA, Egypt: Pylon to the sanctuary of Isis (Hadrian A.D. 135) Berlin.



Fig. 511 TARSUS, Cilicia: Ornamental gate (Caracalla A.D. 198-211) ANS.



Fig. 510 ALEXANDRIA (Heracleopolite Nome) Egypt. Shrine of Heracles (Trajan A.D. 110) BM.



Fig. 512 PAGAE, Greece: Two storey gate with image of Heracles (Septimius Severus A.D. 193-211) ANS.



Fig. 513 CAESAREA GERMANICA, Bithynia: City walls and gate (Germanicus c. A.D. 40) ANS.



Fig. 514 ZELA, Pontus: The Propylaea on the Acropolis (Caracalla A.D. 198-211) Berlin.



515



516



517

Fig. 515 PTOLEMAIS, Phoenicia: The Acropolis (Elagabalus A.D. 218–222) Paris

Fig. 516 ANAZARBUS, Cilicia: The Acropolis with head of Zeus in the foreground (Claudius A.D. 45) Berlin

Fig. 517 GANGRA, Paphlagonia: Towers and two secular buildings (Caracalla A.D. 198–211) Berlin

Fig. 518 EPHESUS, Asia: Jupiter Pluvius seated above the city (Antoninus Pius A.D. 138-161) BM.



Fig. 521 EMERITA, Spain: Gate and city walls (Tiberius A.D. 14-38) BM.



Fig. 519 SARDIS, Asia: Lion before the walls of the city (Caracalla A.D. 198-211) Vienna.



Fig. 522 PELLA ? Macedonia: The city walls (Late 1st. cent. B.C.) BM.



Fig. 520 EPHESUS, Asia: Galley carrying image of Artemis with the city in the distance (Gordian III 238-244) Paris.

BIBLIOGRAPHY

This selection of references to earlier work is intended to lead the reader to a more intimate acquaintance with the problems involved. It does not set out to be a comprehensive list of all relevant works, but supplements the chapters of this book both as a guide to further reading and as explanation of certain remarks which we have felt it necessary to make.

NUMISMATIC

(For reference to the catalogues of cabinets, see Grierson)

- L. Anson, *Numismatica Graeca*, 1-11, Greek Coin-Types Classified for Immediate Identification, London, 1910-1916 (reprint, 1967).
- Antonio García y Bellido, *Hispania Graeca*, Tome II (Instituto Español de Estudios Mediterráneos, Publicaciones sobre arte y arqueología), Barcelona, 1948, 219-231.
- A. Beltrán, "Los Monumentos en las monedas Hispano-Romanas," *Archivo Español de Arqueología*, xxvi, 1953, 39-66.
- C. Bosch, "Die kleinasiatischen Münzen der römischen Kaiserzeit," *Jahrbuch des Deutschen Archäologischen Institutes*, *Archäologischer Anzeiger*, Berlin, 423-455.
- British Museum, *Coins of the Roman Republic in the British Museum*, 1910 (1970) (H. Grueber).
- British Museum, *Coins of the Roman Empire in the British Museum*, 1923 (in progress) (H. Mattingly).
- G. Dattari, *Numi Augg. Alexandrini*. *Catalogo della Collezione G. Dattari*, Cairo, 1901 (reprint, 1969).
- L.F.J.C. De Sauley, *Numismatique de la Terre Sainte*, Paris, 1874.
- T.L. Donaldson, *Architectura Numismatica*, London, 1859 (reprint, 1966).
- Thomas Drew-Bear, "Representations of Temples on the Greek Imperial Coinage," *American Numismatic Society Museum Notes* 19, 1974, 27-63.
- Günter Fuchs, *Architekturdarstellungen auf römischen Münzen der Republic und der frühen Kaiserzeit* (Deutsches Archäologisches Institut, *Antike Münzen und geschnittene Steine*, ed. Erich Boehringer, No. 1) Berlin, 1969.
- Philip Grierson, *Bibliographie numismatique*, Bruxelles, 1966.
- Konrad Kraft, *Das System der Kaiserzeitlichen Münzprägung in Kleinasien, Materialien und Entwürfe*, Berlin, 1972.
- Fernand Chapouthier, *Les Dioscures au service d'une déesse. Étude d'iconographie religieuse*, Paris, 1936.
- Tony Hackens, "Architectura Numismatica, à propos de quelques publications récentes," *L'Antiquité Classique*, xli, 1972, 244-254.
- F. Imhoof-Blumer and P. Gardner, *A Numismatic Commentary on Pausanias*, London, 1887 (*Journal of Hellenic Studies*, 6, 1885; 7, 1886, 8, 1887) (reprint, 1964).
- Harald Kühmann et al. (Antike) *Bauten Roms auf Münzen und Medaillen*, München, 1973.
- L. Lacroix, *Les reproductions de statues sur les monnaies grecques*, Liège, 1949.
- Josef Liegle, "Architekturbilder auf antiken Münzen," *Die Antike, Zeitschrift für Kunst und Kultur der Klassischen Altertums*, xii, 1936, 202-228.
- Mattingly, Sydenham, Sutherland, Kent, and Carson, *Roman Imperial Coinage*, British Museum, 1923 (in progress).
- George C. Miles, "Mihrab and Anazah: A Study in Early Islamic Iconography," *Archaeologica Orientalia in Memoriam Ernst Herzfeld*, New York, 1952, 156-171.
- J.C. Milne, University of Oxford, Ashmolean Museum, *Catalogue of the Alexandrian Coins*, Oxford, 1933. (New Edition, 1971).
- J.C. Milne, "Pictorial Coin Types at the Roman Mint in Alexandria," *Journal of Egyptian Archaeology*, 1943, 1950, 1951, continued by J.W. Curtis, *ibid.*, 1955.
- Erwin Ohlenutz, *Die Kulte und Heiligtümer der Götter in Pergamon*, Darmstadt, 1940 (reprint, 1968).
- M. Jessop Price, "Architecture on ancient coins," *The Classical Tradition* (The British Museum Yearbook 1, 1976) 33-47.
- Kurt Regling, "Die Münzen als Hilfsmittel der archäologischen Forschung," *Walter Otto, Handbuch der Archäologie*, München, 1939, 134-144. (Reprint, 1969).

- J. Rouvier**, "Numismatique des villes de la Phénicie," *Journal internationale d'archéologie numismatique*, Athens, 3, 1900, 125-168, 237-312; 4, 1901, 35-66; 5, 1902.
- Henri Seyrig**, *Antiquités Syriennes*, 5 volumes, Paris, 1934-1958.
- Bluma L. Trell**, *Architectura Numismatica*, Part II, Temples in Asia Minor, New York University, 1942, diss. unpublished.
- Bluma L. Trell**, "Architecture on Ancient Coins," *Archaeology*, 1976, 6-13.
- W.H. Waddington, E. Babelon, Th. Reinach**, *Recueil générale des monnaies grecques d'Asie Mineure*, 1904-1924.

GENERAL

- A. Boëthius and J.B. Ward-Perkins**, *Etruscan and Roman Architecture*, Harmondsworth, 1970.
- V. Chapot**, *La colonne torse et le decor en hélice dans l'art antique*, Paris, 1907.
- L. Crema**, *L'architettura romana* (Enciclopedia classica, sezione, III: Archeologia e storia dell'arte classica, xii, 1), 1959; idem., *Manuale di storia dell'architettura antica*, Milano, 1962.
- W.B. Dinsmoor**, *Architecture of Ancient Greece, An Account of its Historic Development*, London/New York, 1950.
- M. Leglay**, *Saturne Africain*, Monuments I, 1961; II, 1966; *Histoire* (Bibliothèque des études Françaises d'Athènes et de Rome, fasc. 205), 1966.
- A.W. Lawrence**, *Greek Architecture*, London, 1957.
- W.H. Plommer**, *Ancient and Classical Architecture* (Simpson's History of Architectural Development, vol. 1) London/New York, 1956 (reprint, 1961).
- D.S. Robertson**, *A Handbook of Greek and Roman Architecture*, Cambridge, 1945.
- P. Romanelli**, *Topographia e archeologia dell'Africa Romana*; Rome, 1970.
- G. Taylor**, *Roman Temples of Lebanon, A Pictorial Guide*, Beyrouth, 1967.
- Enciclopedia dell'arte antica, classica e orientale*.
- Theodor Klausner**, *Reallexikon für Antike und Christentum* (in progress).
- Paulys**, *Realencyclopädie der classischen Altertumswissenschaft*.

HARBOURS

- Aline A. Boyce**, "The Harbour of Pompeiopolis, A Study in Roman Ports and Dated Coins," *American Journal of Archaeology*, 62, 1958, 66-78.
- Lionel Casson**, *Ships and Seamanship in the Ancient World*, Princeton, 1971, bibliography p. 367, note 22.

PORTABLE SHRINES

- Henri Seyrig**, *Syria*, xviii, 1937, 368-378; xlix, 1972, 104-108.

TOMB/ALTAR/SHRINE

- Paul Collart**, "La Tour de Qalaat Fakra," *Syria*, 1, 1973, 137-161.
- Paul Collart, and Pierre Coupel**, *L'Autel monumental de Baalbek*, Paris, 1951.
- René Dussaud**, "Temples et cultes de la Triade Héliopolitaine à Baalbek," *Syria*, xxiii, 1942/3, 33-37.
- Ernest Will**, "La Tour funéraire de Palmyre," *Syria*, xxvi, 1949, 89-116; Idem., "La tour funéraire de la Syrie et les monuments apparentés," *Ibid.*, 258-313.
- Klaus Shippman**, *Die iranischen Feuerheiligtümer* (Religionsgeschichtliche Versuche und Vorarbeiten, Bd. 31), Berlin/New York, 1971.
- Melmet Çetin Şahin**, *Die Entwicklung der griechischen Monumentaltäre*, Bonn, 1972.
- F. Studniczka**, "Altäre mit Grabenkammern," *Jahreshefte des Österreichischen archäologischen Institutes*, 6, 1903, 123-186.

NYMphaea

- O. Bernhardt, "Ueber Badeswesen und Hygienisches auf griechischen und römischen Münzen," Schweizerischen Numismatischen Rundschau, xxiv, 1928, 3-30.
- J. Des Gagniers, P. Devambez, L. Kahil, P. Ginouves, Laodicée du Lycos, Le Nymphée (Université Laval, Recherches Archéologiques, Series I, Fouilles, Campagnes, 1961-1963 Paris, 1969.
- Norman Neuerberg, L'architettura delle fontane e dei ninfei nell'Italia antica (Reale Accademia di archeologia, lettere e belle arti di Napoli, Memorie, 5) Naples, 1965.
- Salvatore Settis, "Esedra" e "Ninfeo" nelle Terminologie architettoniche del mondo romano dall'età repubblicana alla tarda antichità, Aufstieg und Niedergang der römischen Welt, Geschichte und Kultur Roms im Spiegel der neueren Forschung, hrsg. von Hildegard Temporini, I, Von Anfängen Roms bis zum Ausgang der Republik, 4 Bd., Berlin, 1973, 661-745.

ARCHES, ETC.

- M. Bieranacka-Lubanska, "Iconographie. Sources to the history of Roman aqueducts in Western Thrace," Archaeologia Polona, xiv, 1973, 315-329.
- A. Blanchet "Les villes fortifiées de péninsule balkanique d'après les monnaies de l'époque romaine" Bulletin Societati Numismatice Române 18, 1923, 1-14.
- F. Noack, Triumph und Triumphbogen, Vorträge der Bibliothek Warburg, hrsg., von Fritz Saxl, 1925/6, Berlin, 1928, 147 ff.
- M. Stuart, "The Denarius of M. Aemilius Lepidus and the Aqua Marcia," American Journal of Archaeology, 49, 1945, 222-251.
- D. Tudor, Podurile Romane de la Dunărea de Jos, Bucharest, 1971, 53-153.

ROME

- Marie R. Alföldi, "Signum Deae, die Kaiserzeitlichen Vorgänger des Reichsapfels," Jahrbuch für Num. und Geld, 11, 1961, 19-32.
- Aufstieg und Niedergang der römischen Welt, Geschichte und Kultur Roms im Spiegel der neueren Forschung, hrsg. von Hildegard Temporini, I; Von Anfängen Roms bis zum Ausgang der Republik, Bd. IV, Berlin, 1973, 636-639.
- Alfonso Bartoli, Curia Senatus, Lo Scavo ed il Restauro (Istituto di Studi Romani, I monumenti Romani, III) Roma, 1963.
- Alfonso Bartoli, "Il monumento della perpetuità del Senato," Studii Romani, ii, 2, 1954, 127-137.
- Axel Boethius, "Veteris Capitolii humilia tecta," Acta archaeologica et artium historiarum pertinentia, Inst. Rom. Norwegiae, Oslo Universitetsforlaget, 1962, 27-33; cf. Gjerstad's reply, Ibid., "A proposito della ricostruzione del Tempio arcaico di Giove Capitolino in Roma," 35-40.
- Donald F. Brown, Temples of Rome as Coin Types, Numismatic Notes and Monographs, 90, New York, 1940.
- Donald F. Brown, Architectura Numismatica, Part I: The Temples of Rome, New York University, unpublished diss., 1941.
- A.M. Colini, "Meta Sudans," Rendiconti, Atti della Pontificia accademia Romana di archeologia, 13, 1937, 15-39.
- Donald R. Dudley, Urbs Romana, a source book of classical texts on the city and its monuments selected and translated with a commentary, Phaidon, 1971 (Capitulum, 55-58, Curia 87-88).
- Günter Fuchs, Architekturdarstellungen auf römischen Münzen der Republik und der frühen Kaiserzeit (Deutsches Archäologisches Institut, Antike Münzen und Geschnittene Steine, ed. Erich Boehringer, Bd. 1) Berlin, 1969, passim.
- Einar Gjerstad, Early Rome, III, Fortifications, Domestic Architecture, Sanctuaries, Stratigraphic Excavations (Acta Instituti Romani, Regni Sueciae, xvii, 3) Lund, 1960, 168-204; Ibid., xvii, 4, Early Rome, IV, 2, Synthesis of the Archaeological Evidence, Lund, 1966, 388-398.
- Einar Gjerstad, "Discussions Concerning Early Rome, 3," Historia, xvi, 1967, 257-278.

- Tony Hackens**, *Histoire et iconographie du temple capitolin*. Dissertation, Univ. Catholique Louvain, 1962, Unpublished.
- Tony Hackens**, "De Tempol en de Goden van het kapitol op de romeinse Minten," *Exposition Numismatique*, Brussels, 1966, 33-36.
- Per Gustaf Hamberg**, *Studies in Roman Imperial Art with Special Reference to the State Reliefs of the Second Century*, Uppsala, 1945, 96 (reprint, 1968).
- Hans Jucker**, "Capitolium restitutum," *Jahrbuch des Bernischen Historischen Museums*, 1959/60, 289-295.
- Steven Lattimore**, "A Greek Pediment on a Roman Temple," *American Journal of Archaeology*, 78, 1974, 55-61.
- Ernest Nash**, *Pictorial Dictionary of Ancient Rome*, London, 1968 (Capitolium, 530-533, Colosseum, 16-25; 268-269; Curia, 287-289).
- A. Palladio**, *Le Terme dei Romani*, 1797. Tavv. v, vi, (Royal Institute of British Architects, vol. ii fol. i).
- Romolo A. Staccoli**, *Modelli di edifici etrusco-italici (Rome (City) Università. Istituto di etruscologia e antichità italiane. Studi e materiali, 6)* Florence, 1968.
- Bluma L. Trell**, "Architectura Numismatica, Early Types, Greek, Roman, Oriental," *Numismatic Chronicle*, xii, 1972, Capitolium, 53-54; Curia, 55-57.
- Bluma L. Trell**, *Num. Chron.* xiii, 1973, 225.
- E. Voerl**, "Die Darstellung eines Keltentempels auf einem Denar von Kaiser Augustus," *Jahrbuch der Schweizerischen Gesellschaft für Urgeschichte*, 1939, 150-157.
- A. Von Gerkan**, "Das Obergeschloss des flavischen Amphitheatres," *Römische Mitteilungen*, 40, 1925, 11-50.

ATHENS

- J. Svoronos**, *Les monnaies d'Athènes*, Munich, 1923-1926.
- John Travlos**, *Pictorial Dictionary of Ancient Athens*, New York, 1971.
- Paulys Supp.** xiii, 1973, s.v. Athenai, 56-139.

CORINTH

- Oscar Broneer**, "Hero Cults in the Corinthian Agora," *Hesperia*, ii, 1942, 128-161.
- Corinth**, *Results of Excavations conducted by the American School of Classical Studies at Athens*, vol. VI, 1, part 1^a, H.N. Fowler, Introduction, Architecture, 1932; vol. V, 1, part 2, Richard Stillwell, Architecture, 1941; vol. I, part vi, Bert Hodge Hill, The Springs, Peirene, Sacred Spring, Glauke, 1964, Princeton.
- W.B. Dinsmoor**, "Note on a Circular Monument in the Corinthian Agora" *Hesperia*, 11, 1942, 314-315.
- Robert L. Hohlfelder**, "Pausanias I, 2,3, A Collection of Archaeological and Numismatic Evidence," *Hesperia*, xxxix, 1970, 326-331.
- F.W. Imhoof-Blumer and P. Gardner**, *A Numismatic Commentary on Pausanias*, Supplement, 154-158, London, 1887 (reprint, 1964).
- Georges Roux**, *Pausanias en Corinthe (Livre II, 1 a 15)*, texte, traduction, commentaire archéologique et topographique (*Annales de l'Université de Lyons*, sér. 3, Lettres, fasc. 31) Paris, 1958.

DELPHI

- École Française d'Athènes**, *Fouilles de Delphes*, Tome II, F. Courby, *Le sanctuaire d'Apollon, La Terrasse du temple*, Paris, 1927.
- F.W. Imhoof-Blumer and P. Gardner**, *A Numismatic Commentary on Pausanias*, London, 1887. (reprint, 1964), 118-123.

AMASEIA

- J.G.C. Anderson, "A Journey of Exploration in Pontus," *Studia Pontica*, I, Bruxelles, 1903, 47-50.
J.G.C. Anderson, Franz Cumont, Henri Grégoire, *Recueil des inscriptions grecques et latines du Pont, de l'Arménie*, *Studia Pontica*, III, fasc. I., Bruxelles, 1910, 109-148.
A.R. Bellinger, "The Eighth and Ninth Dura Hoards," *Numismatic Notes and Monographs* 85, New York, 1939, 9-13.
Franz Cumont et Eugene Cumont, "Voyage d'exploration archéologique dans le Pont et la petite Arménie," *Studia Pontica*, II, Bruxelles, 1906, 138-184.
Maximova, M.I., *Cities of The Black Sea (Russian)* Moscow/Leningrad, 1956.
W.H. Waddington, E. Babelon, Th. Reinach, *Recueil général de monnaies d'Asie Mineure*, vol. I, fasc. i, Paris, 1904, 26-42.

NEOCAESAREA

- A.R. Bellinger, *The Coins; The Excavations at Dura-Europos, Final Report, VI*, New Haven, 1949, pl. xl, figs. 1995-2023.
Paulys. Suppl. x (1965) s.v. Neocaesarea 485; xvi (1933), 2409-2413.
Franz Cumont, "Voyage d'exploration archéologique dans le Pont et la petite Arménie," (*Studia Pontica*, II) 1906, 267-273.
Henri Seyrig, "Une déesse Anatolienne," *Antike Kunst*, 13, 1971, 76-78.
Rudolf Winks, *Clipeata Imago, Studien zu einer römischen Bildnisform*, Bonn, 1969, 130.

NICAEA

- Cevriye Artuk, "Die Tempel von Nikaia nach Münzdarstellungen," *Türk Tarih Kongresi*, Ankara, 1961, 38-49.
Alfons Maria Schneider, "The City Walls of Nicaea," *Antiquity*, xii, 1938, 437-443.
Alfons Maria Schneider, *Die römischen und Byzantinischen Denkmäler von Iznik-Nicaea (Istanbuler Forschungen des archäologischen Institutes des Deutschen Reiches, Abteilung Istanbul, Bd. 16)* Berlin, 1943.
Alfons Maria Schneider and Walter Karnapp, *Die Stadtmauer von Iznik (Nicaea) (Istanbuler Forschungen des archäologischen Institutes des Deutschen Reiches, Abteilung Istanbul, Bd. 9)* Berlin, 1938.
W.H. Waddington, E. Babelon, Th. Reinach, *Recueil générale des monnaies grecques d'Asie Mineure*, Vol. I, 3, 395-511.

TROY

- Alfred R. Bellinger, *Troy, Excavations Conducted by the University of Cincinnati, 1932-1938. The Coins*, Princeton, 1961; cf. review by L. Robert, *Monnaies Antiques on Troade (Hautes Etudes Numismatiques, 1)* Paris, 1966.
G.W. Blegen, C.G. Boulter, J.L. Casky, M. Mawson and J. Sperling, *Troy, Excavations conducted by the University of Cincinnati, Princeton*, vol. ii, 1951; vol. iii, 1953; vol. iv, 1958.
F.W. Goethart and H. Schelf, *Der Athena Tempel von Ilion*, (*Deutsch. Arch. Inst. Denkmäler antiker Architektur*, x) Berlin, 1962. cf. review by H. Kähler, *Gnomon* xxxvi, 1964, 79-87.
Heiner Knehl, "Der Athenatempel in Ilion, eine Korrektur zur Grundrissekonstruktion," *Athenische Mittheilung*, 88, 1973, 131-133.
Anna Sadurska, *Les Tables Iliques (Centre d'archéologie méditerranéenne de l'Académie Polonaise de Sciences)* Warsaw, 1964, p.28.

CYZICUS

- Bernard Ashmole, "Cyriac of Ancona and the Temple of Hadrian at Cyzicus," *Journal of the Warburg Institute*, 19, 1956, 179-191.
- A. Boëthius and J. Ward-Perkins, *Etruscan and Roman Architecture*, Hammondsworth 1970, 392, 478/9, 574(18)¹⁴.
- Bernard Goldman, *The Sacred Portal, a Primary Symbol in Ancient Judaic Art*, Detroit, 1966, passim.
- Hans Peter Laubscher, "Zum Fries des Hadrianstempel in Kyzikos," *Istanbuler Mitteilungen* (Deutsches Archäologisches Institut, Abteilung Istanbul), Bd. 17, 1967, 211-217.
- Phyllis Williams Lehmann and Karl Lehmann, *Samothracian Reflections, Aspects of the Revival of the Antique* (Bollingen Series, xcii) Princeton, 1973, 27-56.
- Fernand Robert, *Thyméle, recherches sur la signification et la destination des monuments circulaires dans l'architecture religieuse de la Grèce* (Bibliothèque des écoles Françaises d'Athènes et Rome, Fasc. 147), Paris, 1939.
- G. Roux, *L'architecture de l'Argolide au IV^e et III^e siècles av. J.C.*, Paris, 1961, 131-200.

PARIUM

- Bluma L. Trell, "Tomb, Altar or Shrine? - The Numismatic Evidence," *Transactions of the International Numismatic Congress*, New York/Washington, D.C., September, 1973, (Basel, 1976), 163-169.
- Paulys Suppl., xii 1970, s.v. Parion, 982-986.

PERGAMUM

- A. Boëthius and J. Ward-Perkins, *Etruscan and Roman Architecture*, Hammondsworth, 1970, 476-479.
- Königliche Museen zu Berlin, *Altertümer von Pergamon*, Berlin, 1885 - III¹ Jakob Schrammen, *Der Grosse Altar. Der Obere Markt*, 1906, III² Hermann Winnefeld, *Der Fries des grossen Altars*, 1910.
- Elisabeth Rohde, *Pergamon, Burgberg und Altar* (Staatliche Museen zu Berlin, Antiken-Sammlung) Berlin, 1969, 99-102.
- Maria Floriani Squarclapino, *Leptis Magna*, Basel, 1966.

EPHESUS

- Anton Bammer, *Die Architektur des jüngeren Artemision von Ephesos*, (Veroff. d. Deutsch. Arch. Inst.) Wiesbaden, 1972.
- Anton Bammer, "Recent Excavations at the Altar of Artemis in Ephesos," *Archaeology*, 27, 1974, 202-205.
- Anton Bammer, *Istanbuler Mitteilungen*, 25, 1975, 319-334.
- Robert Fleischer, *Artemis von Ephesos und verwandte Kultstatuen aus Anatolien und Syrien*, Leiden, 1973.
- Hugh Plommer, "St. John's Church, Ephesus," *Anatolian Studies*, 12, 1962, 119-129.
- Paulys Suppl. xii (1970), s.v. Ephesos, 1654-1673; 1666-1673.
- Brunhilde Sesmondo Ridgway, "A Story of Five Amazons," *American Journal of Archaeology*, 78, 1974, 1-17.
- Sabine Schultz, *Die Münzprägung von Magnesia am Mäander in der römischen Kaiserzeit*, Berlin, 1975.
- Bluma L. Trell, *The Temple of Artemis at Ephesos*, (Numismatic Notes and Monographs, No. 107), New York, 1945.

SAMOS

- Helmut Berve and Gottfried Gruben, *Griechische Tempel und Heiligtümer*, München, 1961, 236-243, 282.
- Thomas Drew-Bear, "Representations of Temples on the Greek Imperial Coinage," *American Numismatic Society Museum Notes*, 19, 1974, 27-63.
- Oscar Reuther, *Der Heratempel von Samos seit der Zeit des Polykrates*, Berlin, 1957.

- Rinate Tölle, *Die Antike Stadt Samos, ein Führer*. (Deutsches. Archäologisches Institut, Athens), Mainz, 1969, bibl., p. 120.
- Bluma L. Trell, *The Temple of Artemis at Ephesos*, Numismatic Notes and Monographs, No. 107, New York, 1945, 33-35.
- Hans Walter, *Das griechische Heiligtum, Heraion von Samos*, München, 1965.

SARDIS

- Bulletin, *American Schools of Oriental Research*, 154, 1959; 157, 1960; 158, 1960; 162, 1961; 166, 1962; 170, 1963; 191, 1968; 199, 1970, bibl. pp. 7-8; 203, 1971; 206, 1972; 211, 1973, bibl. pp. 14-15, note I. (Excavation Reports).
- K.S. Frazer, C.H. Greenwalt, Jr., G.M.A. Hanfmann, *Sardis, Report I*, Harvard University Press, 1976.
- Gottfried Gruben und Peter Robert Franke, "Beobachtungen zum Artemis-Tempel von Sardis," *Mitteilungen des Deutschen Archäologischen Institutes, Athenischen Abteilung*, bd. 76, 1961, 155-208.
- George M.A. Hanfmann, "Greece and Lydia," 8^{me} Congrès internationale d'archéologie classique. le rayonnement des civilisations grecque et romain sur les cultures périphériques, Paris, 1963, Paris, 1965, 490-500.
- George M.A. Hanfmann, *From Croesus to Constantine, the cities of Western Asia Minor and the Art in Greek and Roman times*, Michigan University, Paris, 1975.
- George M.A. Hanfmann, *Letters from Sardis*, Cambridge, 1973.
- F. Imhoof-Blumer, "Die Lydische Kore", *Nomisma, Untersuchungen auf dem Gebiete der Antiken Münzkunde*, viii, 1913, 20-22.
- A.E.M. Johnston and T.V. Buttrey, "Greek and Roman Coins Found at Sardis," *Bulletin. American School of Oriental Research*, 211, 1973, 34-36, A full publication of the coins found in the Sardis excavations, and a die study of the mint of Sardis is in press.
- P.R. Métraux, "A New Head of Zeus from Sardis," *American Journal of Archaeology*, 75, 1971, 155-159.
- John Griffiths Pedley, *Sardis in the Age of Croesus*, Oklahoma University Press, 1968, 9.
- John Griffiths Pedley, *Ancient Literary Sources of Sardis (Archaeological Exploration of Sardis, Monograph 2)* Harvard University Press, 1972, nos 276-7.
- Bluma L. Trell, *The Temple of Artemis at Ephesos*, Numismatic Notes and Monographs, no. 107, New York, 1945, 36-39.
- Bluma L. Trell, "Tomb, Altar or Shrine? - The Numismatic Evidence," *Transactions of the International Numismatic Congress*, New York/Washington, D.C., September, 1973, (Basel, 1976), 163-169.

SELGE

- Helène Danthine, *Le palmier-dattier et les arbres sacrés dans l'iconographie de l'Asie occidentale ancienne*, "Paris, 1937.
- Robert Fleischer, "Selge", *Jahrbuch Österreichisches Archäologisches Institut, Grabungen*, 1968, 19-23.
- M. Leglay, *Saturne Africain, Histoire* (Bibliothèque des Écoles Françaises d'Athènes et de Rome, fasc. 225), Paris, 1966, see especially pp. 288-9 for barriers.
- A.A. Mansel, "Osttor und Waffenrelief von Side," *Archäologischer Anzeiger*, (Beiblatt zum Jahrbuch des Deutschen Archäologischen Institutes) Berlin, 1968, 260-261, 272.
- Bluma L. Trell, "Tomb, Altar or Shrine? - The Numismatic Evidence," *Transactions of the International Numismatic Congress*, New York/Washington, D.C., September, 1973, (Basel, 1976), 163-169.

PAPHOS

- Einar Gjerstadt, *The Cypro-Geometric, Cypro-archaic and Cypro-classical Periods* (The Swedish Cyprus Expedition, vol. iv, part 2) Stockholm, 1948, 428-453.
- Sir George Hill, *A History of Cyprus*, Cambridge, vol. I, 1940.

- V. Karageorghis, "A representation of a temple on an 8th century B.C. Cypriot Vase," *Rivista di studi fenici*, I, 1974, 9-13.
- F.G. Maier, "Ausgrabungen in Alt Paphos" *Archäologischer Anzeiger*, Beiblatt zur *Jahrbuch*, 1967, 303-330.
- F.G. Maier, "Alt Paphos auf Zypern," *Antike Welt*, II, 1971 (Zurich), 3-114.
- Bogdan Rutkowski, *Cult Places in the Aegean World* (Polish Academy of Sciences, Institute of the History of Material Culture) *Bibliotheca antiqua* x, Warsaw, 1972, passim.
- Bluma L. Trell, "Architectura Numismatica Orientalis, A Short Guide to the Numismatic Formulae of Roman Syrian Die-Makers," *Numismatic Chronicle*, x, 1970, 42-43.
- Olaf Vessberg and Alfred Westholm, *The Hellenistic and Roman Periods in Cyprus* (The Swedish Cyprus Expedition, vol. iv, part 3) Stockholm, 1956, 1-8.
- Alfred Westholm, "The Paphian Temple of Aphrodite and its relation to Oriental Architecture," *Acta Archaeologica*, iv, 1933, 201-236.

BYBLOS

- Paul Collart, "La tour de Qalaaat Fakra," *Syria*, I, 1973, 137-161.
- R. Donceel, "Recherches archéologiques au Liban, 1962-1965", *L'antiquité classique*, xxxv, 1966, 232-237.
- Robert du Mesnil du Buisson, *Études sur les dieux phéniciens hérités par l'Empire Romain* (Études préliminaires aux religions orientales dans l'Empire Romain, tome 14) Leiden, 1970, 56-72.
- Robert du Mesnil du Buisson, *Nouvelles études sur les dieux et les mythes de Canaan* (Études préliminaires aux religions orientales dans l'Empire Romain, tome 33), Leiden, 1973, 88-89.
- Maurice Dunand, *Byblos, son histoire, ses ruines, ses légendes*,² Beyrouth/Paris, 1968.
- H. Kalayan, "Rapport préliminaire sur les travaux de reconnaissance du site de Maschnaka," *Mathaf, Bulletin du musée de Beyrouth*, xvii, 1964, 107-110.
- Henri Seyrig, "La résurrection d'Adonis et le texte de Lucien," *Syria*, xlix, 1972, 97-100.
- Henri Seyrig, "Intailles relatives à des cultes Syriens," *Syria*, 1972, 109-112.
- Bluma L. Trell, "Architectura Numismatica Orientalis, A Short Guide to the Numismatic Formulae of Roman Syrian Die-Makers," *Numismatic Chronicle*, x, 1970, 31-32.
- Bluma L. Trell, "Tomb, Altar or Shrine? - The Numismatic Evidence," *Transactions of the International Numismatic Congress*, New York/Washington, D.C., September, 1973, (Basel, 1976), 163-169.

SIDON

- M. Jean Babelon, "Le voile d'Europe," *Revue archéologique*, 1942/3, 125-140.
- Winfried Bühler, *Europa, ein Überblick über die Zeugnisse des Mythos in der antiken Literatur und Kunst*, München, 1968.
- Robert du Mesnil du Buisson, "L'ancien dieu Tyrien Ouoo sur des monnaies de Tyre," *Mélanges de l'Université Saint-Joseph*, Tome xli, fasc. 1, 1965, 1-27.
- Robert du Mesnil du Buisson, *Études sur les dieux phéniciens, hérités par l'Empire Romain* (Études Préliminaires aux religions orientales dans l'Empire Romain, Tome 14), Leiden 1970, passim.
- Robert du Mesnil du Buisson, *Nouvelles études sur les dieux et des mythes de Canaan* (Études préliminaires aux religions orientales dans l'Empire Romain, Tome 33) Leiden, 1973, 99-125.
- Adolf G. Horn, "Canaan and the Aegean Sea; Greco-Phoenician, Origins Reviewed," *Diogenes* 58, 1967, 37-61.
- René Mouterde, S.J. "Regards sur Beyrouth Phénicienne, Hellénistique et Romaine, *Mélanges de l'Université Saint-Joseph*, Tome xl, fasc. 2, 1964, 145-181.
- Bogdan Rutkowski, *Cult Places in the Aegean World* (Polish Academy of Sciences, Institute of the History of Material Culture) *Bibliotheca antiqua*, x, Warsaw, 1972, pp. 163-7, 197-203, p. 264. no. 17.
- S. Schaeffer, "Marsyas et les Phrygiens en Syrie," *Revue des Études Antiques*, xxi, 1919, 239-248.
- Bluma L. Trell, "Architectura Numismatica Orientalis, A Short Guide to the Numismatic Formulae of Roman Syrian Die-Makers," *Numismatic Chronicle*, x, 1970, 29-50.

BAALBEK-HELIOPOLIS

- Robert Amy, "Temples à escaliers," *Syria*, xxvi, 1950, 82-136.
 Robert Amy, "La reconstruction de l'autel monumental de Baalbek," *Rev. arch.*, 1953, 50-67.
 A. Boëthius and J. Ward-Perkins, *Etruscan and Roman Architecture*, Harmondsworth, 1970, 417-426.
 Donald F. Brown, "The Arcuated Lintel and the Symbolic Interpretation in Late Antique Art," *American Journal of Archaeology*, 46, 1942, 389-399.
 Paul Collart and Pierre Coupel, *L'autel monumental de Baalbek* (Institut Français d'Archéologie de Beyrouth. Bibliothèque Archéologique et Historique, vol. lii) Paris, 1951; cf. review E. Bradford Wells in *American Journal of Archaeology*, 57, 1953, 155-156.
 R. Donceel, "Recherches et travaux, archéologiques récents au Liban, 1962-1965," *L'antiquité classique*, xxxv, 1966, 224-254.
 René Dussaud, "Jupiter Héliopolitain, bronze de la collection Charles Sursock," *Syria*, I, 1920, 3-15.
 René Dussaud, "Temples et cultes de la Triade Héliopolitaine à Baalbek," *Syria*, xxiii, 1942/3, 33-77.
Enciclopedia dell'arte antica, classica e orientale, (1960), s.v. Heliopolis, 1137-1140.
 Kazimierz Michalowski, *Art of Ancient Egypt*, n. d. Edfu, 544-546. Denderah, 501-505.
 Henri Seyrig, "Nouveaux monuments de Baalbek et la Becque," *Bulletin du Musée de Beyrouth*, xvi, 1961, 109-135.
 Henri Seyrig, "Le Culte du Soleil en Syrie à l'époque romaine," *Syria*, xlviii, 1971, 345-349.
 George Taylor, *The Roman Temples of Lebanon, a Pictorial Guide*, Beyrouth, 1967, 32-51.
 Gustavo Traversari, *Gli spettacoli in Acqua nel teatro tardo-antico*, Roma, 1960, 98-103.
 D. Winnefeld, "Zur Geschichte des Syrischen Heliopolis," *Rheinisches Museum für Philologie* 69, 1914, 139-159.

EMISA

- Hans Roland Baldus, *Uranus Antoninus, Münzprägung und Geschichte* (Antiquitas. Abhand. zur Vor- und Früh-Geschichte zur Klass. und prov. Röm. archäologie und zur Geschichte. Altertums. Bd. 11) Bonn, 1971.
 Henri Seyrig, "Antiquités Syriennes, 76. Caractères de l'histoire d'Émèse," *Syria*, xxxvi, 1959, 184-192.
 Henri Seyrig, "Culte du Soleil en Syrie, II, Émèse," *Syria*, xlviii, 1971, 340-345.

NEAPOLIS, SAMARIA

- Biblical Archaeologist*, xxvi, 1965; xxxi, 1968; 1969 (Excavation Reports).
 R.J. Bull, "A Preliminary Excavation of an Hadrianic Temple at Tell-er-Ras on Mt. Gerizim," *American Journal of Archaeology*, 71, 1967, 387-393.
 R.J. Bull, "The Two Temples at Tell er Ras on Mt Gerizim in Occupied Jordan," *American Journal of Archaeology*, 74, 1970, 189-190.
 R.J. Bull, and G.E. Wright, "Newly Discovered Temples on Mt. Gerizim (Hadrianic)," *Harvard Theological Review*, lviii, 1965, 234-237.
Bulletin of the American Schools of Oriental Research, 190, 1968: 204, 1971: 205, 1972.

JERUSALEM

- M. Avi-Yonah, "The Facade of Herod's Temple, an Attempted Reconstruction," *Essays in Memory of E. R. Goodenough*, Leiden, 1968, 327-335.
 F. Bickerman, "Une proclamation Séleucide relative au Temple de Jérusalem," *Syria*, xvi, 1946-8, 67-85.
Le Compte du Mesnil du Buisson, "L'inscription de la niche central de la synagogue de Doura-Europos," *Syria*, 1963, 303-314.
 Bernard Goldman, *The Sacred Portal, A Primary Symbol in Ancient Judaic Art*, Detroit, 1966, passim.
 Carl H. Kraeling, *The Synagogue* (The Excavations at Dura Europos. Final Report viii, 1), New Haven, 1956, 84-86.

- A. Muehsam, *Coin and Temple, a Study of the Architectural Representation on Ancient Jewish Coins*, (Near Eastern Research, 1, Leeds University Oriental Society) Leiden, 1966.
- André Parrot, *Le Temple de Jérusalem* (Cahier d'archéologie biblique, 5), New York, 1955.

ALEXANDRIA

- M.L. Bernhard, "Quelques remarques sur Alexandria," *Revue archéologique*, 1972, 317-320. Pharos lamp, see fig. 2.
- Danielle Bonneau, *Le Fisc et le Nil, incidences des irrégularités de la crue du Nil sur la fiscalité foncière dans l'Égypte grecque et romaine*, Paris, n.d. (1971?).
- B.W. Deusser, "A Numismatic Contribution to the Evidence for Dating the Building Program of the Alexandrian Serapis Temple," unpublished paper submitted to the American Numismatic Society Seminar, 1968.
- L. Fourcher, "Les Mosaïques Nilotiques Africaines," *Colloques Internationaux du Centre National de la recherche scientifique, sciences humaines, la mosaïque Gréco-Romaine*, Paris, Aout-Sept., 1963, Paris, 1968, 137-145.
- P.M. Frazer, *Ptolemaic Alexandria*, Oxford, 1972.
- J. Hackin and J.R. Hackin, *Recherches Archéologiques à Begram, chantier 2* (Mémoires de la délégation archéologique française en Afghanistan, Tome IX) Paris, 1939, 42-44.
- J. Hackin, J. Auboyer, V. Elisséeff, O. Kurz, Ph. Stern, *Rencontre de Trois Civilisations, Inde-Grèce-Chine, Nouvelles recherches archéologiques à Begram (ancien Kapici), 1939-1940* (Mémoire de la délégation archéologique française en Afghanistan, Tome XI), Paris, 1954, 101-102.
- Susan Handler, "Architecture on Roman Coins of Alexandria," *American Journal of Archaeology*, 75, 1971, 57-74.
- Susan Handler, *The Architecture of Alexandria in Egypt as depicted on the Alexandrian Bronze Coinage of the Roman Imperial Period*, unpublished dissertation, Bryn Mawr, 1967/8.
- William Hornbostel, "Sarapis, Studien zur Überlieferungsgeschichte den Erscheinungsformen und Wandlung der Gestalt eines Gottes," Leiden, 1973, see index, s.v. Serapeum.
- S. Loescheke, *Antike Lampen und Lichthäuschen*, Bonner Jahrbücher, Jahrbücher des Vereins von Altertums Freunden in Rheinlands, 118, 1909, 307-430.
- Kazimierz Michalowski, *Art of Ancient Egypt*, New York, 1970, Alexandria, 501-505; Kom Ombo, 547, fig. 936.
- P. Pfister, "Nil, Nilomètre et l'orientalisation du paysage Hellénistique," *Revue des Arts Asiatiques*, vii, 1931, 120-140.
- Charles Picard, "Sur quelques représentations nouvelles du Phare d'Alexandrie et sur l'origine alexandrine des paysages portuaires," *Bulletin de Correspondence Hellénique*, lxxvi, 1952, 61-95.
- M. Th. Picard-Schmitter, "L'Allégorie de l'Égypte sur un relief provenant de Carthage," *Revue archéologique*, 1971, 29-56.
- Paulys Suppl. xii, 1970, Nachträge, s.v. Ephesos, 1652-1654.
- Alan Rowe, *Discovery of the Famous Temple and Enclosure of Serapis at Alexandria with an explanation of the enigmatical inscriptions on the Serapeum plaques of Ptolemy IV by Etienne Drioton* (Supplément aux Annales des Services des Antiquités de l'Égypte, Cahier 2) Cairo, 1946.
- Alan Rowe, B.R. Rees, "A Contribution to the Architecture of the Western Desert, IV, The Great Serapeum of Alexandria," *Bulletin of the John Rylands Library*, 1957, 484-520.
- R. von Salditt-Trappman, *Tempel der Ägyptischen Götter in Griechenland und an der Westküste Kleinasien* (Études préliminaires aux religions orientales dans l'Empire Romain, Tome 15, Leiden, 1970).
- John E. Stambaugh, *Sarapis under the Early Ptolemies* (Études préliminaires aux religions orientales dans l'empire Romain, tome 25), Leiden, 1972, 79-84.
- Durk Wortman, "Kosmogonie und Nil Flut," *Bonner Jahrbücher des rheinischen Landesmuseums in Bonn und des Vereins von Altertums Freunden in Rheinlande*, Bd. 166, 1966, 62-112.

ABBREVIATIONS USED IN THE CATALOGUE

AMNG	B. Pick et al., Die Antiken Münzen Nord-Griechenlands (Berlin, 1898).
Ann.Soc.Num.	Annuaire de la Société française de numismatique et d'archéologie (Paris).
ANS	The American Numismatic Society
Arch. Anz.	Archäologischer Anzeiger.
Arch. Polona	Archaeologia Polona (Warsaw).
Babelon, Perses	E. Babelon, Les Perses Achéménides (Paris, 1893).
Beltran	A. Beltran, Curso di Numismatica I, Numismatica antigua (Cartagena, 1950).
BM	The British Museum.
BMC	Catalogue of Greek Coins in the British Museum.
BMCRE	Coins of the Roman Empire in the British Museum.
CNP	Corpus Nummorum Palaestinensium (Tel Aviv/Jerusalem, 1956-).
Dattari	G. Dattari, Monete imperiali greche, Num. Augg. Alexandrini Cairo, 1901).
De Saulcy	L.F.J.C. de Saulcy, Numismatique de la Terre Sainte (Paris, 1874).
Garrucci	P.R. Garrucci, Le Monete dell' Italia antica (Rome, 1885).
Grant FITA	M. Grant, From Imperium to Auctoritas: A historical study of the aes coinage in the Roman Empire 49 B.C.-A.D.14 (Cambridge, 1946)
Hunter	G. Macdonald, Catalogue of Greek Coins in the Hunterian Collection University of Glasgow (1899-1905).
Imh. Bl. Gr.u. Rom.	F. Imhoof Blumer, Zur griechischen und römischen Münzkunde (Geneva, 1908).
JEA	Journal of Egyptian Archaeology.
JNG	Jahrbuch für Numismatik und Geldgeschichte
Jurukova	J. Jurukova, Die Münzprägung von Deultum (Berlin, 1973).
KIM	F. Imhoof Blumer, Kleinasiatische Münzen (Vienna, 1901-2).
Lyd. Stadtm.	F. Imhoof Blumer, Lydische Stadtmünzen (Geneva/Leipzig, 1897).
Mabbot	Hans F.C. Schulman (New York) Sale catalogue 6-11 June 1969.
Mazard	J. Mazard, Corpus Nummorum Numidiae Mauretaniaeque (Paris, 1955).
Meshorer	Y. Meshorer, Jewish Coins of the second Temple period (Tel Aviv, 1967).
Mouchmov	N.A. Mouchmov, Ancient Coins of the Balkan Peninsular (Sofia, 1967).
MundM	Münzen und Medaillen A.G., Basel.
NC	Numismatic Chronicle.
NCP	F. Imhoof Blumer and P. Gardner, A numismatic Commentary on Pausanias (London, 1887).
Oeconomidou	M. Oeconomidou, The Coinage of Nicopolis (Athens, 1975).
Pick, Bulgarien	R. Pick, Münzbilder aus Bulgariens (Gotha, 1931).
Receuil	W.H. Waddington et al. Receuil général des monnaies grecques d'Asie Mineure (Paris, 1904-1925).
Rhein. Mus. f. Philol.	Rheinisches Museum für Philologie.
Robert	A. Dupont Sommer and L. Robert, La déesse de Hierapolis Castabala (Paris, 1964).
Schonert	E. Schonert-Geiss, Die Münzprägung von Perinthos (Berlin, 1965).
SNG ANS	Sylloge Nummorum Graecorum. The American Numismatic Society.
SNG Cop	Sylloge Nummorum Graecorum, The Royal Collection of Coins and Medals, Danish National Museum.
SNG FW	Sylloge Nummorum Graecorum, Fitzwilliam Museum, Cambridge.
SNG vonA	Sylloge Nummorum Graecorum, Sammlung von Aulock.
Sydenham	E.A. Sydenham, The Coinage of Caesarea in Cappadocia (London, 1933).
vA MinL	H. von Aulock, Die Münzprägung der Gordian III und der Tranquillina in Lykiens (Tübingen, 1974).

Vives
v.Fritze
Weber

ZfN

A. Vives. La Moneda Hispanica (Madrid, 1924–26).
H. von Fritze, Die antike Münzen Mysiens (Berlin, 1913).
L. Forrer, Descriptive Catalogue of the Collection of Greek Coins formed by Sir
Hermann Weber (London 1926).
Zeitschrift für Numismatik (Berlin).

The Architectural Coin Types of the Ancient World
(Not including the coins of Rome)

This is a catalogue of the buildings in each city which appear on coins, not a catalogue of coin varieties. For ease of reference, different views of the same building — e.g. perspective views — are given separate entries; but all facades (for example) of the same building come under a single heading, with some note as to the varieties found in different examples. The appearance of the building at different times in a coin series is not distinguished, nor are coins of larger or smaller flans. Where the building forms part of the whole type — e.g. when held by a goddess — it is included only if it is not found as a separate type, or if it supplies a different view. Small altars, pillars, and other architectural fragments, are not included. Rome has been omitted because lists of building types can be easily found in such works as *Roman Imperial Coinage* and *Coins of the Roman Empire* in the British Museum. We have, however, illustrated several pieces.

The catalogue follows the normal numismatic order of geography, except that the cities of the province of Asia are listed alphabetically and not by ethnic areas. The provinces and geographical areas come in the order:

Hispania Citerior
Hispania Ulterior
Gaul
Italy
Sicily
Sardinia
Bosporus
Moesia
Thrace
Macedonia
Illyria
Epirus
Southern Greece
Aegean Islands
Pontus
Bithynia
Asia
Galatia
Pisidia
Lycia
Pamphylia
Cilicia
Cyprus
Commagene
Syria
Arabia
Mesopotamia

Parthia
Persia
India
Egypt

Each entry gives the type of building, the number of columns on the facade, with varieties where relevant, the deity illustrated as cult image, or named in a dedication, and other notes of architectural interest. A reference to one of our illustrations, or to another published illustration, or to the museum where a specimen may be found, is also given. This can only hope to be the briefest guide to the main varieties found in national museums and in published sources. The authors have made every effort to sift out misattributions and wrong descriptions that plague all work such as this, and in the main there are included only such coins as they have seen. They are fully aware that the list may be far from complete, and would welcome information on types not apparently included. As explained elsewhere, certain details such as arched lintels and spiral fluted columns, may have meaning for the appearance of the edifice, but may also be attributed to the artists decorative approach to the subject. Each building series requires a separate study with all examples collected. In the meantime the list may act as a guide to the buildings found at different cities, and in particular it underlines the quantity and variety of buildings depicted on ancient coins of the eastern Mediterranean.

City and Building (Columns)	Cult or Image	Remarks	Reference
Hispania Citerior			
Caesaraugusta			
1 Temple (4,6)	Augustus	Corinthian capitals	Vives pl.CL.3
Carthago Nova			
2 Temple (4)	Augustus	Pronounced door	Vives pl.CXXXI.13-6
Ilici			
3 Temple (4)	Juno	Pronounced door	Fig.37
Tarraco			
4 Temple (8)	Augustus	Corinthian capitals; sometimes with parotids	Vives pl.CLXX.3
Hispania Citerior			
Abdera			
5 Temple (4)	Solar cult	Pronounced doors	Vives pl.LXXXI.1-4
6 Temple (4)		Two fish (columns)	Fig.335
7 Temple (4)		Arched lintel	Paris
8 Two temples	Imperial cult?		Beltran p.50.Figs.10-13
Emerita			
9 Temple (4)	Augustus?		Vives pl.CXLIV.9-10
10 Gate with walls above			Fig.521
11 Altar		Ara Pacis type	Vives pl.CXLIV.17-10
Gades			
12 Temple (4)		Pronounced doors	Vives pl.LXXVII.4-5
Lascuta			
13 Stepped altar			Vives pl.CXII.8

City and Building (Columns)	Cult or Image	Remarks	Reference
Malaca			
14	Temple (4)	Solar cult	Vives pl. LXXXV.4
Gaul			
Vienne			
15	Gate and harbour buildings		Fig.62
Africa			
Cirta			
16	(Juba 1) Turreted gate	Two lower arches	Mazard 523
17	(Juba 1) Temple or portico (8)	Steps in front	Fig.508
18	(Juba 1) Temple or portico (5)	Three Atlas caryatids	Fig.38
19	(Juba 11) Temple (2, 4, 6) Augustus		Fig.128
Sabratha			
20	Temple (5)		Fig. 421
Italy			
Paestum			
21	Three storied building	Pitched roof, sometimes domed	Fig.475
22	Arcade (Basilica?)		SNG Cop. 1365
23	Temple (2)	Bona Mens	SNG Cop.1363
24	Temple (2) ¾ view		SNG ANS 782
25	Aedicula		Paris
Tarentum			
26	Dovecot?		Garrucci pl.C.33
Terina			
27	Fountain		Fig. 92
Sicily			
Himera			
28	Fountain in sanctuary		Fig. 91

City and Building (Columns)	Cult or Image	Remarks	Reference
Panormus			
29	Lighthouse or tower		Fig.67
30	Temple (4)		ANS
Selinus			
31	Altar in sanctuary		Fig.437
Sardinia			
Carallis			
32	Temple (4)	Venus	Pronounced doors Fig.120
Turris Libisonis?			
33	Temple (6)		Grant FITA p.205
Bosporus			
Panticapaeum?			
34	Gate		BM
35	Gate and walling		NC 1971 pl.24.1
36	Temple (5)	Capitolium type	SNG Cop.53
Moesia			
Callatis			
37	Gate	Figure in niche	Fig.88
Dionysopolis			
38	Temple (4)		Berlin
Marcianopolis			
39	View of city and forum		Fig.25
40	Temple (4)	Serapis	AMNG pLXX.25
41	Temple (4)	Tyche	SNG Cop.261
42	Temple (4)	Apollo and Pytho	AMNG pLXX.21
43	Arch	Four figures above	Fig.85
44	Gate	One or three openings	Figs.499,501

City and Building (Columna)	Cult or Image	Remarks	Reference
Nicopolis ad Istrum			
45	Gate	Palatial building above, and temple through gate	Fig. 26 (Colour p. 14)
46	Gate with walls above		Berlin
47	Temple ¾ view	Serapis ? Among trees	Fig. 402
48	Nymphaeum		Fig. 70 (Colour p. 49)
49	Temple (4)	Dionysus	BM
50	Temple (4)	Asclepius	AMNG pLXX
51	Temple (4)	Zeus	AMNG 1981
52	Temple (4)	Artemis	Mabbott 663
53	Temple (4)	Tyche	BM
54	Temple (4)	Concordia	SNG Cop. 290
55	Temple (4)	Serapis	Spiral flutes AMNG pLXX.22
56	Temple (5)		AMNG pLXX.17
57	Gate	Two towers	AMNG pLXX.13
58	Gate	Three towers	Berlin.
Odessus			
59	Temple (4)	Tyche	Parotids, spiral flutes Fig. 5 (Colour p. 32)
Tomi			
60	Temple (4)	Dionysus	JNG 1949, 626
61	Temple (4)	Tyche	AMNG pLXX.19
62	Temple (4)	Zeus	BM
63	Temple (4)	Imperial ?	BM
64	Temple (4)		Paris
65	Temple with colonnade in front		Mouchmov pL.V.23
66	Gate	Three or four openings	Fig. 500
Thrace			
Anchialus			
67	Gate	Surmounted by warrior	Fig. 87

City and Building (Columns)	Cult or Image	Remarks	Reference
68 Gate		Two towers	AMNG pl.VL17
69 Gate		Figure in niche	AMNG pl.VIL10
70 Turreted wall			AMNG pl.VL34
71 Temple (4)	Concordia	Spiral flutes	AMNG pl.VIII.28
72 Temple	Serapis		AMNG pl.VL35
Apollonia Pontica			
73 Temple (4)	Apollo		Pick, Bulgarien. Fig.23
74 Altar			Fig.441
Augusta Trajana			
75 Temple (4)	Serapis		BM
76 Temple (4)	Asclepius		BM
77 Aedicula (2)	Apollo	Barrel vault ?	Fig.490
78 City walls on hill			Mouchmov pl.xxix.9
79 Gate		Two or three towers	Fig.86 (Colour p.14)
80 Temple (4)	Artemis	On garlanded podium	Pick, Bulgarien, Fig.11
Bizya			
81 City view			Fig.24 (Colour p.101)
82 Gate with walls above			Mouchmov pl.XVIII.8
83 Gate			Fig.497
Deultum			
84 Temple (4)	Concordia		Jurukova 136
85 Temple (4)	Zeus/Serapis	Spiral fluted	Jurukova 133
86 Temple (4)	Asclepius	Window in pediment	Jurukova 343
87 Temple (4,6)	Apollo	Corinthian capitals	Jurukova 134
88 Temple (4)	Tyche		Jurukova 175
89 Temple (4)	Genius		Jurukova 379
90 Temple ¾ view	Serapis		Jurukova 262
91 Temple ¾ view	Aphrodite		Jurukova 261

City and Building (Columns)	Cult or Image	Remarks	Reference
92 Temple ¾ view	Apollo		Jurukova 263
93 Temple ¾ view	Asclepius ?		Jurukova 266
Hadrianopolis			
94 Temple (4)	Tyche	Spiral flutes	SNG Cop590
95 Temple (4)	Zeus	Spiral flutes	BM
97 Temple on podium	Artemis	Spiral flutes	Mouchmov pl. XIX.8
98 Gate			Fig.504
99 Nymphaeum			Fig.69
Maronea			
100 Temple (6)	Dionysus	Broken pediment	Fig.383
Pautalia			
101 Mountain with five temples and nymphs			Fig.29
102 Temple ¾ view	Asclepius	Among trees	Paris
103 Temple and 2 altars	Asclepius	With tree	Fig.434
104 Temple (4)	Asclepius		SNGFW 1741
Perinthus			
105 Temple (6,8)		Often with galley	Schonert 461
106 Two temples	Actia and Pythia		Schonert 519
107 Two temples ¾ view	Actia and Pythia	Held by Tyche	Fig.44
Philippopolis			
108 Temple (4,8)	Dionysus		Mouchmov pl.XXXII.3
109 Temple ¾ view		Often held by standing figures	Fig.416
110 Temple (4)	Tyche		BM
111 Temple (6)			Paris
111A City view with three hills			Arch. Polona 1973,321
111B Temple and colonnade on hill			Arch. Polona 1973,325
Serdica			
112 Temple (4)	Asclepius	Sometimes altar in front	BM
112A Aedicula (4)	Asclepius	On podium; conical roof	Numismatika (Sofia) 3.1970, 41.5

City and Building (Columns)	Cult or Image	Remarks	Reference
113 Fountain ?			Arch. Polona 1973, 317.
Sestus			
114 Tower of Hero			BM
Topirus			
115 Round shrine		Sometimes with horsemen	Figs. 471, 472.
Coela			
116 Temple (4)	Genius		BM
Macedonia			
Beroea (including koinon issues)			
117 Temple (4) on podium		With figures	BM (cast)
118 Temple ¾ view			AMNG III.1, pl. V.11
119 Aedicula (2)	Heracles (Farnese)		AMNG pLIV.33
120 Two temples		Sometimes with column between	Fig. 451
121 Two temples ¾ view			Paris
Cassandra			
122 Temple (2)	Dionysus		JNG 1949 pLII.22
123 Aedicula (2)	Zeus Ammon		AMNG pLXIII.15
Dium			
124 Temple (2)	Asclepius		SGN Cop 159
Edessa			
125 Temple (4)	Dionysus	Arcuated lintel	JNG 1949 pLII.25
Pella ?			
126 City view			Fig. 522
Stobi			
127 Temple (4)	Asclepius		AMNG pLXXI.24
128 Temple (4)	Dionysus		Paris
129 Temple (4) round ?			AMNG pLXXI.25

City and Buildings (Columns)	Cult or Image	Remarks	Reference
Thessalonica			
130 Temple (2,4)	Apollo Pythios	Sometimes without architrave	AMNG pl.XXIV.29
131 Temple ¾ view	Apollo Pythios		SNG Cop 435
132 Temple (2)	Cabeirus		AMNG pl.XXIV.12
133 Four temples	Neocorate		Fig.458
Illyria			
Apollonia			
134 Temple	Zeus	Corinthian capitals; among trees	Fig.436
135 Temple ¾ view	Apollo	Among trees	Fig.398
136 Temple ¾ view	Heracles	Altar to r.	BM
Epirus			
Buthrotum			
137 Aqueduct			Fig. 80
138 Temple (2)	Helios		Ashmolean
Nicopolis			
139 Temple ¾ view	Aktia ?	Porch of 2 columns	Oeconomidou pl.27.20
140 Temple (2,4)	Asclepius		Oeconomidou pl.42.186
141 Aedicula (2)	Nemesis ?		Oeconomidou pl.20.4
142 Aedicula (2)	Heracles Farnese		Oeconomidou pl.1.5
143 Altar			Oeconomidou pl.18.56
144 Gate			Oeconomidou pl.17.51-5
145 Fountain		Meta Sudans type	Fig.76
146 Domed two-storey structure (Heroon ?)			Fig.48
Corcyra			
147 Temple ¾ view	Apollo	Porch of two columns	Fig.400
148 Temple (6)			ANS
149 Aedicula (2)	Zeus Karios		BM
South Greece			
Delphi			
150 Temple (2,4,6)	Apollo		Fig.156

City and Buildings (Columns)	Cult or Image	Remarks	Reference
151 Temple ¾ view	Apollo		Fig. 155
152 Altar		With pediment	Fig. 157
Tanagra			
153 Temple (2,4)	Artemis		Fig. 427
154 Shrine (2)	Dionysus	2 Caryatids	Fig. 341
Chalcis			
155 Temple (2) in which baetyl			Fig. 19
Athens			
156 Acropolis		Impression often reversed	Figs. 130-1 (Colour p.68)
157 Theatre of Dionysus			Fig. 133 (Colour p.68)
Aegosthena			
158 Enclosure in which snake and tree			Athens
Megara			
159 Shrine (2) in which herm		Barrel vault ?	Fig. 495
160 Gate and harbour			Fig. 482
161 Temple ¾ view	Athena		Berlin
163 Processional shrine			Fig. 41
Pagae			
164 Shrine (2)	Artemis	Among trees	NCP pl. A.ii
165 Temple (2)	Isis		NCP pl. FF. iv
166 Gate in which Heracles		Two story	Fig. 512
167 Temple ¾ view			ANS
168 Arch		Three openings and figures	Fig. 498
Aegina			
169 Harbour			Fig. 59
170 Temple ¾ view		No roof	Fig. 411

City and Buildings (Columns)	Cult or Image	Remarks	Reference
Corinth			
171	Acrocorinth and temple of Aphrodite		Fig.135-6
172	Temple (6)	Gens Julia	Fig.143
173	Temple (6)	Tyche	BM
174	Temple (2,4,6)	Seated Hermes	BM
175	Temple (4)	Seated Apollo	BM
176	Temple (4)	Artemis, Huntress	Arcuated lintel Fig.144
177	Temple (4)	Capitoline triad	Fig.142
178	Temple (4)	Nero ?	SNG Cop.235
179	Temple (2,4)	Aphrodite	BM
180	Temple (4)	Poseidon	BM
181	Temple ¾ view	Poseidon	Fig.145
182	Arch	Single opening	Fig.152
183	Arch	Three openings	BM
184	Conical monument on which statue		Fig.153
185	Lighthouse		Fig.147
186	Harbour		Fig.146
187	Agora		Fig.148
188	Peirene fountain		Figs.139,139A
189	Fountain	Meta Sudans type	Fig.113
190	Round shrine, domed Melicertes	Among trees	Figs.150-1
191	Enclosure in which tree		Fig.479
192	Tomb of Lais		Fig.149
Sicyon			
193	Aedicula (2)	Artemis	NCP pl.H.xix.
194	Temple on podium	Flanked by herms, sometimes among trees	Fig.425
Aegium			
195	Temple ¾ view	With torches	BM

City and Buildings (Columns)	Cult or Image	Remarks	Reference
Bura			
196	Hill with temple $\frac{3}{4}$ view and shrine of Heracles		Fig.2
197	Arcade or portico (6)		Fig.478
Cynaetha			
198	Hill and city		Fig.1
Patras			
199	Temple (8)	Imperial Tondo in pediment	Fig.392
200	Temple (2)	Hermes	SNG Cop.205
201	Temple (2)	Athena	SNG Cop.200
202	Fountain		Fig.74
203	Harbour from the sea		Fig.60
204	Harbour from the land		Fig.61
Zacynthus			
205	Temple (2)	Imperial	Paris
206	Aedicula (2)	Female and infant	Paris
Colone			
207	Temple (2)		NCP pl.GG.xxii
Mothone			
208	Harbour		Fig.484
209	Temple (2)	Asclepius and Hygieia	Mabbott 959 (pl.956)
Gytheium			
210	Temple (4)	Asclepius Half fluted columns	Fig.4
Argos			
211	Round Shrine on podium		Fig.45
212	Temple $\frac{3}{4}$ view	Asclepius No architrave	NCP pl.GG.iii
213	Temple on acropolis	Athena	NCP pl.K.xliii
214	Temple (2)	Leto and Choe	Paris
215	Temple $\frac{3}{4}$ view	Possibly in antis	Fig.404
216	Temple (2)	Hera ?	Corinth Excavations

City and Buildings (Columns)	Cult or Image	Remarks	Reference
Epidaurus			
217 Temple (4)	Asclepius		Fig.355
218 Round temple (Tholos ?)	Elpis		Fig.47
Troezen			
219 Round peristyle building with portico	Corinthian		Fig.46
220 Fountain of Heracles			Fig.75
221 Temple (2)	Asclepius		NCP pl.GG.xiv
222 Acropolis			NCP pl.M.iii-iv
223 Temple (2)	Female deity		Paris
Phigaleia			
224 Aedicula (2) in which herm			NCP pl.V.xi
Islands			
Tenos			
225 Temple (2)	Poseidon and Dionysus		JNG 1949 pl.VIII.25
Thera			
226 Temple (4)	Apollo	Ionic capitals	Paris
Crete (Koinon): Gortyn?			
227 Temple (2)			Svoronos pl.XXXII.18
Cnossus			
228 Labyrinth			Fig.21
Cydonia			
229 Temple (6)			Svoronos pl.X.17
Pontus			
Koinon			
230 Temple (4) (at Amaseia ?)			Receuil 1
231 Temple ¾ view (at Neocaesarea ?)			Receuil 2a

City and Buildings (Columns)	Cult or Image	Remarks	Reference
Amaseia			
232	View of city		Figs. 159,162 (Colour p.101)
232A	Construction of city tower		Fig.159A
233	Temple (4)	Marked parotids	Fig.164
234	Temple (4)	Serapis ?	Receuil 41
235	Temple (2,4)	Tyche	Sometimes with arcuated lintel or without architrave
236	Temple ¾ view		Paris
237	Altar of Zeus Stratios		Fig.163
Amisus			
238	Mountain, altar, and temple (4)	Zeus	Sometimes doors instead of temple image
239	Temple (4)	Zeus ?	Receuil 113
240	Temple (4)	Demeter	Corinthian capitals
241	Temple (3)	Aphrodite	Spiral flutes
Comana			
242	Temple (2,4)	Ma/Enyo	Figs. 176,351
243	Portico (4)		Broken pediment
Neocaesarea			
244	Portico (5)		Fig.173
245	Sanctuary gate	Ma/Zeus	Often walling between columns
246	Temple ¾ view (4)		Peripteral
247	Temple ¾ view (4)		Prostyle
248	Temple (4)	Seated Zeus	Paris
249	Two temples		Fig.175
250	Two temples ¾ view		Fig.178
251	Gate (or nymphaeum) Tyche		Fig.179
Sebastopolis-Heracleopolis			
252	Stoa	Heracles	Two tetrastyle wings and barrier
253	Aedicula ¾ view	Heracles	Figs.8-9
254	Temple (4)		Fig.443
			Receuil pl.XIV 24

City and Buildings (Columns)	Cult or Image	Remarks	Reference
Zela			
255	Temple/portico (4,6)	Sometimes with altar, trellis, broken pediment or arcuated lintel	Figs.263,330,362-3,384 (Colour p.102)
256	High with walls and propylon		Fig.514
257	Temple (4)	Tyche	Corinthian, arcuated lintel
258	Hill with altar		Fig.304
Paphlagonia			
Gangra-Germanicopolis			
259	City buildings		Fig.517
260	Temple (4)		Receuil pl.XXII.1
Neoclaudiopolis			
261	Temple (4)		Receuil pl.XXIII.11
262	Temple (4)	Artemis Ephesia	Receuil 13
Sinope			
263	Aedicula (2)	Apollo	BM
264	Aedicula (2)	Nemesis	BM
265	Temple (2)	Nemesis	Receuil p..P.8
Bithynia			
266	Temple (4,6,8)	Rome and Augustus at Nicomedeia ?	Fig.396
267	Temple (2)	Capitoline triad	Receuil pl.XXXVI.7.
268	Arch supporting capricorn		Receuil pl.XXXV.4
269	Altar (Nicaea)	Zeus	Fig.188
Bithynium			
270	Temple (8)	Imperial	Sometimes without image
271	Temple ¾ view		Receuil pl.XLIII.10
Caesareia Germanica			
272	Temple (4)	Zeus	SNG Cop.345
273	City walls and gate		Fig.513
274	Harbour		Fig.57 (Colour p.50)

City and Buildings (Columns)	Cult or Image	Remarks	Reference
Calchedon			
275 Temple (4)	Apollo	Arcuated lintel	Receuil pl. XLVIII.11
Creteia Flaviopolis			
276 Temple (4)	Tyche		Receuil 12
277 Temple (4)	Zeus		Receuil pl. I.IV.6
278 Temple ¾ view	Zeus		SNG vonA 519
279 Temple (4)		Between two statues	Receuil pl. LIII.24
Heraclea Pontica			
280 Temple (6)	Rome		Fig.7
281 Temple (4)	Zeus	Corinthian, with parotids	BM
282 Lighthouse			Fig.63
283 Stadium with temple of Heracles			Fig.473
Juliopolis			
284 Temple (4)	Tyche		Receuil pl. LXIII.24
Nicaea (cf. Koinon)			
285 Temple (4,6)	Tyche		Fig.186
286 Temple ¾ view	Tyche		SNG vonA.595
287 Temple ¾ view			Fig.187
288 Temple (4)	Asclepius		Receuil pl. LXXI.4
289 Temple (4)	Dionysus		Receuil pl. LXXII.18
290 Temple (4, 6)			Receuil pl. LXXXIV.22
291 Two temples			Mabbott 1155
292 Building with pediment and statues		2 columns in antis	Fig.189
293 City walls			Fig.190
294 Colonnade (4,6)			Figs.180-1
295 Gate or portico		Sometimes on head of Tyche	Figs.182-3, 496 (Colour p. 14)
Nicomedia (cf. Koinon)			
296 Temple (6,8)	Neocorate	Corinthian	Fig.390

City and Buildings (Columns)	Cult or Image	Remarks	Reference
297 Two temples	Neocorate	Sometimes held by Tyche or above ship	Fig.446
298 Temple (6)	Demeter		Receuil pl.XCI.5
299 Temple (4)	Concordia		Receuil pl.XCI.28
300 Two temples and column on which Demeter			Receuil pl.XCV.10
301 Three temples		Sometimes above ship	Fig.457
302 Three temples (one above of Demeter)			Fig.456
303 Temple (4) and worshippers			SNG vonA.7120
Prusa			
304 Temple (6)	Zeus	Corinthian	Receuil pl.CI.35
305 Temple (6)		Ionie	BM
306 Temple (4) and two river gods		Arcuated lintel	Receuil pl.CII.10
307 Round temple with emperor and tree Peripteral			Fig.49 (Colour p.102)
Prusias ad Hypium			
308 Temple (4)	Zeus Capitolios		NC 1967, pl.III.1
309 Gate			Fig.505
Tium			
310 Temple (2)	Zeus		Receuil pl.CX.6
Asia (i.e. Mysia, Troas, Aeolis, Ionia, Caria, Lydia, Phrygia)			
Ionian League (cf. Sardes)			
311 Temple (6)	Imperial		SNG vonA.7814
Abydos, Troas			
312 Temple (8)	Artemis Ephesia	Sometimes without image	SNG vonA.7542
313 Temple ¾ view			SNG Cop.62
314 Tower of Hero			Fig.36
315 Tower		With trumpeters and ship	Fig.486
Acrasus, Lydia			
316 Temple (6)	Artemis Ephesia		Paris

City and Buildings (Columns)	Cult or Image	Remarks	Reference
Aezani, Phrygia			
317 Temple (8)			SNG von A.3355
318 Temple (4)	Zeus		SNG von A.3357
319 Temple (4)	Artemis		SNG von A.3354
Alabanda, Caria			
320 Temple or large altar (4) Apollo			NC 1971, pl.26.21
Alexandria, Troas			
321 Temple (2,6)	Apollo Smintheus		SNG von A.1462
322 Temple ¾ view		Prostyle	Fig.401
323 Bouleuterion			Fig.474
324 Top of arch		Three openings	KlM.pl.XXX.13
325 Top of arch		Single opening	KlM.pl.XIX.12
Alia, Phrygia			
326 Temple (4)			KlM.pl.XX.11
Amorium, Phrygia			
327 Temple (2,4)	Zeus	Sometimes arched lintel	BMC36
328 Temple (4)	Athena	Spiral flutes	BMC54
329 Temple (6)		Spiral flutes	SNG von A.3412
330 Gate in which altar (4)			SNG von A.3402
Ancyra, Phrygia			
331 Temple (4)	Tyche	Arched lintel	SNG von A.3444
Antioch, Caria			
332 Bridge			Fig.82 (Colour p.50)
333 Temple (4)	Tych	Arcuated lintel. spiral flutes	SNG Cop.37
334 Temple (4)	Athena		SNG Cop.39
335 Temple (4)	Zeus Capitolios	Ionic	SNG von A.2424
Apamea, Phrygia (cistophorus; cf. Ephesus and Laodicea)			
336 Round aedicula (4)		With barrier	BMC 31

City and Buildings (Columns)	Cult or Image	Remarks	Reference
Aphrodisias, Caria			
337 Temple (2,4,8)	Aphrodite	Often arched lintel	BM
338 Covered altar	Aphrodite		Prowe Sale (1914)1173
330 Aedicula (2)	Artemis Ephesia		SNG vonA.2435
340 Enclosure with tree			SNG vonA.2449
Apollonia ad Rhyndacum, Mysia			
341 Temple (4)	Apollo	Sometimes without cult image	Fig.350
Apollonia Salbace, Caria			
342 Temple (4)	Leto, Apollo, Artemis	Sometimes spiral flutes	Fig.27
Apollonis, Lydia			
343 Temple (4)	Dionysus		JNG 1949,pl.II.31
Apollonos Hieron, Lydia			
344 Temple (6)	Apollo	Broken entablature	BM
Attaea, Mysia			
345 Temple (4)	Zeus		v.Fritze,pl.VI.23
Attuda, Caria			
346 Temple (4)	Cybele	Centre columns spiral fluted, side columns half fluted	Fig.366
Bargasa, Caria			
347 Temple (4)	Asclepius	Spiral flutes, arcuated lintel	SNG von A.2513
Blaundus, Lydia			
348 Temple (4)	Apollo	Ionic, spiral flutes	Fig.365
Bruzus, Phrygia			
349 Temple (4)	Zeus	Incomplete architrave	SNG vonA.3527
Cadi, Phrygia			
350 Temple (4)	Zeus	Spiral flutes, arched lintel	SNG von A.8390

City and Building (Columns)	Cult or Image	Remarks	Reference
351 Temple (4)	Artemis Ephesia	Sometimes with spiral flutes, arched lintel or with architrave	SNG von A. 3691
Ceramus, Caria			
352 Temple (4)	Zeus		SNG von A. 2581
Ceretapa, Phrygia			
353 Temple (6)			Paris
Cibyra, Phrygia			
354 Temple (6)		Doric entablature, spiral flutes	Paris
355 Temple (4)			KIM. pl. VII. 13
356 Temple (2) in which basket		Spiral flutes	SNG von A. 3756
Cidramus, Caria			
357 Temple (2)		in which veiled deity with snake	SNG von A. 2589
Cilbiani, Lydia			
358 Temple (6)	Artemis Ephesia		SNG von A. 2995
359 Temple (4)	Apollo	With worshippers	Paris
Colophon, Ionia			
360 Temple (4)	Apollo Clarios	Altar and worshippers in front	Fig. 440
Cos			
361 Temple (2)	Asclepius and Hygieia		BM
362 Temple (4)	Heracles Farnese		Paris
Cyme, Aeolis			
363 Gymnasium or sanctuary with athlete			Fig. 20
364 Temple (2,4)	Artemis Ephesia	Sometimes with caryatids	Fig. 13
365 Temple (6)	Isis		Paris
Cyzicus, Mysia			
366 Round masonry building and Persephone			Figs. 200-2 (Colour p. 102)
367 Round aedicular	Demeter		Fig. 208
368 Temple and round building			Figs. 198-9

City and Building (Columns)	Cult or Image	Remarks	Reference
369 Temple (8)	Neocorate		SNG von A.1260
370 Temple (4) in which herm			Fig.210
371 Two temples	Neocorate	Sometimes held by emperor or Tyche	Fig.448
Daldis, Lydia			
372 Temple (4)	Apollo	Arch in pediment, sometimes in rural scene	Fig.435
Dardanus, Troas			
373 Temple (2) with sacrificial scene			Fig.405
Dioshieron, Lydia			
374 Temple (4)	Zeus	Sometimes arcuated lintel	SNGFW 4856
Docimeum, Phrygia			
375 Temple (6)		Sometimes standing figure in pediment	SNG Cop.352
376 Temple ¾ view		Corinthian	Fig.410
377 Two storey colonnade with equestrian statues			Fig.28
Dorylaeum, Phrygia			
378 Aqueduct			Fig.78
Ephesus, Ionia (See also Philadelphia)			
379 Temple (2,4,6,8)	Artemis Ephesia		Figs.221,224,229 (Colour p.120)
380 Temple ¾ view (4)	Neocorate	Corinthian	Fig.412
381 Temple (4)	Neocorate	With altar and worshippers	Fig.438
382 Two temples			BM
383 Three temples			BM
384 Four temples around		Sometimes on single podium	Fig.243
385 Beacoe shrine ?			Fig.53
386 Round aedicula		With barrier	BMC pl.XII.11 (See Apamea and Laodicea)
387 View of City above which Jupiter Pluvius			Fig.518
388 View of City above which galley and Artemis Ephesia			Fig.520

City and Building (Columns)	Cult or Image	Remarks	Reference
389	Portable shrine drawn by horses		Fig. 459
Ephesus—Magnesia			
390	Two temples	Artemis Ephesia and Artemis Leukophryene	BM
Eresus, Lesbos			
391	Temple (8,11)		Fig. 397
Erythrae, Ionia			
392	Temple (4)	Heracles	SNG Cop. 771
393	Temple (4)	Tyche	Paris
Eucarpeia, Phrygia			
394	Temple (4)	Tyche	BMC. 3
Eumeneia, Phrygia			
395	Temple (4,6)	Artemis Ephesia Sometimes with conical roof and spiral flutes	Figs. 32, 423 (Colour p. 120)
396	Temple (4)	Tyche Spiral flutes	BMC 61
397	Temple (6)	Emperor Spiral flutes	Paris
Germe, Mysia			
398	Temple (4)	Apollo Citharoedus Spiral flutes	SNG von A. 7228
Hadrianopolis, Phrygia			
399	Temple (4) in which oil basin		Fig. 342
400	Portico (4) with steps leading to altar		Fig. 15
Halicarnassus, Caria			
401	Temple (2,4)	Tyche	SNG von A. 2535
Harpasa, Caria			
402	Temple (6)	Athena Arcuated lintel	SNG von A. 2540
Heraclea ad Latmum, Ionia (cf. Heraclea Salbace)			
403	Temple (2)	Artemis In antis	Fig. 343

City and Building (Columns)	Cult or Image	Remarks	Reference
Heraclea Salbace, Caria			
404 Temple (2,4)	Artemis Ephesia		SNG Cop.405
Hierapolis, Phrygia			
405 Temple 4,6)	Apollo Citharoedus	Spiral flutes, arcuated lintel	Fig.371
406 Temple (6)		Ionic; standing figure in pediment	Paris
407 Three temples, one of emperor			KJM.p.241.32
408 Temple (6)	Emperor	Bust of 'Men' in pediment	Fig.389
409 Temple ¼ view	Emperor ?		Fig.403
Hierocaesarea, Lydia			
410 Temple (4)	Artemis		BM
Hypaepa, Lydia			
411 Temple (4,6)	Artemis Anaitis	Often spiral flutes; sometimes arched lintel	Fig.382
412 Temple (4)	Tyche		BM
413 Gate in which flaming altar			Lyd.Stadt m.pl.IV.10
Iasus, Caria			
414 Temple (8)		Corinthian	Munich
Ilium, Troas			
415 Temple (6)	Athena		Fig.195
Julia Ipsus, Phrygia			
416 Temple (2)	Men		SNG von A.3680
Lampsacus, Mysia			
417 Temple (6)	Priapus	Arcuated lintel	Fig.372
418 Temple (4)	Zeus	Arcuated lintel	Vienna
Laodicea, Phrygia			
419 Temple (2) in forum scene			Fig.23 (Colour p.31)
420 Temple (8) in front of which sacrifice	Windows in pediment		Fig.226
421 Temple (2,4,6,8)	Emperor		Cop.SNG 573

City and Building (Columns)	Cult or Image	Remarks	Reference
422 Temple (4,6,8)			SNG von A.3846
423 Temple (4)	Zeus and Domitian		BM
424 Three temples	Zeus, emperor, ? Asclepius		SNG von A.3858
425 Two temples on posia			SNG von A.2864
426 Aedicula (2)	Athena/Roma	Held by Tyche	SNG von A.8418
427 Round temple (6) with barrier			KIM 264.7 (cf. Apamea and Ephesus)
Lesbos (Koinon) Cf. Mytilene			
428 Temple (8)			SNG von A.7743
Maeonia, Lydia			
429 Temple (4)	Hestia		SNG von A.8235
Magnesia ad Maeandrum, Ionia (cf. Ephesus)			
430 Temple (4)	Artemis Leukophryene		Fig.225
431 Shrine (2)	Leto ?		BM
432 Shrine (2)	Dionysus		JNG 1949 pl.IX.19
433 Beacon-shrine ?			BM
Magnesia ad Sipylum, Lydia			
434 Temple (4)	Tyche	Sometimes spiral flutes or without architrave	SNG von A.3006
435 Temple (2,4)	Cybele		Cop. SNG 272
Metropolis, Ionia			
436 Temple (2,4)	Ares	Arcuated lintel	Fig.370
Metropolis, Phrygia			
437 Temple (4)	Cybele		Paris
438 Temple (4)	Zeus	Arcuated lintel	SNG von A.8424
Midaem, Phrygia			
439 Temple (4)			SNG von A.3890
Miletus, Ionia			
440 Aedicula (4)	Apollo of Didyma	Arcuated lintel, spiral flutes	Fig.239

City and Building (Columns)	Cult or Image	Remarks	Reference
441 Temple (6)			SNG Cop.1007
Mylasa, Cria			
442 Temple (2,4)	Zeus Labraundus		Fig.353
443 Temple (4)	Zeus Osogoas		Fig.332
Myrina, Acolis			
444 Temple (6)	Apollo of Grynium		Fig.386
Mytilene, Lesbos			
445 Temple (2,4)	Hera		SNG Cop.416
Nacrassa, Lydia			
446 Temple (4)	Artemis huntress		SNG von A.3035
Neapolis, Ionia			
447 Temple (4)	Apollo		BM
448 Temple (4)	Artemis Leukophryene		ZfN 1887,44
Nysa, Lydia			
449 Temple (4,6)	Men Kamareites	Sometimes with arched lintel	Fig.388
450 Temple (6)	Dionysus		Lyd.Stadtm.p.110.17
451 Colonnade (9) on which figures			Fig.476
Parium, Mysia			
452 Altar in sanctuary	Parus		Figs.214—5
453 Altar ¾ view			Fig.98
454 Gate			Figs.211,213
Peltae, Phrygia			
455 Temple (2,4)	Artemis Ephesia		BMC 23
Pergamum, Mysia			
456 Portico to altar court			Fig.217 (Colour p.119)
457 Temple (2,4,6)	Rome and Augustus		Fig.349
458 Temple (4)	Trajan and Zeus		Fig.3

City and Building (Columns)	Cult or Image	Remarks	Reference
459 Temple (6)			Weber 5207
460 Two temples and column			Fig.450
461 Temple and courtyard Aphrodite Paphia			Fig.268
462 Temple (6) Asclepius			Fig.327 (Colour p.32)
463 Temple (2) on high podium Telesphoros			Fig.337
464 Temple (4) Seated Caracalla			Fig.439
465 Three temples Augustus, Caracalla, Trajan			Fig.30
466 Three temples one above			Fig.454
Philadelphia, Lydia			
467 Temple (6) Artemis Anaitis			BM
468 Temple (2,4) Helios			SNG von A.3081
469 Temple (4) Dionysus			Paris
470 Temple (10) with emperor sacrificing			Prague
471 Temple (4) Artemis Ephesia Arched lintel			SNG von A.3077
472 Temple ¾ view with worshippers and Artemis Ephesia			Paris
473 Temple (2,4) Zeus			SNGFW4873
474 Temple (4) Aphrodite ? Arcuated lintel			Paris
475 Aedicula (2) Aphrodite Spiral flutes			Ly d.Stadtm.pl.V.14
Philadelphia-Ephesus			
476 Temple ¾ view on high stepped podium			Fig.408
Philomelium, Phrygia			
477 Temple (round?) with hexagonal court Dionysus			Fig.19
478 Temple (6) Snake Corinthian			Fig.387
Pionia, Mysia			
479 Temple (4) Standing Artemis ?			SNG von A.1566
Prymnessus, Phrygia			
480 Temple (4) Dikaioisyne ?			BMC 37

City and Building (Columns)	Cult or Image	Remarks	Reference
Saitta, Lydia			
481 Temple (4)	Aphrodite	Arcuated lintel, spiral flutes	MundM 18:vi:70,433
Samos			
482 Naiskos (4)	Hera	Arcuated lintel, sometimes with altar	Figs.324,236
483 Temple (3)	Hera	Ionic	Fig.235
Sardis, Lydia			
484 Temple (4,6)	Kore		Fig.241
485 Temple (4,6)			SNG von A.3137
486 Temple (6)	Emperor ?		Fig.380
487 Two temples $\frac{3}{4}$ view	Neocorate		Fig.328 (colour p.49)
488 Three temples	Neocorate		Fig.242
489 Four temples around	Neocorate		BM
490 Four temples in a row	Neocorate		MundM 6.vi.51,132
491 Temple and courtyard	Aphrodite Paphia		Fig.31
492 Altar	Zeus Lydios		Figs.244-5 (Colour p.49)
493 City walls		Lion in front	Fig.519
Sibidunda, Phrygia			
494 Temple (2) in which baetyl			Lewis coll., Cambridge
495 Temple (2) in which altar etc.			Hirsch Sale XIII,4157
Silandus, Lydia			
496 Temple (4)	Dionysus		Fig.354
497 Temple (4,6)			BM
Smyrna, Ionia			
498 Temple (8)		Parotids and statues	Fig.326 (Colour p.32)
499 Temple (4)	Tiberius		SNG Cop.1338
500 Two temples	Tiberius and Hadrian		SNG von A.2248
502 Three temples	Tiberius, Roma, Hadrian		Fig.455
502 Three temples, two in $\frac{3}{4}$ view, in central, Roma			SNG von A.2224
503 Temple (4)	Tyche		SNG von A.2190

City and Building (Columna)	Cult or Image	Remarks	Reference
504 Temple (4)	Nemesis		BMCRE III pl.74.7 (Cistophorus)
505 Temple (6)		Held by Roma or Amazon	SNG von A.8009
Synnada, Phrygia			
507 Temple (8)	Dionysus		SNG Cop.732
508 Temple (6,8)	Zeus		SNG von A.3995
509 Temple (2)	Amaltheia		SNG von A.3994
510 Aedicula (2), in which cippus		Domed roof	SNG von A.3992
511 Temple (2) in which cippus		Arched lintel	KIM pl.IX.19
Teos, Ionia			
511A Temple (4)	Augustus		Fig.356
Thyateira, Lydia			
512 Temple (4)	Apollo Tyrimnaeus		Lyd. Stadtm. pl.VI.15
513 Temple (4)	Athena/Roma	Arched lintel	Fig.368
Tiberiopolis, Phrygia			
514 Temple (4)	Artemis Ephesia		BMC 19
515 Temple (4)	Tyche		SNG von A.4031
Tralles, Lydia			
516 Temple (4)	Zeus	Arched lintel	Fig.377
517 Temple (8,10)		Eagle in pediment	Fig.391
518 Two temples	Emperor or Zeus		Fig.447
519 Shrine in cave			BM
Tripolis, Lydia			
520 Temple (4)	Leto		SNG von A.3327
Galatia			
Ancyra (including Koinon)			
521 Temple (8)			SNG von A.6142
522 Temple (4,6)		Sometimes on stepped podium	Fig.379
523 Temple ¾ view		Peripteral	SNG von A.6149

City and Building (Columns)	Cult or Image	Remarks	Reference
524 Temple ¾ view	Men	Prostyle or in antis with arched lintel	Fig.399
525 Two temples ¾ view in which thymiastria		No roof line	Fig.449
526 Temple held by goddess			Paris
527 Temple (4)	Athena		ANS
Germa			
528 Temple (2)	Imperial		Fig.336
Pessinus			
529 Temple (6)			, SNG von A.6208
Tavium			
530 Temple (6) on podium			SNG von A.6238
Caesarea, Cappadocia (Eusebeia)			
531 Two towers, sanctuary and Mt. Argaeus			Imh.Bl.Gr.u.Rom.pl.VIII.18
532 Temple (4) at foot of Mt Argaeus			SNG von A.6498
533 Temple (2,4)	Mt. Argaeus		Fig.54
534 Temple (4)		On podium	Sydenham p.29 fig.2
535 Temple (4)	Athena/Roma	Eagle in pediment	Paris
536 Temple (6)	Neocorate	Decorated architrave, eagle in pediment	Fig.378
537 Temple (2)	Artemis Pergaia	Sometimes with inner naiskos	Fig.346
538 Temple (4)	Tyche		Sydenham p.78.275
539 Pyramid ?			SNG von A.6340
Pisidia			
Adada			
540 Temple (6)	Trajan	Prominent column bases	NC 1964, pl.XII.16
541 Altar on platform			Arch.Anz.1931.pl.15.5
Andeda			
542 Temple (2)	Artemis Pergaia		SNG von A.4908

City and Building (Columna)	Cult or Image	Remarks	Reference
Antioch			
543 Temple (6)	Men	Barrier in front	Fig.265
544 Aedicula (round ?) (4)	Tyche/Fortuna		BM
Apollonia Mordiacum			
545 Temple (8)	Emperor		Fig.393
546 Temple (2)			Paris
Ariassus			
547 Temple (2)	Artemis Pergaia		Fig.331
Baris			
548 Temple (2)	Tyche	Scalloped design in pediment	SNG von A. 5013
Codrula			
549 Temple (2)	'Dios Kotanous'		NC 1969,31.11
Comama			
550 Temple (2)	Veiled female		Paris
551 Temple (2)	Two veiled females seated		Paris
Conana			
552 Temple (4)	Tyche	Arched lintel	SNG von A. 5074
Cremna			
553 Temple and inner shrine	Luna		Fig.345
554 Temple (2)	Cybele		SNG von A. 8602
Etenna			
555 Monument with caduceus			Fig.52
Isinda			
556 Aedicula (2)	Roma		BMC 22
Lysinia			
557 Temple (2)	Artemis Leukophryene ?		Vienna

City and Building (Columns)	Cult or Image	Remarks	Reference
Olbasa			
558 Temple (2,4)	Aphrodite		JNG 1971, pl.2,15
559 Temple in which altar or inner shrine			JNG 1971, pl.1.4
Pednelissus			
560 Temple (2)	Baetyl		BMC 3
Pogla			
561 Aedicula (2)	Artemis Pergala		SNG von A.5142
Prostanna			
562 Temple (2)	Men	Decorated lower columns	Paris
Sagalassus			
563 Temple (8) in which herm			Fig.394
564 Sanctuary (3) with altars	Dioscuri		Fig.256
565 Temple (2,4)	Tyche	Sometimes with arched lintel or with figure and mountain on architrave	Fig.360
Claudiosleuceia			
566 Temple (2)	Snake on base	Altar outside	Fig.428
Selge			
567 Sanctuary on platform with two trees and altars			Figs.252-3,261-2,(Colour p.154)
568 Temple in which round object			Fig.259
569 Temple (2)	Artemis Pergaia		SNGFW5199
Termessus			
570 Temple (2)			SNG von A.5344
571 Aedicula (2)	Emperor	Spiral flutes, Ionic	SNG von A.5357
Timbria			
572 Temples (2,4)	Tyche	BM	
Tityassus			
573 Temple (4)	Cybele	Grills between outer columns Ionic, often snake in pediment	SNG von A.5375

City and Building (Columns)	Cult or Image	Remarks	Reference
Isaura			
574	Gate in which Tyche seated		Fig.502
575	Temple (4)	Tyche	Paris
576	Temple in which bust on column (4)	Spiral flutes	SNG von A.5412
577	Temple (4)		Paris
Lycia			
Acalissus			
578	Temple (2)	Female deity	vA MinL.pl.1.3
Aperlae			
579	Altar in court		Fig.18,18A
580	Portico (4) in which altar		Fig.17
Gagae			
581	Temple (2)	Two images, one holding Nike	vA MinL pl.4.56
Myra (including Koinon)			
582	Temple (2,4)	Aretnis	Fig.333
583	Enclosure with column		vA Min L pl.10.169
Patara			
584	Temple (2)	Zeus	vA MinL pl.13.217
585	Aedicula (4)	Tyche	Fig.424
586	Two columns on which statues supporting arch	Canopy supported by figures	vA MinL pl.13.233
Patara-Myra			
587	Temple (2)	Zeus and Artemis	vA MinL pl.14.258
Pamphylia			
Aspendus			
588	Temple (4)	Serapis ?	Fig.381
589	Temple (4)	Two images	BMC pl.XXII.1
590	Two aediculae		BMC 79
591	Temple (4)	Cybele	ANS

City and Building (Columna)	Cult or Image	Remarks	Reference
Attalea			
592 Temple (2,4,6)	Athena		SNG von A.4618
593 Temple (2)	Artemis Pergaia		SNG von A.4627
Perga			
594 Temple (2,4)	Artemis Pergaia	Sometimes with inner columns	Fig.334, 344
595 Temple (2)	Tyche		SNG von A.4750
596 Temple (2) in which eagle, with standards			Fig.338
Side			
597 Temple (4,6)	Apollo	Sometimes held by Tyche	BM
598 Temple ¾ view	Apollo	Arched lintel	Fig.407
599 Temple (2,4)	Athena/Roma	Sometiems held by Tyche	BMC 87
600 Temple (2)	Eagle and standards		SNG Cop.432
601 Temple (2)	Three images	Inner shrine	Naville Sale XVII.1542
602 Gate in which victory crowning standards			Fig.503
603 Aedicula (round ?)	Tyche	Arched lintel, conical roof	Fig.470
604 Harbour			Fig.481
605 Three temples			Fig.453
Cilicia			
Adana			
606 Aedicula (2)	Seated Tyche		BM
Aegeae			
607 Temple (4,6,8)	Asclepius	Corinthian, sometimes arched lintel	Fig.395
608 Temple (4)		Eagle in pediment	Ann.Soc.Num. VIII.1884,149- 51
609 Temple (2)	Seated Tyche		ANS
610 Temple ¾ view		Arched lintel	Fig.406
611 Aedicula (2)	Eagle		BM
612 Walls and gate of Thebe with Cadmus			Fig.35
613 Lighthouse			Fig.66,485
Anazarbus			
614 Temple (7,8,10)			SNG von A.5499

City and Building (Columns)	Cult or Image	Remarks	Reference
615 Shrine drawn by elephants			Fig.461
616 Temple (6)	Emperor		SNG von A.5495
617 Temple ¼ view			Paris
618 Tripartite shrine		Sometimes central part only	Figs.429-32
619 Two temples			SNG FW 5227
620 Temple (2)		Spiral flutes	Paris
621 Acropolis and buildings		Head of Zeus in front	Fig.516
622 Aqueduct			Fig.81 (Colour p.50)
623 Temple (2,4)	Seated Tyche	Arched lintel	Fig.339
Anemurium			
624 Temple (2,4)	Tyche	Sometimes spiral flutes or arched lintel	SNG von A.5529
Antioch			
625 Temple (4)	Tyche	Arched lintel	SNG Cop.67
Carallia			
626 Temple (2)	Tyche		SNG von A.5608
Colybrassus			
627 Temple (4)	Zeus		BMC14
628 Temple (4)	Oil Basin	'Gymnasiarchia'	Fig.357
629 Temple (4)	Roma		SNG von A.5664
Coropissus			
630 Temple (2,4)	Seated Tyche		SNG von A.5675
Diocaesarea			
631 Temple (6)	Zeus	Altar sometimes to left	Fig.385
632 Gate			Fig.507
Germanicopolis			
633 Temple	Seated Tyche		Paris

City and Building (Columns)	Cult or Image	Remarks	Reference
Hierapolis Castabala			
634 Temple (4)			Robert pl.XXIX.105
635 Aedicula (2)	Tyche		Robert pl.XIX.108
Lamus			
636 Temple (4)			Paris
Lyrbe			
637 Enclosure, baetyl, and tree			SNG von A.5697
Mallus			
638 Temple (4)	Nemesis		BM
Mopsus			
639 Bridge			Fig.83
Ninica			
640 Temple (4)	Emperor		BMC 9
641 Temple ¾ view			Paris
Olba			
642 Tower			Fig.487
Philadelphia			
643 Temple (2)	Eagle		SNG von A.5800
Seleuceia ad Calycadnum			
644 Temple (4)	Artemis Pergaia		Paris
645 Aedicula (2)	Seated Tyche		KlM pl.XX.24
646 Altar and two standards			Imh.Bl.,Gr.uRom.pl.VIII.8
Selinus			
647 Temple (4)	Trajan		BMC 1
Soli-Pompeopolis			
648 Harbour			Fig.483

City and Building (Column)	Cult or Image	Remarks	Reference
Tarsus			
649	City walls		Fig. 94
650	Shrine of Ana		Fig. 96
651	Temple (10)	Neocorate	SNG von A. 5981
652	Two temples	Neocorate	Sometimes held by Tyche SNG von A. 5996
653	Two temples ¾ view	Neocorate	Tyche seated between NC 1925.315,18
654	Temple (4)		Tyche seated to right; no lintel Paris
655	Temple (4)	Seated Tyche	No architrave SNG von A. 6055
656	Temple (6)	Heracles and Asclepius?	Hunter
657	Temple (4)	Aphrodite	Mabbott Sale 2236
658	Temple (4)	Vase	Grills between outer columns BMC 139
659	Temple (4)	Perseus	Paris
660	Temple (4)	Apollo Pythios	BM
661	Temple ¾ view	Apollo Lykios	BM
662	Temple ¾ view and emperor		Paris
663	Monument of Sandan		Fig. 97
664	Aedicula (2)	Sandan	BM
665	Aedicula (2)	Julia Domna	Paris
666	Gate		Fig. 511
Titiopolis			
667	Aedicula (2)	Tyche	BMC 1
Elaeusa-Sebaste			
668	Aedicula (2)	Figure on globe	KIM pLXVII.4
Cyprus			
Koinon			
669	Temple (4)	Tyche	Stairs in front; arcuated lintel Fig. 369
(Paphos)			
670	Temple and colonnades	Aphrodite	Courtyard in front Fig. 266 (Colour p. 154)

City and Buildings (Columns)	Cult or Image	Remarks	Reference
Commagene			
Samosata			
671 Temple	Seated Tyche		Vienna
Zeugma			
672 Temple on hill	Zeus Katabaites		Fig.22
Syria			
Cyrrhestica – Cyrrhus			
673 Temple (6)	Zeus		SNG Cop.49
Hierapolis Bambyce			
674 Temple (2)	Hadad ?		Fig.95
675 Temple (2)	Standard	Figures of Hadad and Atargatis	Fig.293
Chalcidice – Chalcis			
676 Aedicula $\frac{3}{4}$ view	Helios		Fig.444
Pieria – Antioch			
677 Portable shrine (4)	Seated Tyche		Fig.42
Balanea (Leucas)			
678 Aedicula (4)	Astarte/Tyche	Domed	ANS
Emisa			
679 Temple (6)	Elagabal		Figs.296–8
680 Temple $\frac{3}{4}$ view	Elagabal		Fig.299
681 Altar			Fig.301
Gabala			
682 Aedicula (2)	Roma		BMC 10
683 Aedicula (2)	Astarte/Tyche		ANS
684 Aedicula (2)	Julia Domna		Paris
Laodicea ad Mare			
685 Lighthouse			Fig.65

City and Building (Column)	Cult or Image	Remarks	Reference
686 Aedicula (2)	Eagle		BMC 95
687 Aedicula (2,4)	Astarte/Tyche	Spiral flutes	SNG Cop.358
688 Aedicula (2)	Julia Domna		Fig.469
Nicopolis			
689 Aedicula (2)	Nemesis ?	Spiral flutes	BMC 2
Paltus			
690 Portable shrine			Fig.462
691 Temple (2)	Athena		Paris
692 Temple (4)	Astarte/Tyche		BM
Seleucia			
693 Temple (2)	Astarte/Tyche		Paris
694 Temple (4)	Zeus Kasios		BM
695 Aedicula ¾ view	Zeus Kasios		Fig.445
Coele Syria – Damascus			
696 Three temples in lower of which Tyche			Fig.452
697 Temple (4) and river grotto	Marsyas (sometimes Hadad ?)		Fig.433
698 Temple ¾ view and river			Fig.413
699 Temple (4)	Astarte/Tyche	Arched lintel, sometimes with shell in pediment	Fig.43
700 Aedicula (2,4)	Astarte/Tyche	Sometimes with ram on plinth with carry bars	Fig.467
Heliopolis			
701 Temple (10)	Hadad/Zeus		Fig.280
702 Temple ¾ view	Hadad/Zeus		Figs. 279,290 (Colour p.171)
703 Temple and sanctuary ¾ view	Simios/Hermes		Fig.282 (Colour p.171)
704 Two temples			Fig.281
705 Portico with towers			Fig.284
706 Temple (4)	Astarte/Venus		Rhein. Mus.f. Philol. 1914 p.144 fig.6

City and Building (Columns)	Cult or Image	Remarks	Reference
Phoenicia – Aradus			
707 Aedicula (2)	Astarte/Tyche		Fig.340
Berytus			
708 Temple (4,6)	Poseldon		SNG Cop.113
709 Temple (4)	Astarte/Tyche		Fig.275
710 Gate in which Marsyas			Fig.276
711 Lighthouse			Fig.64
Botrys			
712 Temple (6,8)	Astarte/Tyche		SNG Cop.131
Byblos			
713 Sanctuary with baetyl			Fig.271 (Colour p.153)
714 Temple (6)	Astarte/Tyche	Sometimes with flat roof actuated lintel	Fig.375
715 Aedicula (round ?) (2,4)	Astarte/Tyche	Sometimes conical roof	SNG Cop.147
Caesarea ad Libanum			
716 Temple (4)	Astarte/Tyche		BMC 8
717 Aedicula (2)	Astarte/Tyche	Caryatids	Fig.14
Dora			
718 Temple (4)	Astarte/Tyche		BM
Orthosia			
719 Temple (4)	Astarte/Tyche	Sometimes arched lintel	Fig.376
Ptolemais			
720 Acropolis and buildings			Fig.515
721 Temple (4,6,8)	Astarte/Tyche		SN Cop.184
722 Temple (4)	Serapis, Isis, Astarte/Tyche		
723 Portable Shrine (2)	Hadad/Zeus		Fig.463
724 Portable shrine ¾ view	Hadad/Zeus		de Saulcy pl. VIII.10
725 Aedicula (2)	Aphrodite		BM
726 Two tower/altars and tree			CNP IV pl.XVL226
727 Sanctuary with portico and temple (nymphaeum)			Fig.73
728 Harbour			Fig.480

City and Building (Columns)	Cult or Image	Remarks	Reference
Sidon			
729	City walls and slipway		Fig.93
729A	Stepped pyramid ?		ANS MN 1976.13.
730	Temple and sanctuary Astarte		Fig.277 (Colour p.13)
731	Temple (4,6) Astarte/Tyche		Fig.361
732	Temple, altar, and columns		Fig.359
733	Temple (4) Dionysus (probably Astarte)		JNG 1949,96,648
Tripolis			
734	Tripartite temple Astarte/Tyche	Central aedicula and 4 columns on each wing	Fig.420
735	Tripartite temple and facade (4) Astarte/Tyche		Ashmolean
736	Aedicula (2) Astarte/Tyche		SNG Cop.286
737	Flat roofed shrine Astarte/Tyche		BMC 139
738	Gate to Sanctuary (4) Zeus Hagios		SNG Cop.288
739	Temple and gate Zeus Hagios		Fig.238 (Colour p.32)
740	Temple (4) Emperor	With parotids	Paris
Tyre			
741	Temple (8)		BMC 361
742	Temple ¾ view Melkart		Fig.415
743	Temple (4,6) Astarte/Tyche	Sometimes with altar and palm tree in front	Fig.237,373
744	Temple (2) and worshippers Astarte/Tyche and Marsyas		ANS
745	Aedicula (4) With smaller aedicula and statues on pedestals within, caryatids support canopy		Fig.329 (Colour p.102)
746	Portable shrine (2) ¾ view in which celestial images		Figs.40.464--5
747	Portable aedicula (2) Astarte/Tyche		Fig.468
748	Walls and gate of Carthage, and Dido		Fig.34
749	Walls and gate of Thebes, and Cadmus		Babelon, Perses 2341
750	Fountain house Oceanus		ANS
Trachonitis - Caesarea Panias			
751	Sanctuary of Pan		Figs.10--12
752	Temple (4) Astarte/Tyche		BM

City and Building (Column)	Cult or Image	Remarks	Reference
753 Temple (6)	Athena		de Saulcy pl.XVIII.4
754 Temple (4)	Zeus		ANS
755 (Herod Philip II) Temple (4)	Sun Disc	Unusual inset podium	Fig.358
756 (Herod Agrippa I) Temple (2)	Female deities		Meshorer pl.XII.89
757 Temple (6) on podium	Claudius ?		de Saulcy pl.XVIII.3
758 Temple (2) on podium	Agrippina ?		de Saulcy pl.XVIII.3
Decapolis – Abila			
759 Gate and towers in which altar			Fig.258
760 Temple (2,4)	Astarte/Tyche		de Saulcy pl.XVI.5
Antiochia ad Hippum			
761 Temple (4)	Zeus Arotios		BM
Capetolias			
762 Temple (8,10)	Zeus		BM
763 Gate and towers in which temple of Zeus			Fig.285 (Colour p.13)
764 Temple (4,6)	Astarte/Tyche		de Saulcy pl.XVI.9
Dium			
765 Gate (6) in which altar		Arched lintel	Fig.374
Gadara			
766 Temple (2,4)	Zeus	Corinthian	de Saulcy pl.XV.4
767 Aedicula (2)	Astarte/Tyche		Paris
Pella			
768 Town and temple on mountain			Fig.56 (Colour p.172)
769 Temple (4)	Asclepius ?		de Saulcy pl. XVI.8
770 Nymphaeum			Fig.72

City and Building (Columns)	Cult or Image	Remarks	Reference
Galilee — Gaba			
771 Temple (4)	Astarte/Tyche	Domed roof	BM
Diocaesarea (Sepphoris)			
772 Temple (4)	Zeus		BMC 26
773 Temple, tripartite	Zeus		de Saulcy pl. XVII.5
774 Temple (4)	Astarte/Tyche		de Saulcy pl. XVII.6
775 Two temples			Vienna
Tiberias			
776 Temple (4)	Zeus/Hadrian ?		de Saulcy pl. XVII.12
Samaria — Antipatris			
777 Temple (4)	Astarte/Tyche		ANS
Caesarea Maritima			
778 Temple (4)	Astarte/Tyche	Sometimes colonnade and altar in front	Fig. 367
779 Temple (6) in which altar			CNP. II pl. VIII.93
780 Altar		(Sometimes like Cyzicus no. 366)	CNP. II pl. VIII.229–230
Diospolis			
781 Aedicula (4)	Astarte/Tyche		BM
Neapolis			
782 Temple and buildings on Mt. Gerizim			Figs. 302–3 (Colour p. 172)
783 Two temples and Mt. Gerizim			BMC 159
784 Temple (2,4)	Astarte/Tyche	Arched lintel	Fig. 422
Nysa-Skythopolis			
785 Temple (4)	Astarte/Tyche	Corinthian	ANS
Sebaste			
786 Temple (4)	Capitoline triad		BMC 12
787 Temple (4)	Astarte/Tyche		ANS

City and Building (Columns)	Cult or Image	Remarks	Reference
Judaea –Jerusalem (Aelia Capitolina)			
788 Temple (4,6)	Astarte/Tyche		Fig.311
789 Temple (4,2)	Capitoline triad (sometimes Zeus alone)		Fig.312
790 Temple (4)	Jehovah	Flat roof	Fig.306
Agrippias (Anthedon)			
791 Temple (4)	Astarte/Tyche	Domed roof	Paris
Ascalon			
792 Temple (2)		Flat roof, inner shrine	Fig.465
Eleutheropolis			
793 Temple (4)	Astarte/Tyche	Arched lintel	BM
Gaza			
794 Gate in which owl (AR)			BM
794A City walls (copied from Sidon)			BM
795 Temple (2) or gate	Marnas and Io		BM
796 Temple (4,6)	Astarte/Tyche		BM
Nikopolis			
797 Temple (4)	Astarte/Tyche		ANS
Arabia			
Adraa			
798 Aedicula (2,4)	Astarte/Tyche		ANS
799 Altar of Dusares			Fig.442
Bostra			
800 Temple (2,4)	Astarte/Tyche		BM
801 Temple (2)	Athena/Roma		BM
802 Temple (2)	Dusares/Dionysus		BM
803 Altar of piled stones (Dusares)			BM
804 Altar of Dusares on terrace ¾ view			Fig.257

City and Building (Columns)	Cult or Image	Remarks	Reference	
Charachmoba				
805	Altar on terrace		BMC 3	
Esbous				
806	Temple (4)	Astarte/Tyche	BM	
Petra				
807	Temple (2,4)	Tyche	Berytus 1947, pl. XIV.1-4	
Philadelphia				
808	Processional shrine drawn by horses		BM	
Mesopotamia				
Carrhae				
809	Temple (4) in which baetyl and standards in inner shrine		Fig.418	
810	Altar with steps		ANS	
Edessa				
811	Temple (2) or altar with pediment		Paris	
812	Temple ¾ view in which baetyl		BM	
813	Temple (2) in which shrine		Fig.347	
814	Podium on which two figures		Paris	
Nesibis				
815	Temple (4)	Tyche	Head of Helios in pediment, and windowed pilasters	Fig.417
816	Aedicula (2)	Tyche	Spiral flutes	BM
817	Temple ¾ view			Paris
Rhesaena				
818	Temple ¾ view	Eagle	Sometimes without roof	SNG Cop.245-6
Rabathmoda				
819	Temple (4) as statue base of Hadad/Ares			Fig.419
Parthia				
820	City walls			BM

City and Buildings (Columns)	Cult or Image	Remarks	Reference
821 Aedicula (2)	Zeus seated		BM
822 Aedicula (2)	Zeus standing		BM
Persis			
823 Altar shrine			Figs. 50-51
India			
Bactra ?			
824 Enclosure with tree			BM
825 Stupa ¾ view with colonnade			Fig. 99
826 Shrine (2)	Female deity		BM
827 Shrine with three figures			BM
Taxila			
828 Enclosure with tree			BM
Egypt			
Alexandria			
829 Pharos			Fig. 313
830 Temple (2,4)	Serapis (Sometimes with Isis and other figures)		Dattari pl. XXX. 1154
831 Temple with 3 doors	Serapis		Fig. 318
832 Temple (2)	Serapis	One or two inner shrines or stelai	Fig. 348
833 Temple (2)	Harpocrates		Fig. 492
834 Temple (2)	Canopi		Fig. 493
835 Temple (2,4)	Zeus/Serapis		Dattari pl. XXX. 1157
836 Temple (2)	Tyche reclining		Dattari pl. XXX. 3062
837 Altar gate	Tyche (sometimes with snake)		Fig. 16
838 Single arch			Fig. 33
839 Triple arch		With pediment and sometimes with windows	Fig. 89
840 Temple (2)	Sacred boat		Dattari pl. XXX. 1158
841 Shrine carried by sacred boat, in which xoanon			Dattari pl. XXVII. 3557
842 Temple (2)	Nemesis (griffin)	Barrel vault ?	Fig. 494

City and Building (Columns)	Cult or Image	Remarks	Reference
843 Temple (2)	Tyche		Dattari pl.XXX.3061
844 Temple (2,4)	Nile		Dattari pl.XXIX.3801
845 Temple (2)	Hermanubis		Dattari pl.XXXIX.1138
846 Temple (2)	'Demeter'		Dattari pl.XXIX.1133
847 Kiosk	Heracles		Dattari pl.XXIX.1136
848 Temple (2)	Elpis		Dattari pl.XXIX.3030
349 Temple (2,4)	Athena/Roma		Dattari pl.XXIX.1131
850 Fountain with statues on high podium			Fig.488
851 Fountain with Heracles			Fig.77
852 Pylon	Isis		Fig.509
853 Pylon	Canopus		Dattari pl.XXX.1167
854 Portable shrine	Canopi		Dattari pl.XXIX.1132
855 Round temple	Mars Ultor (copied from Cistophorus)		Dattari pl.XXIX.14
856 Nilometer		Domed top	Figs.321-2
857 Gate ?		Possibly a couch	JEA 1961.119-133
Aphroditepolite Nome			
858 Temple (2)	Isis (between cats or birds on pedestals)	Barrel vault ?	Fig.489,491
Heracleopolite Nome			
859 Temple (2)	Heracles	Flat roof decorated with Uraei	Fig.510
Hermopolite Nome			
860 Aedicula (2)	Thoth		Dattari pl.XXIV.6269
Menelaite Nome			
861 Columned altar ? with uraei	Harpocrates		Dattari pl.XXXIV.6309
Cyrene			
862 Tomb of Batus		Pyramid surmounted by column	BM.

INDEX

The index incorporates references both to the text and to the illustrations. It does not list details of all buildings given in the catalogue (pp.241-287); but page references are given to cities to be found in the bibliography (Bibl.) and Catalogue (Cat.).

- Abdera, Spain; Fig. 335, (Cat. p.243)
 Abūla, Decapolis, Syria 34, 164; Fig. 288. (Cat. p.282)
 Abydos, Troas; Fig. 36, 486. (Cat. p.258)
 Acalissus, Lycia; (Cat. p.273)
 Achaea, Greece 17
 Achilles 107; Fig. 194.
 Acrasus, Lydia; (Cat. p.258)
 Acrocorinth 39, 79, 80; Fig. 135-7 See Corinth.
 Acropolis 39, 57, 75-8, 175, 181; Fig. 56, 129, 133-4, 302-3, 514-6. See Acrocorinth.
 Adada, Pisidia; (Cat. p.270).
 Adana, Cilicia; (Cat. p.274).
 Adonis 151.
 Adraa, Arabia; Fig. 442. (Cat. p.284).
 Adyton see Cella.
 Aedcula 21, 145, 164; Fig. 208, 234, 236, 239, 443-5, 452, 490.
 - with Caryatids; Fig. 13-4, 329, 424.
 Aegeae, Cilicia 40, 181; Fig. 35, 66, 395, 406, 485. (Cat. p.274).
 Aegina, Greece 40; Fig. 59, 411. (Cat. p.251).
 Aegium, Peloponnese (Cat. p.252)
 Aegosthena, Greece; (Cat. p.251)
 Aelia Capitolina; Judaea 179; Fig. 311, 312. (Bibl. p.237-8; Cat. p.284)
 Aelian Bridge, Rome; Fig. 84.
 Aemilia, Basilica, Rome; Fig. 477.
 Aezani, Phrygia; (Cat. p.259)
 Africa 33, 38, 73-4, 123, 188.
 Afghanistan 181.
 Agathe Tyche 99, 104; Fig. 186.
 Agora, 24, 77, 82, 85; Fig. 148. See Forum.
 Agrippias, Judaea; (Cat. p.284)
 Ake-Ptolemais, Phoenicia 44; Fig. 73, 463, 480, 515. (Cat. p.280)
 Akkadian Seal, see Seal.
 Alabanda, Caria; (Cat. p.259)
 Alexander of Abonoteichos 118.
 Alexander the Great 118, 173, 183.
 Alexander Severus, Fig. 44, 68, 71, 78, 159, 159A, 178-9, 252-3, 293, 339, 347, 368, 387, 451, 456.
 Alexandria, Egypt 21, 28, 33, 40, 44, 47, 180-188, 226; Fig. 16, 33, 77, 89, 313-319, 321, 322, 348, 488, 489, 491-4, 509, 510. (Bibl. p.238; Cat. p.286-7).
 Alexandria, Troas 108; Fig. 401, 474. (Cat. p.259)
 Alia, Phrygia (Cat. p.259)
 Altar 21-2, 24, 27, 33-4, 38-9, 73, 85, 95, 102, 107, 117-8, 122-5, 127, 131, 133-5, 137, 139-45, 151, 169, 173-5; Fig. 15, 17-8, 38, 49, 98, 168, 179, 215, 217-9, 236-7, 244-5, 252-3, 256-8, 261-1, 264, 288, 297-8, 304, 330, 359, 367, 385, 394, 413, 428, 434, 437-443, 445, 449.
 - Apollo Aktaios see Tomb of Parius.
 - Aphrodite, Byblos 150-2; Fig. 271.
 - Ara Pacis, Rome; Fig. 105.
 - Chians 89; Fig. 157-8.
 - Cybele 140-1.
 - Dusaes 145; Fig. 257, 442.
 - Elagabal 167-70; Fig. 296-301.
 - Heracles; Fig. 443.
 - Hermocreon 53, 118.
 - Horned, see Semitic.
 - Jupiter Heliopolitanus 166; Fig. 286.
 - Monumental; Fig. 441.
 - Zeus 99, 122-25; Fig. 217-8, 426.
 - Zeus Hypsistos 172-5; Fig. 302-3.
 - Zeus Litaos 99; Fig. 188.
 - Zeus Lydios 139-41; Fig. 244-5.
 - Zeus Stratos 90-3; Fig. 159, 163.
 - With caduceus; Fig. 52.
 - With snake; Fig. 428.
 Altar Court 21, 22, 24, 34, 38, 104, 117-8, 122-5, 131, 143-6, 150-2, 164; Fig. 18, 18A, 189, 214-5, 271, 273, 287, 362-3, 374, 449.
 See also Court.
 Amaseia, Pontus 21, 90-3; Fig. 6, 159-164. (Bibl. p.233; Cat. p.255)
 Amazon 127, 139.
 Amisus, Pontus; Fig. 352, 426. (Cat. p.255)
 Ammienus Marcellinus 183.
 Amorium, Phrygia (Cat. p.259)
 Ampelius, see Lucius.
 Amphitheatre 61-2, 82; Fig. 110-1.
 Anatolia, see Asia Minor.
 Anazarbus, Cilicia 47; Fig. 81, 339, 429-31, 461, 516. (Cat. p.274-5)
 Anchialus, Thrace; Fig. 87 (Cat. p.246-7)
 Ancyra, Galatia; Fig. 379, 399, 449 (Cat. p.269-70)
 Ancyra, Phrygia; (Cat. p.259)
 Andeda, Pisidia; (Cat. p.270)
 Anemurium, Cilicia; (Cat. p.275)
 Antigonos, see Mattathiah.
 Antioch (ad Maeandrum), Caria 47; Fig. 82 (Cat. p.259)
 Antioch, Cilicia; (Cat. p.275)
 Antioch (ad Hippum), Decapolis; (Cat. p.282)
 Antioch, Pisidia 145; Fig. 265. (Cat. p.271)
 Antioch (ad Orontem), Syria 34, 117; Fig. 42 (Cat. p.278)
 Antipatris, Samaria; (Cat. p.283)
 Antoninus Pius; Fig. 47, 77, 146, 229, 264, 302, 303, 313, 321, 337, 341, 348, 350, 355, 397, 427, 466, 471, 483, 497, 518.
 - Temple of; Fig. 264.
 Antony, Mark 73-4.

- Anu 53, 177; Fig. 96.
 Apamea, Phrygia (Cat. p.259)
 Aperiace, Lycia 24, 34; Fig. 17-18A. (Cat. p.273)
 Aphrodite 79; Fig. 135.
 - Byblos 150-53; Fig. 271.
 - Corinth 79-80.
 - Paphos 33, 137, 139, 145-9; Fig. 31, 266, 268.
 See also Venus.
 Aphroditopolite Nome, Egypt; Fig. 489, 491. (Cat. p.287)
 Aphrodisias, Caria; (Cat. p.260)
 Apollo 77-8; Fig. 350, 365, 398, 400, 416, 435, 453, 490.
 - Aktaios 118; Fig. 216.
 - Citharoedus Fig. 371.
 - Clarios; Fig. 440.
 - Didymaios 135; Fig. 239.
 - Grynium; Fig. 386.
 - Helios 118.
 - Leto and Artemis; Fig. 27.
 - Pythios 87-9; Fig. 154-6, 158.
 - Smintheus; Fig. 401.
 Apollonia (ad Rhyndacum), Mysia; Fig. 350. (Cat. p.260)
 Apollonia, Illyria; Fig. 398, 436. (Cat. p.250)
 Apollonia Mordiaeum, Pisidia; Fig. 393. (Cat. p.271)
 Apollonia Pontica, Thrace; Fig. 441. (Cat. p.247)
 Apollonia Salbace, Caria 24; Fig. 27. (Cat. p.260)
 Apollonis, Lydia; (Cat. p.260)
 Apollonis Hieron, Lydia; (Cat. p.260)
 Aqua Traiana, Rome 47; Fig. 79.
 Aqueduct 11-2, 47; Fig. 78-81.
 Aradus, Phoenicia; Fig. 340. (Cat. p.280)
 Ara Pacis, Rome 58, 99; Fig. 105.
 Arcade 24, 74, 99, 152; Fig. 180, 476, 478, 480-4.
 See also Colonnade, Portico, Stoa.
 Arcadia, Greece 17.
 Arch, Triumphal 33, 47, 85, 117-8, 179; Fig. 33, 82, 85, 89, 107, 211-3, 307, 506-7. (Bibl. p.231)
 Arched lintel 19; Fig. 22, 49, 71, 234, 236-7, 241-2, 284-5, 288, 361, 365-377.
 Ares 147; Fig. 370, 419.
 Argaeus, Mount, Cappadocia 39; Fig. 54.
 Argive Heraeum 130; Fig. 227.
 Argos, Peloponnese 36; Fig. 45, 196, 404. (Cat. p.253)
 Ariassus, Pisidia; Fig. 331. (Cat. p.271)
 Ark of the Covenant 177, 179.
 Arsinoe 113, 115.
 Arsinoeion 36, 113, 115; Fig. 205.
 Artemis; Fig. 27, 333.
 - Anaitis Fig. 382.
 - Ephesia 19, 33, 126-32, 137, 147, 165-6, 169-70, 177, 185; Fig. 13, 32, 221-4, 243, 423, 520.
 - Huntress 82; Fig. 144, 427.
 - Kore 137, 141; Fig. 240-2.
 - Leukophryene 166; Fig. 225.
 - Pergaia; Fig. 14, 331, 334, 344, 346.
 - and Apollo Aktaios 118.
 Artemisium, see Artemis Ephesia.
 Ascalon, Judaea 166; Fig. 466. (Cat. p.284)
 Asclepius 32, 36, 85; Fig. 4, 327, 355, 387, 395, 434.
 Asherat 156.
 Ashtoreth 129.
 Asia Minor 11, 19, 33, 66, 113, 123, 137, 139.
 Asklepiades 111, 113, 115.
 Asklepiodoros 115.
 Aspendus, Pamphylia; Fig. 381 (Cat. p.273)
 Astarte 155-7; Fig. 237, 275, 293, 311, 361, 367, 373, 375-6, 420, 422, 460.
 - Europa 24, 156-7; Fig. 277.
 See also Asherat, Atargatis.
 Atargatis-Venus 159-61; Fig. 281. See also Asherat, Astarte.
 Athena 76-7, 123; Fig. 45.
 - Ilias 106-8; Fig. 195-7.
 - Parthenos 75-7.
 - Polias 77, 99; Fig. 184.
 - Promachos 76-7; Fig. 132.
 See Also Roma.
 Athenagoras 118.
 Athens 39, 75-8, 107; Fig. 129-134. (Bibl. p.232; Cat. p.251)
 Atlas Caryatid 30.
 Attaea, Mysia; (Cat. p.260)
 Attalea, Pamphylia; (Cat. p.274)
 Attalos of Cyzicus 113-5.
 Attuda, Caria; Fig. 366. (Cat. p.260)
 Augean Stables 44.
 Augusta Traiana, Thrace; Fig. 86, 490. (Cat. p.247)
 Augustus 57, 73-4; Fig. 30, 37, 62, 125, 128, 349, 356, 391. See also Roma.
 Aurelian; Fig. 259.
 Autun 74.
 Avienus 169.
 Baalbek-Heliopolis, Syria 19, 38-9, 145, 152, 158-66, 169-70; Fig. 278-284, 286-7, 290-1, 295. (Bibl. p.237; Cat. p.279)
 Babylon 131.
 Bacchus 160-1; Fig. 281. See also Dionysus.
 Balanea (Leucas), Syria; (Cat. p.278)
 Balbinus; Fig. 239.
 Bamah 39.
 Baetyl 34, 53, 145, 147-9, 151-2, 169-70; Fig. 39, 266-8, 271. See also Stone.
 Baldachino 19, 21, 65, 123, 144; Fig. 217, 219, 256, 329.
 Bargaia, Caria; (Cat. p.260)
 Baris, Pisidia; (Cat. p.271)
 Bar Kosiba 177, 179; Fig. 306.
 Barrier 145, 152, 177; Fig. 8-9, 262-8, 306, 344, 367.
 Bases, decorated column 19, 127. Fig. 32, 220-4, 229.
 Basilica Aemilia, Rome Fig. 477.

- Baths 11, 12, 60–2; Fig. 114.
 Beacon; Fig. 53.
 Begram, Afghanistan 181; Fig. 315.
 Beisan, Palestine; Fig. 228.
 Bellerophon 80.
 Beroea, Macedonia; Fig. 451 (Cat. p.249)
 Berytus, Phoenicia 40, 181; Fig. 64, 275–6. (Cat. p.280)
 Beule Gate 77.
 Bible see Testament.
 Bithynia 11–2, 14, 36; Fig. 188, 396 (Cat. p.256)
 Bithynium, Bithynia; (Cat. p.256)
 Bizya, Thrace 24, 91; Fig. 24, 497 (Cat. p.247)
 Black Sea 92.
 Blaundus, Lydia; Fig. 365. (Cat. p.260)
 Boaz see Jachin.
 Bostra, Arabia 38, 145; Fig. 257 (Cat. p.284)
 Botrys, Phoenicia (Cat. p.280)
 Bouleuterion; Fig. 474.
 Bridge 47, 91; Fig. 82–4.
 Bronze-Age 147, 149, 151–2, 156.
 Bruzus, Phrygia; (Cat. p.260)
 Buddha 57.
 Building, fortified 181.
 – Public 15, 24; Fig. 26, 517.
 – Round 36, 85, 102; Fig. 19, 45–9, 103, 109, 198–202, 207–8, 329, 471–2.
 – Two storied 26, 219; Fig. 26, 28, 475–7.
 See also Aedicula, Altar, Bouleuterion, Enclosure, Fountain, Heroon, Lighthouse, Sanctuary, Shrine, Temple, Tholos, Tomb, Tower.
 Bura, Peloponnese 17; Fig. 2, 478. (Cat. p.253)
 Buthrotum, Epirus 47; Fig. 80. (Cat. p.250)
 Byblos, Phoenicia 24, 150–3; Fig. 271–3, 375. (Bibl. p.236; Cat. p.280)
 Byzantine 24, 8, 11 6. See also Church.
 Cadi, Phrygia; (Cat. p.260–1)
 Cadmus 33, 156; Fig. 35.
 Caduceus see Altar
 Caesar see Julius
 Caesaraugusta, Spain; (Cat. p.243)
 Caesarea Germanica, Bithynia; Fig. 57, 513. (Cat. p.256)
 Caesarea, Cappadocia 39; Fig. 54, 346, 377–8. (Cat. p.270)
 Caesarea, Mauretania (Cirta) 74; Fig. 128. (Cat. p.244)
 Caesarea Maritima, Samaria 164; Fig. 367. (Cat. p.283)
 Caesarea ad Libanum, Phoenicia; Fig. 14. (Cat. p.280)
 Caesarea Panias, Syria 21; Fig. 10–2, 358; (Cat. p.281–2)
 Calchedon, Bithynia; (Cat. p.257)
 Caligula 85.
 Callatis, Moesia 47; Fig. 88. (Cat. p.245)
 Canopi; Fig. 493
 Capitolas, Decapolis 34, 164; Fig. 285. (Cat. p.282)
 Capitolium see Jupiter Capitolinus
 Carnallia 104; Fig. 1, 6, 8–9, 29, 30, 64, 86, 148, 163, 165, 174, 189, 198, 226, 238, 246, 263, 296–9, 343, 352, 369, 374–8, 383, 389, 398, 434, 439, 448, 454–5, 472, 490, 511, 514, 517, 519.
 Carallia, Cilicia; (Cat. p.275)
 Carallis, Sardinia 66; Fig. 120. (Cat. p.245)
 Caria 24, 5 4; Fig. 90.
 Carrhae, Mesopotamia; Fig. 418 (Cat. p.285)
 Carthago Nova, Spain; (Cat. p.243)
 Caryatid 33, 77, 102; Fig. 13–4, 38, 329, 424.
 Candlestick; Fig. 310
 Cassandra, Macedonia; (Cat. p.249)
 Castor and Pollux 157
 Catacombs, Rome 178–9.
 Cathedral, see Church.
 Cats, sacred; Fig. 489.
 Cave see Grotto.
 Oella, Tripartite 19, 24, 33–4, 64–6, 69, 70, 82, 149, 156–7, 184–5, 207.
 Cenchræae, Peloponnese 82, 85; Fig. 146.
 Ceramus, Caria; (Cat. p.352).
 Ceretapa, Phrygia; (Cat. p.352).
 Chalcis, Euboea 33; Fig. 39. (Cat. p.251)
 Chalcis, Syria 165; Fig. 294, 444. (Cat. p.278)
 Charachmoba, Arabia; (Cat. p.285)
 Choregic monument 78.
 Christ 107, 131, 157.
 Christian architecture 131.
 – Saint 34.
 – Church 71, 123.
 – Byzantine 130.
 – Early Christian 131.
 – Mediaeval 34, 164.
 – Modern 135.
 – Mshabbak; Fig. 230.
 – St. Pantaleon, Cologne 131; Fig. 232.
 – St. Paul-les-Dax, France; Fig. 231.
 – St. Peter's, Rome 131; Fig. 233.
 – Santa Maria Maggiore, Rome 177.
 – Syrian 34.
 Cibra, Phrygia; (Cat. p.261)
 Cicero 66.
 Cidramus, Caria; (Cat. p.261)
 Cilbani, Lydia; (Cat. p.261)
 Circus Maximus, Rome; Fig. 104
 Cirta see Caesarea, Mauretania.
 City View 24, 39, 57, 90–2, 104–5; Fig. 1, 2, 24–5, 56, 159–6, 162, 518, 520.
 Claros, Ionia; Fig. 440.
 Claudius I 99, 227; Fig. 180–1, 516.
 Claudius II Gothicus 105.
 Claudiopolis, Bithynia 12.
 Claudioseleucia, Pisidia; Fig. 428 (Cat. p.272)
 Cleopatra 73–4.
 Cnossus, Crete 24; Fig. 21 (Cat. p.254)
 Codrula, Pisidia; (Cat. p.271)
 Coela, Thrace; (Cat. p.249)
 Colone, Peloponnese; (Cat. p.253)

- Colonnade 19, 24, 85, 99, 107, 122–3, 149, 152, 156, 173–5, 220; Fig. 28, 61, 180–1, 302–3, 359.
See Arcade, Stoa.
- Colophon, Ionia; Fig. 440 (Cat. p.261)
- Colosseum, Rome 24, 60–2, 82; Fig. 110, 114.
- Column 24, 85, 143, 145, 156, 157, 166, 214; Fig. 149, 227, 309, 425, 450–1.
- Colybrassus, Cilicia; Fig. 357 (Cat. p.275)
- Comama, Pisidia; (Cat. p.271)
- Comana 97; Fig. 176, 351, 364. (Cat. p.255)
- Commagene 24
- Commodus; Fig. 36, 46, 54, 60, 141, 147, 186, 240, 262, 336, 401, 405, 442, 446, 450.
- Conana, Pisidia; (Cat. p.271)
- Corcyra; Fig. 400 (Cat. p.250)
- Corinth 24, 27, 39, 40, 44, 61, 66, 79–86; Fig. 113, 135–153, 479. (Bibl. p.232; Cat. p.252)
- Coropissus, Cilicia; (Cat. p.275)
- Cos; (Cat. p.261)
- Court 18, 21, 23–4, 80–1, 123, 131, 133, 135, 143, 145, 147–9, 151–2, 156–7, 160–1, 163, 170.
See also Altar.
- Cremna, Pisidia; Fig. 345. (Cat. p.271)
- Crenellations 34, 53, 61, 147, 177, 181–2, 221, 224.
- Cresilas 139.
- Crete 156; (Cat. p.254)
- Creteia Flaviopolis, Bithynia; (Cat. p.257)
- Creusa 77
- Croesus 127, 140.
- Cromyon, Greece 85–6.
- Curia Julia, Rome 71–4; Fig. 124–5.
- Cult, imperial 74, 82, 93, 109, 115–6; Fig. 3, 23, 30, 128, 143, 159, 198–9, 209, 220, 264, 305, 336, 349, 356, 377–9, 389, 393, 396, 397, 412, 414, 432, 438–9, 446–8, 450–8.
See Neocorate.
- Cybele 123, 140–1; Fig. 366.
- Cyme, Aeolis 24; Fig. 13, 20. (Cat. p.261)
- Cynaetha, Peloponnese 17; Fig. 1. (Cat. p.253)
- Cyprus 33, 137, 139, 143, 145–9; Fig. 255, 266, 369. (Bibl. p.235–6; Cat. p.277)
- Cyrene; (Cat. p.287)
- Cyriac of Ancona 111, 113, 115–6.
- Cyrrhus, Cyrrhastica; (Cat. p.278)
- Cyzicus, Mysia 36, 109–116, 137, 145; Fig. 198–210, 448. (Bibl. p.234; Cat. p.261–2)
- Daldis, Lydia; Fig. 435. (Cat. p.262)
- Damascus, Syria 34; Fig. 43, 413, 433, 452, 467. (Cat. p.279)
- Dardanus, Troas; Fig. 405. (Cat. p.262)
- Datames 53.
- Delphi, Greece 87–9, 145; Fig. 154–8. (Bibl. p.232; Cat. p.250–1)
- Demeter 35, 109–116, 215; Fig. 41, 352, 456, 198–208.
- Demetrius of Ephesus 127.
- Demetrius II, Syria; Fig. 97.
- Dendera, Egypt 160
- Deultum, Thrace; (Cat. p.247–8)
- Diana see Artemis.
- Dido 33; Fig. 34.
- Didyma, Ionia 123, 135; Fig. 239. See Miletus.
- Diocaesarea, Cilicia; Fig. 385, 507. (Cat. p.275)
- Diocaesarea Sepphoris, Galilee; (Cat. p.283)
- Diocletian 74.
- Diomedes 107; Fig. 196.
- Dionysus 75, 77, 78, 104, 157; Fig. 19, 133–4, 341, 354, 380, 383, 403, 439. See also Bacchus.
- Dionysopolis, Moesia; (Cat. p.245)
- Dioscuri 97, 145, 157; Fig. 52, 256.
- Dioshieron, Lydia; (Cat. p.262)
- Diospolis, Samaria; (Cat. p.283)
- Dium, Decapolis 166; Fig. 374. (Cat. p.282)
- Dium, Macedonia; (Cat. p.249)
- Docimeum, Phrygia 24; Fig. 28, 410. (Cat. p.262)
- Dodecanese 53; Fig. 90.
- Dome of the Rock, Jerusalem 177.
- Domitian 66, 87, 89, 135; Fig. 74, 113, 122, 142, 162, 212, 235, 326.
- Dora, Phoenicia; (Cat. p.280)
- Dorylaeum, Phrygia 47; Fig. 78. (Cat. p.262)
- Dura Europos, Mesopotamia 177–9; Fig. 308.
- Dusares 145; Fig. 257, 442.
- Eastern influences 33–4, 151, 156, 164, 179.
- Ebal, Mount 175.
- Edessa, Macedonia; (Cat. p.249)
- Edessa, Mesopotamia; Fig. 347 (Cat. p.285)
- Edfu, Egypt 160.
- Egypt 130, 165, 180–8, 222. See Alexandria.
- Elaea-Sebaste, Cilicia; (Cat. p.277)
- Elagabal 167–70; Fig. 55, 296–9.
- Elagabalus 169; Fig. 11–2, 14, 55, 72–3, 237, 242–4, 276–7, 300, 332, 340, 361, 373, 402–3, 416, 420, 460, 480, 515.
- Eleutheropolis, Judaea; (Cat. p.284)
- Elpis 36; Fig. 47.
- Elst, Netherlands; Fig. 127.
- Emerita, Spain; Fig. 521. (Cat. p.243)
- Emisa, Syria 21, 39, 167–70; Fig. 296–9, 301. (Bibl. p.237; Cat. p.278)
- Enclosure; Fig. 479.
- Ephesus, Ionia 19, 33, 38, 93, 126–32, 139, 141, 147, 160, 166, 170, 177; Fig. 53, 221–224, 229, 243, 412, 438, 459, 518, 520. (Bibl. p.234; Cat. p.262–3)
- and Maenesia; (Cat. p.263)
- and Philadelphia; Fig. 408
- Epidaurus, Peloponnese 36; Fig. 47, 355. (Cat. p.254)
- Epsilon, mystic 89, 145.
- Erechtheum 75–77.
- Erechtheus 7–8.
- Eresus, Lesbos; Fig. 397. (Cat. p.263)
- Erythraea, Ionia; (Cat. p.263)
- Eryx, Sicily 57; Fig. 101.

- Esbous, Arabia; (Cat. p.285)
 Eterna, Pisidia 38; Fig. 52. (Cat. p.271)
 Etruscan ornaments 65–6.
 – Temple 65–6, 70
 Etruscilla; Fig. 234, 261, 360.
 Euboea, Greece 33.
 Eucarpa, Phrygia; (Cat. p.263)
 Eumencia, Phrygia 3; Fig. 32, 423. (Cat. p.263)
 Euphrates River 151.
 Europa 29 See Astarte.
 Eya tree 143.
 Ezekiel 179.

 Faustina I 137, 145; Fig. 48, 155, 210, 264, 380.
 Faustina II 115, 137; Fig. 260, 422, 441.
 Fortuna 19, 35; Fig. 5, 42. See Tyche.
 Forum 24, 71, 74; Fig. 23, 108, 432.
 Fountain 44, 53, 61, 79–82, 85; Fig. 74–7, 91–2, 112–3, 137–141, 488. See Nymphaeum.
 Frontinus 47.

 Gaba, Galilee; (Cat. p.283)
 Gabala, Syria; (Cat. p.243)
 Gadara, Decapolis; (Cat. p.282)
 Gades, Spain; (Cat. p.243)
 Gagae, Lycia; (Cat. p.273)
 Gallery, Gallic 72, 74.
 Gallienus 102, 133; Fig. 27, 63, 82, 190, 211, 213, 295, 329, 338, 393, 449, 464–5, 468, 476, 481, 505.
 Games, Isthmian 82.
 Gangra, Phrygia; Fig. 517. (Cat. p.256)
 Gate 15, 19, 21, 24, 34, 44, 47, 57, 77, 79, 85, 94–100, 102–5, 107, 117–8, 123, 133, 145, 147, 162–65; Fig. 15–7, 26, 34–5, 38, 71, 86–9, 152, 165–74, 182–5, 189, 238, 276, 284–5, 288, 318, 320, 330, 362–4, 374, 384, 449, 496–505, 511–3, 521. See also Arch, Portico.
 Gaul 41, 47, 72, 74
 Gaza; (Cat. p.284)
 Geometric Vase 143, 149; Fig. 255.
 Gerizim, Mount 24, 39, 172–5. See Neapolis, Samaria.
 Germa, Galatia; Fig. 336. (Cat. p.270)
 Germanica see Caesarea Germanica.
 Germanicopolis, Cilicia; (Cat. p.275)
 Germanicus; Fig. 513.
 Germe, Mysia; (Cat. p.263)
 Geta 97, 104; Fig. 2, 49, 61, 88, 145, 149, 168, 170–1, 189, 353, 390, 443, 484, 499.
 Glass 179, 181; Fig. 309, 315.
 Glycon 118.
 Gordian I; Fig. 239.
 Gordian II; Fig. 239.
 Gordian III; Fig. 5, 17–8, 20, 25, 34, 53, 175, 236, 265, 333, 345, 424, 435, 499, 501, 504, 520.
 Goths 24, 105.
 Gothic Cathedral 75
 Graffito see Inscription.

 Gravestone 114. See Relief, Stele. Fig. 494.
 Griffin; Fig. 494.
 Grotto, Corinth 79, 80; Fig. 135.
 – Heracles 17; Fig. 2.
 – Our Lady of the Cavern 78; Fig. 133.
 – Pan 20–1, 78; Fig. 11–2.
 – River God; Fig. 433.
 Grove, sacred 27.
 Grynium, Acolis; Fig. 386.
 Gymnasium 11–3, 24, 99; Fig. 20.
 Gytheion, Peloponnese 19; Fig. 4. (Cat. p.253)

 Hadad 53; Fig. 95, 293, 419, 463. See Jupiter Heliopolitanus.
 Hades 116, 183.
 Hadrian 89, 109–16, 137, 173, 175, 177, 179; Fig. 15–6, 31–2, 76, 152, 157, 199, 201, 209, 224, 243, 312, 342, 396, 426, 455, 492–4, 509.
 Hadrianopolis, Phrygia 21; Fig. 15, 42. (Cat. p.263)
 Halicarnassus, Caria 38. (Cat. p.263)
 Harbour 24, 40, 56, 57, 82, 85; Fig. 57–62, 146, 480–484 (Bibl. p.230)
 Harpasa, Caria; (Cat. p.263)
 Harpocrates 183, 185. See Serapis.
 Harpocrates of Mendes Fig. 482
 Haterii Sarcophagus Fig. 111, 219.
 Hebrews see Jews.
 Hector 107; Fig. 194.
 Helioabalus see Elagabal.
 Heliopolis, Syria see Baalbek.
 Helios 85, 160, 183, 185; Fig. 163, 444.
 Heliosciros (Helios Hieros) 166; Fig. 294.
 Hephaestus 147.
 Hera 133–5; Fig. 235. See Juno
 Heraclea ad Latmum, Ionia Fig. 343. (Cat. p.263)
 Heraclea Pontica, Bithynia 40; Fig. 7, 63, 473. (Cat. p.257)
 Heraclea Salbace, Caria (Cat. p.264)
 Heracleopolis, Bithynia see Sebastopolis.
 Heracleopolite Rome, Egypt; Fig. 510. (Cat. p.287)
 Heracles 17–19, 44, 139–45, 212, 226; Fig. 2, 8–9, 75, 245–6, 247B, 249–50, 252–3, 262, 443, 510, 512. See Melqart.
 Heraeum see Argive, Samos.
 Hercules see Heracles.
 Herm 116; Fig. 210, 425, 495.
 Hermes 82, 109, 116. See also Mercury.
 Hermocreon 53, 118.
 Hermopolite Nome, Egypt (Cat. p.287)
 Hero 33; Fig. 36.
 Herod Philip I; Fig. 358.
 Herod The Great, 177, 179.
 Heron 24, 36, 85; Fig. 28, 48, 153.
 Herostratus 127
 Hierapolis, Cilicia (Cat. p.276)
 Hierapolis, Phrygia; Fig. 371, 389, 403. (Cat. p.264)
 Hierocaesarea, Lydia; (Cat. p.264)
 Hieropolis Bambyce, Syria 53; Fig. 95, 293. (Cat. p.278)

- 'High Places' 39, 161.
 Himera, Sicily 53; Fig. 91. (Cat. p.244)
 Hiram 156, 177.
 Hispania (Citerior: Ulterior) see Spain.
 Hissarlik, Troy 108
 Hittite Art 123, 141.
 - Sculptures 53
 - Sources 143
 Homer 107, 147.
 Homeric Age 108, 147.
 Horned Altar, see Semitic
 Horus 183.
 Hypaepa, Lydia; Fig. 382. (Cat. p.264)
 Hypsas; Fig. 437.

 Iasus, Caria; (Cat. p.264)
 Ilici, Spain 33; Fig. 37. (Cat. p.243)
 Ilium, See Troy.
 India, North 57; Fig. 99. (Cat. p.286)
 Inscription Alexandria 183.
 - Ephesus 130.
 - Hittite 143.
 - Jerusalem 177.
 - Lydian 141.
 - Nicaea 105; Fig. 192.
 Iole 140.
 Ionian Cities, see League.
 Iphitus 140.
 Iranian Art 123.
 - Influence 97.
 Iris River 91.
 Isaura; Fig.502. (Cat. p.273)
 Isinda, Pisidia; (Cat. p.271)
 Isis 183, 185; Fig. 491, 509. see also Serapis.
 Isis, Pharia 82; Fig. 53, 146.
 Islam 34
 Islamic, Shrine, see Shrine.
 Israelites 175.
 Isthmian, see Games.
 Isthmus 82.
 Italy 53, See also Rome.

 Jachin and Boaz 145, 156.
 Janus 61; Fig. 106, 112.
 Jehovah 33, 145, 156, 157, 173, 176-197; Fig. 306.
 Jerusalem, Judaea, Palestine 33, 145, 156, 157, 173,
 176-179; Fig. 306, 1-31 (Bibl. 237; Cat. p.284).
 Jews 176-179.
 Joshua 175.
 Juba I 38, 74; Fig. 38, 508.
 Juba II 73, 74; Fig. 128.
 Judaea, see Jerusalem.
 Julia Domna; Fig. 9, 59, 301, 392, 404, 425, 436, 469
 Julia Ipsi, Phrygia; (Cat. p.264)
 Julia Maesa; Fig. 10, 461.
 Julia Mamaea; Fig. 331

 Julian the Apostate 183
 Julipolis, Bithynia; (Cat. p.257)
 Julius Caesar 71, 73-4, 79
 Juno 33; Fig. 37. See also Hera
 Jupiter Capitolinus 33, 63-6, 69, 70, 82; Fig. 115-9,
 121-3, 142, 312
 - Heliopolitanus 158-66, 169, 171; Fig. 278-281,
 286-7, 290-1
 - Pluvius; Fig. 518

 Ka'ba 151.
 Kasr Fira un, see Petra.
 Kom Ombo, Egypt 185.
 Kore 109-116, 137.

 Labyrinth 24; Fig. 21.
 Laïs 85; Fig.149.
 Lamp 181; Fig. 314.
 Lampsacus, Mysia; Fig.372. (Cat. p.264)
 Lamos, Cilicia; (Cat. p.276)
 Laodicea ad Lycum, Phrygia, 24, 31, 130; Fig. 23,
 226. (Cat. p.264-5).
 Laodicea ad Mare, Syria 40; Fig. 65, 469. (Cat.
 p.278-9)
 Lascuta, Spain; (Cat. p.243)
 League of Ionian Cities 137; Fig. 241. (Cat. p.258)
 Leander 33; Fig. 36
 Lebanon 169.
 Lechaum 82, 84-86; Fig. 147
 Lemnos 147; Fig. 270.
 Leptis Magna, Africa 123, 188; Fig. 220, 324.
 Lesbos; Fig. 397. (Cat. p.265)
 Leto; Fig. 27.
 Lighthouse 40, 42, 85, 181; Fig. 63-67, 147. See also
 Pharos, Tower.
 Livia; Fig. 143.
 Lucian 151, 156.
 Lucius Ampelius 122
 Lucius Verus; Fig. 288, 318, 334, 354, 418, 479.
 Luna; Fig. 345. See Men.
 Lydia 140, 141.
 Lygos tree 133-135
 Lybe, Cilicia; (Cat. p.276)
 Lysinia, Pisidia; (Cat. p.271)

 Ma (Ma-Enyo, Ma-Zeus) 21, 94-98, 192; Fig. 177,
 351, 165-174, 176.
 Macedonia; Fig. 451, 458, 522.
 Maecellum, Rome; Fig. 102.
 Macrinus; Fig. 271, 381, 395, 410, 415, 438, 463.
 Maeander River; Fig. 82.
 Maeonia, Lydia; (Cat. p.265)
 Magna Mater 97, 141, 156.
 Magnesia ad Macandrum, Ionia, 38, 130, 166; Fig.
 225. (Cat. p.265)
 Magnesia ad Sipylum, Lydia; (Cat. p.265)
 Mainz; Fig. 289

- Malaca, Spain; (Cat. p.244)
 Malalas 116, 117.
 Mallus, Cilicia; (Cat. p.276)
 Manuscript of Cyriae of Ancona 111, 113, 116.; Fig. 204, 209.
 Marcianopolis, Moesia 24.; Fig. 25, 85, 499, 501. (Cat. p.245)
 Marcus Aurelius 65, 107, 223.; Fig. 118, 135, 150, 195, 285, 292, 388, 496.
 Mari, Mesopotamia 143, 151, 152; Fig. 254, 273.
 Maronea, Thrace; Fig. 383. (Cat. p.248)
 Mars Ultor 33; Fig. 109.
 Marsyas 155–157; Fig. 275–277, 433.
 Mattatiah Antigonos 179; Fig. 310.
 Mauretania, North Africa 38, 73, 74; Fig. 38, 128, 508. See also Caesarea (Cirta)
 Mausoleum 38.
 Maximinus I; Fig. 187.
 Maximus 209; Fig. 221, 429–31, 500
 Mecca 151.
 Mediterranean, 53.
 Medusa 127.
 Megara, Greece 34; Fig. 41, 482, 495. (Cat. p.251)
 Melicertes 85, Fig. 150–1
 Melqart 156; Fig. 415.
 Men. 145; Fig. 265, 388, 399.
 Mendes, Egypt; Fig. 492.
 Menelaite Nome, Egypt; (Cat. p.287)
 Mercury; Fig. 391.
 Mercury-Simios 39, 159, 161; Fig. 282.
 Mesopotamia 24, 34, 143, 151, 152, 164.
 Mesopotamian Art 123.– Origins 131.
 – Symmetry 143.
 Messalina; Fig. 182–3.
 Meta Sudans 44, 60–62, 82; Fig. 76, 110, 112–3.
 Metropolis, Ionia; Fig. 370. (Cat. p.265)
 Metropolis, Phrygia; (Cat. p.265)
 Midaceum, Phrygia; (Cat. 265)
 Mihrab 34.
 Miletus, Ionia, 135; Fig. 239. (Cat. p.265–6)
 Minerva see Jupiter Capitulinus
 Minoan Documents 147.
 Minos 156.
 Mithradates 192.
 Model of Building 130, 140, 141, 147, 149, 181; Fig. 207, 227, 228, 250, 251, 270, 314.
 Mopsus, Cilicia 47; Fig. 83. (Cat. p.276)
 Mosaic 181, 187, 188; Fig. 316, 324.
 Mosque, Damascus 34.
 – Jerusalem 177
 – Mecca 151.
 Mothone, Peloponnese; Fig. 484. (Cat. p.253)
 Mountain, Sacred 39, 57, 173–175. See Argæus, Ebal, Gerizim.
 Mshabbak, Syria 130; Fig. 230.
 Mycenaean, Documents 147, 148.
 Mylasa, Caria; Fig. 332, 353. (Cat. p.266)
 Myra, Lycia; Fig. 333. (Cat. p.273)
 Myrina, Aeolis, Asia; Fig. 386. (Cat. p.266)
 Mysteries, 109, 111, 115–6, 137, 145, 160, 183.
 Mytilene, Lesbos; (Cat. p.266)
 Nacrassa, Lydia; (Cat. p.266)
 Naiskos, see Aedicula
 Neapolis, Ionia; (Cat. p.266)
 Neapolis, Samaria, Palestine 39, 165, 172–175.; Fig. 55, 292, 302, 303, 422. (Bibl. p.237; Cat. p.283)
 Nefer-Seschem-Ptah 183–185.
 Neocaesarea, Pontus, 21, 44, 94–98, 123; Fig. 71, 165–175, 178, 179, 414. (Bibl. p.233; Cat. p.255)
 Neoclandiopolis, Paphlagonia; (Cat. p.256)
 Neocorate (Neocoros) Title 19, 27, 91, 93, 96–99, 137, 175, 211, 213–215; Fig. 3, 30, 44, 178, 179, 242, 243, 305, 328, 349, 377, 378, 379, 390, 412, 414, 438, 439, 446–448, 450, 451, 454–458.
 Neptune; Fig. 409.
 Nero 33, 47, 198, 205; Fig. 33, 80, 102, 105–7, 379, 412.
 Nerva; Fig. 13
 Nesibis, Mesopotamia; Fig. 417. (Cat. p.285)
 Nicaea, Bithynia 11, 12, 99–105; Fig. 180, 183, 185–192, 496. (Bibl. p.233; Cat. p.257).
 Nicomedeia, Bithynia 11; Fig. 390, 446, 456, 457. (Cat. p.257–8).
 Nicopolis, Epirus 36, 61; Fig. 48, 76. (Cat. p.250)
 Nicopolis, Judaea; (Cat. p.284)
 Nicopolis ad Istrum, Moesia 24, 44; Fig. 26, 70, 402. (Cat. p.246)
 Nicopolis, Syria; (Cat. p.279)
 Nike 143; Fig. 92. See also Victory
 Nile 186–188.
 Nilometer 186–188; Fig. 321–325.
 Ninica, Cilicia; (Cat. p.276)
 Nini-Zaza 151, 152.
 Nymphaeum 43, 44, 49; Fig. 68, 73. (Bibl. p.231)
 Nysa, Lydia, Asia 166; Fig. 388, 476. (Cat. p.266)
 Nysa-Skythopolis, Samaria; (Cat. p.283)
 Obelisks, temple of Byblos, 151; Fig. 272.
 Oceanus; Fig. 483.
 Octavia 82.
 Odessus, Moesia; Fig. 5 (Cat. p.246)
 Odysseus 107.
 Olba, Cilicia; Fig. 487 (Cat. p.276)
 Olbasa, Pisidia; (Cat. p.272)
 Omphale 140; Fig. 248.
 Ophiogeneis 118.
 Oppian Hill 61.
 Oracular cult 145.
 Oriental see Eastern.
 Orthosia, Phoenicia; Fig. 376. (Cat. p.280)
 Osiris 183.
 Otacilia Severa; Fig. 19, 413, 433, 507.
 Pactolus River 141.

- Paestum Italy; Fig. 475. (Cat. p.244)
 Papae, Greece 6; Fig. 498, 512. (Cat. p.251)
 Painting 27, 143, 177–179; Fig. 227, 254–5, 308.
 Palace 91.
 Palestine 33, 39, 130, 145, 156, 157, 164–166, 172–179.
 Palicanus 57.
 Palladio 61.
 Palladion 106–108.
 Palmette; Fig. 90.
 Paltus, Syria; Fig. 462. (Cat. p.279)
 Pan 20, 21, 78; Fig. 10–12.
 Panathenaic Way 77.
 Panormus, Italy 40; Fig. 67. (Cat. p.245)
 Panticapaeum, Bosphorus; (Cat. p.245)
 Paphos, Cyprus, see Cyprus.
 Paris of Troy 118.
 Parium, Mysia, Asia 38, 53, 117, 118, 152; Fig. 98, 211, 213–216. (Bibl. p.234; Cat. p.266).
 Parius 117, 118; Fig. 214–5.
 Parotids 19, 32; Fig. 3, 164, 326.
 Parthenon 75, 77, 78; Fig. 129.
 Parthia; (Cat. p.285–6)
 Patara, Lycia; Fig. 424. (Cat. p.273)
 Patras, Peloponnese 40, 44; Fig. 60, 61, 74, 392. (Cat. p.253)
 Pausanias 17, 79, 82, 85.
 Pautalia, Thrace 27, 39; Fig. 29, 434. (Cat. p.248)
 Pednelissus, Pisidia; (Cat. p.272)
 Pegasus 80; Fig. 136
 Peirene 44, 79–81, 85; Fig. 138–140.
 Pella, Macedonia; Fig. 522. (Cat. p.249)
 Pella, Syria 39, 44, 175; Fig. 56, 72. (Cat. p.282)
 Peltae, Phrygia; (Cat. p.266)
 Perga, Pamphylia 141; Fig. 334, 338, 344. (Cat. p.274)
 Pergamum, Mysia, Asia 19, 21, 32–33, 39, 93, 99, 122–125, 139, 149, 152, 175; Fig. 3, 30, 109, 184, 217, 218, 268, 305, 327, 337, 349, 439, 450, 454. (Bibl. p.234; Cat. p.266–7)
 Perinthus, Thrace 34; Fig. 44. (Cat. p.248)
 Persephone, see Kore.
 Persepolis 38.
 Persia 113.
 Persian Destruction 75.
 Persis 38, 113; Fig. 50, 51. (Cat. p.286)
 Perspective 15, 21–26, 57, 156.
 Pescennius Niger 40; Fig. 57.
 Pessinus, Galatia; (Cat. p.270)
 Petra, Arabia 155, 156; Fig. 274. (Cat. p.285)
 Phaethon 85.
 Pharaohs 181.
 Pharnaces I; Fig. 177.
 Pharos, Alexandria 40, 180–182; Fig. 313–317.
 Pheidias 77, 139.
 Phigaleia, Peloponnese; (Cat. p.254)
 Philadelphia, Arabia; (Cat. p.285)
 Philadelphia, Cilicia; (Cat. p.276)
 Philadelphia Lydia; (Cat. p.267)
 – and Ephesus; Fig. 408. (Cat. p.267)
 Philip I; Fig. 7, 24, 245, 282, 284, 290, 365, 371–2, 417, 423, 452.
 Philip II, Fig. 22, 467.
 Philipopolis, Thrace; Fig. 416. (Cat. p.248)
 Philomelium, Asia 24, 36; Fig. 19, 387. (Cat. p.267)
 Phoenician, Architecture 33, 145, 156, 157, 177.
 – Queen 29.
 – Religion 157.
 – Triad of Deities 156.
 – West (Punic) 149.
 Phradmon 139.
 Pionia, Mysia; (Cat. p.267)
 Plaque 147; Fig. 267, 269.
 Plautilla; Fig. 144, 400.
 Pliny the Younger 11, 12, 99..
 Plinty The Elder 127, 130.
 Pogia, Pisidia; (Cat. 272)
 Pollux, see Castor.
 Polycleitus 139.
 Pompeiopolis, see Soli.
 Pontus 95, 97; (Cat. p.254)
 – Kings 91–93, 97; Fig. 177.
 Portal, Sacred 33, 38, 113.
 Portico 43, 60–62, 67, 122–124, 152, 183; Fig. 478, 508. See also Gate, Stoa.
 Poseidon 82, 133; Fig. 141, 145.
 Pre-Hellenic Architecture 145.
 – Cult 147.
 – Deities 143.
 – Prototypes 137.
 – Sanctuary 142–145.
 Priapus; Fig. 372.
 Priene 139.
 Prima Porta, Type 99.
 Propylaeum 75–78; Fig. 129–131, 514. See also Gate, Portico.
 Prostanna, Pisidia; (Cat. p.272)
 Prusa ad Olympum, Bithynia 36; Fig. 49. (Cat. p.258)
 Prusias ad Hypium, Bithynia; Fig. 505. (Cat. p.258)
 Prymnessus, Phrygia; (Cat. p.267)
 Ptolemais, see Ake –
 Ptolemies 183.
 Ptolemy II 181.
 Punic inscription; Fig. 335.
 Puteal, see Altar
 Pylon 181; Fig. 509.
 Pyramidal Structure 53; Fig. 97.
 Pyramus River; Fig. 82.
 Pyre 38. See also Tomb.
 Qasr-el-Lebia, Cyrene 181; Fig. 316.
 Rabbathmoda, Arabia 166; Fig. 419. (Cat. p.285)
 Relief sculpture
 – Arch of Callatis; Fig. 88.
 – Arch of Nero; Fig. 33, 107.

- Arch of Titus; Fig. 307.
- British Museum 127; Fig. 206, 223, 289.
- Conservatori, Palazzo dei 70; Fig. 118.
- Jupiter Heliopolitanus; Fig. 291.
- Louvre; Fig. 207.
- Pergamon Museum, Berlin 123; Fig. 218.
- St. Paul-les-Dax, France 131; Fig. 231.
- Samothrace 111, 113; Fig. 203.
- Saqqara 130, 185; Fig. 320.
- Sardis 138-41; Fig. 244-5, 250-1.
- Tabula Iliaca 107-8; Fig. 197.
- Temple of Artemis Ephesia see bases, decorated column.
- Tomb of the Haterii see Haterii.
- Renaissance 61, 107.
- Rhaktis, Alexandria 181.
- Rhesaena, Mesopotamia; (Cat. p.285)
- River see Hypsas, Iris, Maeander, Nile, Pactolus, Pyramus, Tiber.
- Roof 78, 127, 135, 147, 156.
- Conical; Fig. 49, 470.
- Decorations 65, 89, 99, 113; Fig. 116, 155.
- Domed 36-7, 57, 113, 115; Fig. 45, 208.
- Flat 33-4, 38, 53, 113, 160, 177, 216; Fig. 39, 40, 50-1, 96, 488.
- Tiles 85.
- See Crenellations.
- Roma; Fig. 7, 368, 455.
- and Augustus 78; Fig. 349.
- Romanesque architecture 34.
- Rome 11-2, 24, 33, 38, 43, 47, 56-66, 67, 69-75, 82, 99, 117, 125, 160, 169, 170, 176-9, 183; Fig. 68, 79, 84, 100-125, 212, 219, 233, 264, 300, 307, 309, 409, 432, 477, 506. (Bibl. p.231-2)
- Rostra, Rome 57; Fig. 100.
- Round see Building.
- Sabratha, Africa; Fig. 421. (Cat. p.244)
- Sagalassus, Pisidia 38, 145; Fig. 256, 360, 394. (Cat. p.272)
- St. Ouen de Thouberville, France 74; Fig. 126.
- St. Pantaleon, Cologne 131; Fig. 232.
- St. Paul 122, 127.
- St. Paul-les-Dax, France; Fig. 231.
- St. Peter's, Rome 131; Fig. 233.
- Saitta, Lydia; (Cat. p.268)
- Salonina; Fig. 470.
- Saloninus; Fig. 357.
- Samaritans 173.
- Samos, Ionia 133-5; Fig. 234-6. (Bibl. p.234-5; Cat. p.268)
- Samosata, Commagene; (Cat. p.278)
- Samothrace 36, 111-6; Fig. 203-5.
- Sanaballet 173.
- Sanctuary 17, 19, 21, 27, 36, 38-9, 54, 76-9, 82, 87, 92, 93, 105, 107, 148, 150-2, 181.
- See also Aphrodite, Apollo, Asclepius, Astarte-Europa, Athena, Demeter, Cella, Dioscuri, Gerizim, Hera, Heracles, Hypsas, Isis, Jupiter Heliopolitanus, Ma, Mercury, Mountain, Nini-Zaza, Pan, Parus, Serapis, Tyche, Zeus.
- Sandan 53; Fig. 97.
- Saqqara, Egypt 130, 184-5.
- Sarcophagus see Haterii.
- Sardinia 66; Fig. 120.
- Sardis, Lydia 33, 49, 93, 136-41, 149; Fig. 31, 240-2, 244-51, 328, 380, 519. (Bibl. p.235; Cat. p.268)
- Satan 122.
- Scabbard 164; Fig. 289.
- Scaean Gate 107.
- Schliemann 108.
- Sculpture see relief.
- Scylla 80-1.
- Seal, Akkadian 145; Fig. 258.
- Sealstone 107; Fig. 194.
- Sebaste, Samaria; (Cat. p.283)
- Sebastopolis-Heracleopolis, Pontus 18-9, 145; Fig. 8-9, 443. (Cat. p.255)
- Selene 156.
- Seleucia ad Calycadnum, Cilicia; (Cat. p.276)
- Seleucia, Pisidia see Claudiosseleucia.
- Seleucia Pieria, Syria; Fig. 445. (Cat. p.279)
- Selge, Pisidia 38, 142-5, 179; Fig. 252-3, 259-62. (Bibl. p.235; Cat. p.272)
- Selinus, Cilicia; (Cat. p.276)
- Selinus, Sicily; Fig. 437. (Cat. p.245)
- Semitic Altar Court 34.
- Architecture 161, 166.
- Horned Altar 21, 33, 38, 150-3, 156, 173-5; Fig. 38, 51, 271, 276, 302-3.
- Sacred Arcas 151.
- Sacred stone 169.
- Sanctuary 157, 159-60.
- Septimius Severus 49, 97, 99, 104, 122; Fig. 4, 26, 41, 52, 64, 69, 70, 75, 87, 136, 138-139A, 151, 153, 156, 166-7, 169, 172-3, 189, 217, 266, 278, 280, 328, 364, 370, 384-6, 411, 419, 462, 469, 478, 486, 498, 502, 512.
- Serapeum, Alexandria 183-5, 187, 191.
- Serapis 183-5; Fig. 318, 348, 381, 402.
- Serdica, Thrace; (Cat. p.248-9)
- Sestus, Thrace 33; Fig. 36. (Cat. p.249)
- Severi 9, 123, 125.
- Severus Alexander see Alexander.
- Shrine, Egyptian 183. See Canopi, Cats, Griffin, Harpocrates of Mendes, Heracles, Isis.
- Islamic 151.
- Our Lady, Athens 78.
- Portable 34, 177, 185; Fig. 40, 42, 295, 462-470. (Bibl. p.230)
- Processional 34, 39, 170, 177, 183, 185; Fig. 41, 55, 300, 319, 459-61.
- Torah 177-9; Fig. 308-9.
- Tripartite see Cella.
- See also Aedicula, Altar, Grotto, Temple, Tower.

- Sibidunda, Phrygia; (Cat. p.268)
 Sicily 40, 53, 57, 211; (Cat. p.244-5)
 Sicyon, Peloponnese; Fig. 425. (Cat. p.252)
 Side, Pamphylia 36; Fig. 407, 453, 470, 481, 503. (Cat. p.274)
 Sidon, Phoenicia 24, 53, 57, 145, 149, 155-57; Fig. 93, 277, 359, 361, 460. (Bibl. p.236; Cat. p.281)
 Silandus, Lydia; Fig. 354. (Cat. p.268)
 Silenus 53-5, 157.
 Simios-Mercury see Mercury.
 Sinope, Paphlagonia; (Cat. p.256)
 Sivadasa; Fig. 99.
 Smyrna, Ionia 32; Fig. 326, 455. (Cat. p.268-9)
 Soli-Pompeiiopolis, Cilicia; Fig. 483. (Cat. p.276)
 Solomon 145, 156, 159, 177.
 Sostratos 181.
 Spain 30, 3; Fig. 37, 335, 521.
 Sphinx 113; Fig. 206.
 Stadium 82; Fig. 473.
 Stairway 19, 33, 34, 40-2, 76-8, 80-1, 85, 99, 100, 113, 117, 122-6, 130, 143, 145, 152, 159-62, 173-5, 177, 180-1, 197, 225.
 Star and snakes 145; Fig. 260.
 Stele 111-4, 186-8; Fig. 203-4, 320, 348.
 Steps see Stairway.
 Stoa 17, 19, 24, 85; Fig. 148. See also Arcade, Colonnade, Portico.
 Stobi, Macedonia; (Cat. p.249)
 Stone, sacred 24, 34, 39, 53, 151, 167-70. See Baetyl, Obelisk.
 Strabo 91-2, 118.
 Stupa of Buddha 57; Fig. 99.
 Styx tree 143, 145.
 Sulla 57.
 Summanus 66.
 Synagogue 177-8.
 Synnada, Phrygia; (Cat. p.269)
 Syrian 157, 169.
 - Arch 19, 163-4. See arched lintel.
 Tabula Iliaca 107-8; Fig. 197.
 Tacitus (Emperor); Fig. 344.
 Tamburlane the Great 159.
 Tanagra, Greece; Fig. 341, 427. (Cat. p.251)
 Tanit 66; Fig. 120. See also Venus.
 Tapestry 188; Fig. 325.
 Tarentum, Italy (Cat. p.244)
 Tarraco, Spain; (Cat. p.243)
 Tarsus, Cilicia 53, 177; Fig. 94, 96-7, 511. (Cat. p.277)
 Tavium, Galatia; (Cat. p.270)
 Taxila, India; (Cat. p.286)
 Telesphorus; Fig. 337.
 Tenos; (Cat. p.254)
 Temple identified by architectural form:
 - Distyle; Fig. 6, 23, 39, 95-6, 259, 331. See also Aedicula, Temple multiple types.
 - Tetrastyle; Fig. 3-4, 27, 37, 43, 54, 117, 120, 122, 142, 144, 164-72, 174-6, 186, 210, 224, 235, 263, 275, 306, 311-2, 318, 349-70, 376-7, 422. See also Aedicula, Gate, Temple multiple types.
 - Pentastyle; Fig. 173, 421.
 - Hexastyle; Fig. 7, 32, 115-6, 123, 143, 156, 195, 226, 237-8, 241, 264-5, 296-8, 327, 371-5, 378-87, 423. See also Temple multiple types.
 - Octastyle; Fig. 221, 229, 326, 390-6.
 - Decastyle; Fig. 280.
 - Hendecastyle; Fig. 397.
 - Prostyle; Fig. 404, 409, 411.
 - Round See Building, round.
 - Three-quarter view 24; Fig. 145, 148, 155, 187, 278, 282, 299, 398-416. See also Temple multiple types.
 Temple multiple types:
 - Two temples 49; Fig. 44, 179, 281, 328, 446-51.
 - Three temples; Fig. 30, 60, 452-57.
 - Four temples 137; Fig. 242-3, 458.
 - Five temples; Fig. 29.
 For temples identified by deities see names of deities.
 For temples of the imperial cult see Cult, imperial.
 See also Acropolis, Aedicula Cella tripartite, City view, Forum, Harbour, Stadium.
 Teos, Ionia; Fig. 356. (Cat. p.269)
 Terina, Italy 53; Fig. 92. (Cat. p.244)
 Termessus, Pisidia; (Cat. p.272)
 Testament, Old 24, 39, 145, 161, 175, 177
 - New 122.
 Thapsus, Africa 74.
 Theatre 11, 12, 75, 77-8; Fig. 133, 134. See Amphitheatre, stadium.
 Thebes, Greece 29, 33.
 Thera; (Cat. p.254)
 Thessalonica, Macedonia; Fig. 458. (Cat. p.250)
 Tholos 36.
 Thrasyllus 78.
 Thyateira, Lydia; Fig. 368; (Cat. p.269)
 Thymiaterrion (Incense altars) 147, 149.
 Tiber River 46-8.
 Tiberias, Galilee; (Cat. p.283)
 Tiberiopolis, Phrygia; (Cat. p.269)
 Tiberius; Fig. 455, 521.
 Timbrada, Pisidia; (Cat. p.272)
 Titiopolis, Cilicia; (Cat. p.277)
 Titus 60-2, 66, 176-179; Fig. 110, 112
 Tityassus, Pisidia; (Cat. p.272)
 Tium, Bithynia; (Cat. p.258)
 Token, lead 40; Fig. 58.
 Tomb (including Tomb/Altar Shrine)
 - Building H, Xanthos 33, 113; Fig. 206.
 - Lais 85; Fig. 149.
 - Mausoleum of Halicarnassus 38.
 - Melicertes 85; Fig. 150-1.
 - Mithradates I 92; Fig. 161
 - Nefer-Seschem-Ptah 130, 185; Fig. 320.
 - Parius 38, 117-8, 121, 152; Fig. 214-5.

– Pontic Kings 91–3.
 Tomi, Moesia; Fig. 500. (Cat. p.246)
 Topirus, Thrace; Fig. 471–2. (Cat. p.249)
 Topography 27–9.
 Torah Shrine 177–9; Fig. 308–9.
 Tower Eiffel 181
 Tower 24, 29, 33–4, 38, 40, 42, 47, 52, 53, 91–2, 104, 147, 163–4, 221, 224, 227; Fig. 67, 485–7, 517.
 Trajan 11, 19, 194; Fig. 3, 30, 33, 79, 84, 89, 104, 108, 164, 176, 188, 225, 294, 305, 322, 346, 399, 432, 444–5, 450, 454, 488–9, 491, 506.
 Trajan Decius; Fig. 66, 257, 382, 408, 485.
 Tralles, Lydia; Fig. 391, 447. (Cat. p.269)
 Tranquillina; Fig. 428.
 Trebonianus Gallus; Fig. 42, 453.
 Tree, Sacred 27, 93, 133, 135, 143; Fig. 163, 236–7, 252–5.
 Triad of Deities 19, 33, 65, 159–161, 183, 185.
 Tripartite see Cella.
 Tripolis, Lydia; (Cat. p.269)
 Tripolis, Phoenicia 133; Fig. 238, 420. (Cat. p.281)
 Triton 80, 82, 85.
 Triumphal Arch see Arch.
 Troezen, Peloponnese 36, 44.; Fig. 46, 75. (Cat. p.254)
 Troy 106–8, 118, 137; Fig. 193, 195. (Bibl. p.233; Cat. p.264)
 Trulla 186–8; Fig. 323.
 Turris Libisonis, Sardinia; (Cat. p.245)
 Tyche; Fig. 6, 16, 42–3, 71, 336, 339, 340, 343, 360, 369, 417, 452, 496. See also Astarte, Fortuna.
 Tyre, Phoenicia 102, 133, 156; Fig. 34, 40, 237, 329, 373, 415, 464–5, 468. (Cat. p.281)

Uranus Antoninus, Sulpicius 170.
 Uruk, Mesopotamia 131.

Valerian; Fig. 83, 256, 281, 406–7, 457, 503.
 Varius Avitus 169. See Elagabalus
 Vase, Geometric 143, 149; Fig. 255..
 – See glass
 Venus 57; Fig. 101.
 – Tanit 66, 69; Fig. 120.
 See also Atargatis-Venus
 Verus, see Lucius Verus
 Vespasian 70; Fig. 115–6, 123.
 Vesta 58; Fig. 103.
 Victory 73, 74. See also Nike
 Vienne, Gaul 40; Fig. 62. (Cat. p.244)
 Villa of The Nile, Leptis 188; Fig. 324.
 Vitruvius 65, 135.
 Volteius 65, 66.
 Volusian 202; Fig. 40, 394.

Walls, City 15, 24, 33, 53–57, 90–93, 104–105, 05, 108, 181; Fig. 24–5, 93, 183, 190, 194, 197, 97, 513, 519, 521, 522.

Wharves, see Harbour
 Window 47, 74, 113, 115, 147, 181, 183, 185; Fig. 89, 228, 232, 266, 315, 318, 475, 509, 517
 – in pediment 19, 34, 99, 127–131, 159–60, 165–6, 169–70; Fig. 189, 221–2, 224–232, 280, 297, 299.

Wonders of The World 122, 127.

Xanthos 34, 113, 149; Fig. 206.

Zacynthus, Peloponnese; (Cat. p.253)
 Zela, Pontus 39, 102, 145, 175; Fig. 263, 304, 30, 362–3, 384, 514. (Cat. p. 256)
 Zeugma, Commagene, Syria 24, 39; Fig. 22. (Cat. p.278)
 Zeus 97, 99, 107, 118, 122–4, 156, 164, 185; Fig. 175, 188, 217–8, 285, 426, 436, 447, 516.
 – Hades 183.
 – Hagios 133; Fig. 238.
 – Helios–Serapis 183, 185.
 – and Heracles 142–145.
 – Hypsistos 165, 172–175; Fig. 292, 302, 303.
 – Kasios; Fig. 445.
 – Katabaites 24, 39; Fig. 22.
 – Labraundcus; Fig. 353.
 – Litalos 99.
 – Lydios 137–141; Fig. 247A
 – Olympios 139.
 – Osogoa; Fig. 332.
 – Philios and Trajan 19, 175; Fig. 3, 305.
 – Poleus 139
 – Stratios 21, 90–93; Fig. 164
 See also Jupiter, Hadad, Ma, Serapis
 Ziggurat 39, 166, 170, 175.